

APPENDIX C
SIMPLIFIED DRAINAGE REQUIREMENTS

CITY OF RENTON
SURFACE WATER
DESIGN MANUAL

December 1, 2016 DRAFT

APPENDIX C

SIMPLIFIED DRAINAGE REQUIREMENTS



CITY OF RENTON

SURFACE WATER DESIGN MANUAL

Section	Page
C.1 Simplified Drainage Review Requirements	C-7
C.1.1 Procedure for Determining Requirements	C-8
C.1.2 Targeted Drainage Review Requirements	C-13
C.1.3 Application of On-site BMPs	C-16
C.1.4 Application of CSWPP Measures	C-24
C.1.5 Simplified Submittal Requirements	C-28
C.2 On-Site BMPs	C-29
C.2.1 Full Dispersion	C-29
C.2.2 Full Infiltration	C-44
C.2.3 Limited Infiltration	C-53
C.2.4 Basic Dispersion	C-54
C.2.5 Farmland Dispersion	C-63
C.2.6 Bioretention	C-63
C.2.7 Permeable Pavement	C-76
C.2.8 Rainwater Harvesting	C-88
C.2.9 Reduced Impervious Surface Credit	C-90
C.2.10 Native Growth Retention Credit	C-93
C.2.11 Perforated Pipe Connection	C-95
C.2.12 Rain Gardens	C-97
C.2.13 Soil Amendment	C-99
C.2.14 Tree Retention Credit	C-102
C.2.15 Vegetated Roofs	C-103
C.3 Construction Stormwater Pollution Prevention (CSWPP) Measures	C-109
C.3.1 Stabilized Construction Entrance	C-110
C.3.2 Mulching	C-112
C.3.3 Nets and Blankets	C-114
C.3.4 Plastic Covering	C-116
C.3.5 Mark Clearing Limits/Minimize Clearing	C-117
C.3.6 Silt Fence	C-117
C.3.7 Vegetated Strip	C-120
C.3.8 Triangular Silt Dike	C-120
C.3.9 Storm Drain Inlet Protection	C-121

C.3.10	Seeding	C-127
C.3.11	Sodding	C-129
C.3.12	Interceptor Dikes and Swales	C-130
C.3.13	Ditches	C-132
C.3.14	Pipe Slope Drain	C-134
C.3.15	Dewatering Control	C-136
C.3.16	Control of Other Pollutants (SWPPS)	C-136
C.4	Simplified Drainage Plan Specifications	C-139
C.4.1	Components of Simplified Drainage Plans	C-139
C.4.2	Specifications for Site Plans	C-141
C.4.3	BMP Design and Maintenance Details	C-145
C.4.4	Written Drainage Assessment	C-146
C.5	Reference Section	C-149
C.5.1	Simplified Drainage Review Process	C-149
C.5.2	Declaration of Covenant	C-151

APPENDIX C

SIMPLIFIED DRAINAGE REQUIREMENTS

The drainage requirements in this appendix are for residential *projects* that are subject to **Simplified Drainage Review** as determined in Section 1.1.2 of the *Surface Water Design Manual (SWDM)*. **Simplified Drainage Review** is a simplified alternative to the Full Drainage Review process normally conducted by the City as part of its review of permits to evaluate a project's compliance with the core and special requirements of the *SWDM*. The thrust of these requirements is to provide for mitigation and control of increased runoff and pollution from development sites. For larger developments, this typically involves engineering analysis and design of flow control facilities (e.g., detention ponds) to mitigate increased runoff, water quality treatment facilities (e.g., wetponds) to remove pollutants from the runoff, and erosion and sediment controls (ESC) to minimize the discharge of sediment-laden runoff and other pollutants during construction.

For projects in Simplified Drainage Review, required mitigation of runoff impacts can usually be achieved with measures that can be applied by a non-engineer. These include **on-site BMPs** (Best Management Practices) such as splash blocks or gravel trenches to disperse or infiltrate runoff from impervious areas, or reducing the amount of impervious area and preserving native vegetation. Such measures provide both flow and water quality mitigation. Also included are simpler **erosion and sediment control (ESC) measures** to prevent the discharge of sediment and other pollutants during construction. Examples of ESC measures include phasing or minimizing clearing, installing silt fences to contain sediment on site, and placing straw or other mulching materials on exposed soils. It also includes implementation of **stormwater pollution prevention and spill control (SWPPS)** practices applicable to specific construction activities such as proper use, handling, and storage of materials, chemicals, equipment, and fuel.

In most cases, the **Simplified Drainage Review** requirements in this appendix can be met with submittals prepared by contractors, architects, or homeowners without the involvement of a professional engineer. For more information on the **Simplified Drainage Review** process, see Section C.5.1.

Why On-Site BMPs are Necessary

On undeveloped land, most rainwater soaks into the ground and flows slowly to nearby lakes and streams through the upper layers of soil. When that same area is cleared or covered with an impervious surface, the rainwater is no longer captured by dense vegetation and forest duff, but flows quickly and in greater quantities across the site and through pipes and channels to streams and lakes. Also, as it flows over developed surfaces (e.g., driveways, roads, lawns, and pastures), various pollutants generated by human uses of the land are picked up and carried downstream. The increased quantities of runoff from the site, when combined with increases from other sites, results in increased flooding and erosion of downstream properties and damage to aquatic areas habitat. And, the pollutants collected by the runoff degrade the water quality and habitat functions of streams, lakes, and wetlands. Larger developments address these

impacts by both storing the runoff in engineered flow control facilities (e.g., detention or infiltration ponds or vaults) that slowly release the runoff downstream and by treating the runoff in engineered water quality facilities (e.g., wet ponds, biofiltration swales, or sand filters) and by application of on-site BMPs to maximum extent feasible.

Controlling flows from smaller projects is just as important as controlling flows from large developments, because the cumulative effect of uncontrolled flows from many small projects can be equivalent to those from a single large project. For projects that qualify as **Simplified Drainage Review** projects, however, engineered flow control facilities may not be practicable or even warranted if the quantity of runoff from developed surfaces can be minimized, dispersed, or otherwise infiltrated onsite through the use of on-site BMPs. The same holds true for water quality facilities. While the primary focus of on-site BMPs is to mitigate increased runoff quantities, they are also effective in mitigating increased pollution generated by developed surfaces.

Construction Stormwater Pollution Prevention (CSWPP), and Why CSWPP Is Necessary

Construction stormwater pollution prevention (CSWPP) is the combined strategies of ESC and SWPPS to control pollutants on construction sites. ESC measures are necessary because land disturbing activity associated with clearing and grading exposes a site's soils to erosion by stormwater. The soil eroded from disturbed areas is referred to as *sediment*, which is washed downstream and deposited in pipes, ditches, streams and lakes. Sediment deposited in a pipe or ditch reduces its capacity to convey flows and can increase the likelihood of flooding. Sediment deposited in streams clog the gravels that salmon use for spawning. Nutrients contained in the eroded soil that reach lakes can upset the chemical balance of the lake, causing excessive growth of algae, milfoil, and other plants, and decreasing recreational uses such as swimming, boating, and fishing. ESC measures are typically used during construction to prevent soil erosion and/or transport of sediment downstream until the site can be stabilized with vegetation cover/landscaping. Other construction activities such as the use, handling, and storage of materials, chemicals, equipment, and fuel can result in contaminants coming into contact with stormwater and potentially washed downstream. Therefore, stormwater pollution prevention and spill control (SWPPS) measures applicable to specific construction activities need to be implemented to avoid the discharge of pollutants from the construction site.

Utility of Appendix C

For projects in **Simplified Drainage Review**, this appendix outlines the drainage requirements, on-site BMPs, and CSWPP measures necessary to mitigate the stormwater impacts of development without the construction of expensive stormwater facilities (i.e., flow control and water quality facilities). For projects in Full Drainage Review or other types of drainage review, the on-site BMPs contained in this appendix are referenced for application to any size or type of project as specified in the *SWDM*. In fact, because flow control facilities cannot mitigate all the impacts from developed surfaces, on-site BMPs are required on all projects in drainage review regardless of whether stormwater facilities are required (see *SWDM* Core Requirement #9, Section 1.2.9, "On-site BMPs").

Organization of Appendix C

The information presented in this appendix is organized into five main sections as follows:

- Section C.1, "Simplified Drainage Review Requirements"
- Section C.2, "On-Site BMPs"
- Section C.3, "Construction Stormwater Pollution Prevention (CSWPP) Measures"
- Section C.4, "Simplified Drainage Plan Specifications"
- Section C.5, "Drainage Review"

Definitions of Key Terms

Proper application of the **Simplified Drainage Review** requirements in this appendix requires an understanding of the following key terms and their definitions. These terms are highlighted in ***bold italic*** throughout Appendix C. Other important terms are defined in the text when they are first introduced. These are highlighted in italic when they are first introduced but are not highlighted throughout the appendix as are key terms.

Civil engineer means a person licensed by the State of Washington as a professional engineer in civil engineering.

Engineering geologist means a person licensed by the State of Washington as a geologist specializing in evaluating geologic site characteristics to determine the responses of geologic processes and materials to development activities, such as removal of vegetation; construction activities such as earthwork; applying loads in foundations and embankments; use of earth materials in construction; and modifying ground water flow.

Erosion hazard area is the critical area¹ designation, defined and regulated in RMC 4-3-050, that is applied to areas underlain by soils that are subject to severe erosion when disturbed. Refer to the City of Renton Map Gallery for a map of erosion hazard areas (<http://rentonwa.gov/government/default.aspx?id=29885>) or view via COR Maps (<http://rp.rentonwa.gov/SilverlightPublic/Viewer.html?Viewer=COR-Maps>).

Flood hazard area is the critical area designation, defined and regulated in RMC 4-3-050, that is applied to areas subject to flooding. Refer to the City of Renton Map Gallery for a map of flood hazard areas (<http://rentonwa.gov/government/default.aspx?id=29885>) or view via COR Maps (<http://rp.rentonwa.gov/SilverlightPublic/Viewer.html?Viewer=COR-Maps>).

Geotechnical engineer means a civil engineer licensed by the State of Washington who has at least four years of professional employment as a geotechnical engineer in responsible charge, including experience with landslide evaluation. Geotechnical engineers specialize in the design and construction aspects of earth materials.

Impervious surface means a non-vegetated surface area that either prevents or retards the entry of water into the soil mantle as under natural conditions before development; or that causes water to run off the surface in greater quantities or at an increased rate of flow compared to the flow present under natural conditions prior to development (see also “*new impervious surface*”). Common impervious surfaces include, but are not limited to, roof, walkways, patios, driveways, parking lots, or storage areas, areas that are paved, graveled or made of packed or oiled earthen materials or other surfaces that similarly impede the natural infiltration of surface water or stormwater. For the purposes of applying the impervious surface thresholds and exemptions contained in this manual, permeable pavement, vegetated roofs, and underdrained pervious surfaces are considered impervious surface while an open uncovered flow control or water quality facility is not. However, for the purposes of computing runoff, uncovered flow control or water quality facilities shall be modeled as impervious surfaces as specified in Chapter 3.

Land disturbing activity means any activity that results in a change in the existing soil cover, both vegetative and non-vegetative, or the existing soil topography. Land disturbing activities include, but are not limited to demolition, construction, clearing, grading, filling, excavation, and compaction. Land disturbing activity does not include tilling conducted as part of agricultural practices, landscape maintenance, or gardening.

¹ Footnote 1 is not used.

Landslide hazard is the critical area designation, defined and regulated in RMC 4-3050, that is applied to areas subject to risk of landslide due to topography, soil conditions, and geology. Refer to the City of Renton Map Gallery for a map of landslide hazards (<http://rentonwa.gov/government/default.aspx?id=29885>) or view via COR Maps (<http://rp.rentonwa.gov/SilverlightPublic/Viewer.html?Viewer=COR-Maps>).

Native vegetated surface means a surface in which the soil conditions, ground cover, and species of vegetation are like those of the original native condition for the *site*. More specifically, this means (1) the soil is either undisturbed or has been treated according to the “native vegetated landscape” specifications in Appendix C, Section C.2.1.8; (2) the ground is either naturally covered with vegetation litter or has been top-dressed between plants with 4 inches of mulch consistent with the native vegetated landscape specifications in Appendix C; and (3) the vegetation is either (a) comprised predominantly of plant species, other than noxious weeds, that are indigenous to the coastal region of the Pacific Northwest and that reasonably could have been expected to occur naturally on the *site* or (b) comprised of plant species specified for a native vegetated landscape in Appendix C. Examples of these plant species include trees such as Douglas fir, western hemlock, western red cedar, alder, big-leaf maple and vine maple; shrubs such as willow, elderberry, salmonberry and salal; and herbaceous plants such as sword fern, foam flower, and fireweed.

New impervious surface means the addition of a man-made, modified, or compacted surface like roofs, pavement, gravel, or dirt; or the addition of a more compacted surface, such as resurfacing by upgrading from dirt to gravel, asphalt, or concrete; upgrading from gravel to asphalt, or concrete; or upgrading from a bituminous surface treatment (“chip seal”) to asphalt or concrete. Permeable pavement and vegetated roofs are considered new impervious surface for purposes of determining whether the thresholds for application of minimum design requirements are exceeded, as are lawns, landscaping, sports fields, golf courses, and other areas that have modified runoff characteristics resulting from the addition of underdrains designed to collect stormwater runoff. Open, uncovered retention/detention facilities shall not be considered impervious surfaces for purposes of determining whether the thresholds for application of minimum design requirements are exceeded. Open, uncovered retention/detention facilities shall be considered impervious surfaces for purposes of runoff modeling.

New pervious surface means the conversion of a native vegetated surface or other native surface to a nonnative pervious surface (e.g., conversion of forest or meadow to pasture land, grass land, cultivated land, lawn, landscaping, bare soil, etc.), or any alteration of existing nonnative pervious surface that significantly increases surface and storm water runoff (e.g., conversion of pasture land, grass land, or cultivated land to lawn, landscaping, or bare soil; or alteration of soil characteristics).

On-site BMP means a small scale drainage facility or feature that is part of a development site strategy to use processes such as infiltration, dispersion, storage, evaporation, transpiration, forest retention, and reduced impervious surface footprint to mimic pre-developed hydrology and minimize stormwater runoff.

Pollution-generating impervious surface means an impervious surface considered to be a significant source of pollutants in stormwater runoff. Such surfaces include those that are **subject to: vehicular use**, industrial activities, or storage of **erodible or leachable materials, wastes, or chemicals** and that receive direct rainfall or the run-on or blow-in of rainfall. A covered parking area would be considered PGIS if runoff from uphill could regularly run through it or if rainfall could regularly blow in and wet the pavement surface. Metal roofs are also considered PGIS unless they are coated with an inert, non-leachable material (see Reference Section 11-E). PGIS includes roofs that are exposed to the venting of significant amounts of dusts, mists, or fumes from manufacturing, commercial, or other indoor activities. PGIS includes vegetated roofs exposed to pesticides, fertilizers, or loss of soil. Other roofing types that may pose risk but are not currently regulated are listed in Reference Section 11-E. Lawns, landscaping, sports fields, golf courses, and other areas that have modified runoff characteristics resulting from the addition of underdrains that have the pollution generating

characteristics described under the “pollution-generating pervious surface” definition are also considered *PGIS*.

Pollution-generating pervious surface (PGPS) means a non-impervious surface considered to be a significant source of pollutants in surface and storm water runoff. Such surfaces include those that are *subject to vehicular use*, industrial activities, storage of *erodible or leachable materials, wastes, or chemicals*, and that receive direct rainfall or the run-on or blow-in of rainfall; or subject to use of pesticides and fertilizers, or loss of soil. Such surfaces include, but are not limited to, the lawn and landscaped areas of residential, commercial, and industrial sites or land uses, golf courses, parks, sports fields (natural and artificial turf), cemeteries, and grassed modular grid pavement.

Project site means that portion of a *site* and any offsite areas subject to proposed project activities, alterations, and improvements including those required by this appendix.

Rain garden means a shallow, landscaped depression with compost-amended native soils and adapted plants. The depression is designed to pond and temporarily store stormwater runoff from adjacent areas, and to allow stormwater to pass through the amended soil profile. Rain gardens can only be used to meet Core Requirement #9.

Replaced impervious surface means any existing impervious surface on the *project site* that is proposed to be removed and re-established as impervious surface, excluding impervious surface removed for the sole purpose of installing utilities or performing maintenance on underground infrastructure. For structures, *removed* means the removal of buildings down to the foundation. For other impervious surfaces, *removed* means the removal down to base course or bare soil. It does not include the removal of pavement material through grinding or other surface modification unless the entire layer of PCC or AC is removed. Replaced impervious surface also includes impervious surface that is moved from one location to another on the project site where the following two conditions are met: (A) runoff characteristics and volumes remain the same or are improved in the area where the existing impervious surface is removed, and (B) impervious surface at the new location is either designated as non-pollution generating or the pollution generating characteristics remain unchanged compared to that of the original location. ***Single family residential project*** means any project that (a) constructs or modifies a single family dwelling unit, (b) makes improvements (e.g., driveways, roads, outbuildings, play courts, etc.) or clears native vegetation on a lot that contains or will contain a single family dwelling unit, or (c) is a plat, short plat, or boundary line adjustment that creates or adjusts lots that will contain single family dwelling units.

Site (a.k.a. *development site*), as used in this appendix, means a single parcel, or either: two or more contiguous parcels that are under common ownership or documented legal control or a portion of a single parcel under documented legal control separate from the remaining parcel, used as a single parcel for a proposed project for purposes of applying for authority from the City to carry out a proposed project. For projects located primarily within dedicated rights-of-way, the length of the project site and the right-of-way boundaries define the site.

Steep slope hazard area is the critical area designation, defined and regulated in RMC 4-3-050, that is applied to areas where extra protection of sensitive slopes is required. Refer to the City of Renton Map Gallery for a map of steep slope hazard areas (<<http://rentonwa.gov/government/default.aspx?id=29885>>).

Target impervious surface means that portion of a *site's* existing, new, and replaced impervious surface from which runoff impacts are required to be mitigated by a particular set of drainage requirements (on-site BMPs in this appendix). . *Note: any impervious surface on the site other than target impervious surface may be mitigated by on-site BMPs in trade for not mitigating an equivalent-sized area of target impervious surface.*

Target pervious surface means all areas subject to clearing and grading that have not been covered by an *impervious surface*, incorporated into a drainage facility, or engineered as structural fill or slope.

(This page intentionally left blank.)

C.1 SIMPLIFIED DRAINAGE REVIEW REQUIREMENTS

Threshold

Simplified Drainage Review is required for any *single family residential project* that will result in 2,000 square feet² or more of *new impervious surface, replaced impervious surface, or new plus replaced impervious surface*, or 7,000 square feet or more of *land disturbing activity*, AND that meets the following criteria:

The project will result in less than 5,000 square feet of new plus replaced *pollution generating impervious surface*, result in less than $\frac{3}{4}$ acre of new *pollution generating pervious surfaces*, AND meets one of the following three additional criteria:

1. The project meets the Basic Exemption from flow control in Core Requirement #3 a) the project results in less than 5,000 square feet of *new plus replaced impervious surface*, AND b) less than $\frac{3}{4}$ acres of *new pervious surface* will be added. *Note the Basic Exemption thresholds are applied by project site.*
2. For projects on predominately till soils:
The project results in no more than 7,947 square feet of *target impervious surfaces* (see below) as defined in Section 1.1.2.1 AND proposed pervious area is equal to or less than 14,941 – 1.88 x (total *target impervious surfaces*).
3. For projects on predominately outwash soils:
The project results in no more than 6,872 square feet of *target impervious surfaces* (see below) as defined in Section 1.1.2.1 AND proposed pervious area is equal to or less than 20,343 – 2.96 x (total *target impervious surfaces*).

Determination of Target Impervious Surface

- If the project is a New Development project, then target impervious surfaces include new *plus proposed replaced impervious surface*.
- If the project is a Redevelopment project where
 - New impervious surface is less than 5,000 square feet *or*
 - Valuation of improvements is less than 50% of the **assessed value** of the existing site improvements.

then target impervious surfaces include new impervious surface.
- If the project is a Redevelopment project where
 - New impervious surface is greater than or equal to 5,000 square feet *and*
 - Valuation of improvements is greater than or equal to 50% of the **assessed value** of the existing site improvements

then target impervious surfaces include new *plus proposed replaced impervious surface*.

Note: for the purposes applying this threshold to a proposed single family residential subdivision (i.e., plat or short plat project), the impervious surface coverage assumed on each created lot shall be 4,000 square feet or the maximum allowed by RMC 4-6-030, whichever is less. A lower impervious surface coverage

² The thresholds of 2,000 and 7,000 square feet shall be applied by project site. All other thresholds specified in terms of square feet of impervious or pervious surface shall be applied by **threshold discharge area** and in accordance with the definitions of these surfaces in the preamble to Section C.1 above. *Note: the calculation of total impervious surface may exclude any such added impervious surface that is confirmed by CED staff to be already mitigated by a City approved and inspected flow control facility or on-site BMP.*

may be assumed for any lot in which the lower impervious surface coverage is set as the maximum through a declaration of covenant recorded for the lot. Also, the **new pervious surface** assumed on each created lot shall be the entire lot area, except the assumed impervious portion and any portion in which native conditions are preserved by a clearing limit per RMC IV, a covenant or easement recorded for the lot, or a tract dedicated by the proposed subdivision.

All projects subject to Simplified Drainage Review must comply with the following two basic mitigation requirements in this appendix:

1. Apply **on-site BMPs** to developed surfaces as directed in Section C.1.3, and
2. Apply **erosion and sediment control (ESC) measures** to disturbed areas during construction and applicable **stormwater pollution prevention and spill control (SWPPS)** measures as directed in Section C.1.4.

To show how these requirements will be met, project applicants must submit drainage plans and supporting documentation as directed in Section C.1.5.

In addition, some Simplified drainage review projects may have *site*-specific or project-specific drainage concerns or requirements that must be addressed by a *civil engineer* or City engineering review staff. Examples include the presence of flood, erosion, or landslide hazards on or near the *site*, safe conveyance of stormwater through the *site*, and application of special drainage requirements. The City will identify any such issues during **Simplified Drainage Review** and will require a separate **Targeted Drainage Review** in addition to **Simplified Drainage Review** to address them (see Section 0). This may require the additional submittal of *site* information, reports, and/or engineering plans signed and stamped by a *civil engineer*. For more information on how **Targeted Drainage Review** relates to **Simplified Drainage Review**, see Section C.5.1.

Use Section C.1.1 (below) to determine the scope of requirements, if any, that must be addressed by a *civil engineer* and/or City engineering review staff under **Targeted Drainage Review**, and learn where to look to determine the scope of requirements for application of on-site BMPs and CSWPP measures and submittal of information necessary for **Simplified Drainage Review**.

C.1.1 PROCEDURE FOR DETERMINING REQUIREMENTS

The following questionnaire/flow chart (Table C.1.1.A) is intended to be a guide for determining the scope of requirements that will apply to a project in **Simplified Drainage Review**, and **Targeted Drainage Review** if applicable. It will refer or direct you to more specific information on the application of requirements found in subsequent subsections, and in some cases, City of Renton Municipal Code.

No.	Question	If YES	If NO
1.	Is the proposed project subject to drainage review as determined by consulting CED ³ or Section 1.1.1 of the SWDM?	Go to the next question.	The project does not need to meet the requirements of the SWDM or this appendix.

³ CED means the City of Renton Department of Community and Economic Development, which is the department responsible for conducting drainage review of proposed projects that are subject to a City of Renton development permit or approval. Applicants for a permit or approval should contact CED staff prior to submittal to determine/confirm that drainage review is required, and if so, what type of drainage review is appropriate. Applicants may also arrange a predesign meeting with CED review staff to confirm the type of drainage review and scope of drainage requirements that apply to the proposed project.

TABLE C.1.1.A QUESTIONNAIRE/FLOW CHART FOR DETERMINING REQUIREMENTS			
No.	Question	If YES	If NO
2.	Is the project subject to Simplified Drainage Review as determined in Section C.1 and confirmed with CED?	Step through the following questions to (1) determine the scope of requirements, if any, that must be addressed by a civil engineer and/or CED under Targeted Drainage Review, and (2) learn where to look to determine the scope of requirements for application of on-site BMPs and CSWPP measures and submittal of information necessary for Simplified Drainage Review.	Directed Drainage Review, Full Drainage Review, Targeted Drainage Review, or Large Project Drainage Review is required as specified in the <i>SWDM</i> , and engineering plans signed and stamped by a civil engineer must be submitted to CED. Use the <i>SWDM</i> and not this appendix to determine drainage review requirements.
3.	Does the site contain or is it adjacent to a flood hazard as determined by CED through a “critical area review” per RMC Title IV?	A notice on title will be required and any proposed structures or substantial improvements within the 100-year floodplain will require a FEMA Elevation Certificate completed by a civil engineer or land surveyor . See Section C.1.2.1 for further details. Go to the next question.	Skip to Question 7.
4.	Has the 100-year floodplain boundary and <i>base flood elevation</i> ⁴ been determined for the flood hazard based on available flood hazard data and deemed acceptable by CED in accordance with RMC 4-3-050?	The floodplain boundary and base flood elevation must be shown on the project’s site plans and on the face of any recorded documents if the project is a subdivision. See Section C.1.2.1 for further details. Go to the next question.	A floodplain study in accordance with Section 4.4.2 of the <i>SWDM</i> must be completed by a civil engineer (or authorized agency) to determine the appropriate floodplain boundary and base flood elevation that will be used by CED to evaluate the proposed project’s compliance with the flood hazard development standards in RMC 4-3-050. See Section C.1.2.1 for further details and requirements. Go to the next question.

⁴ *Base flood elevation* is the elevation of the 100-year floodplain, at the **project site**, that has been determined in accordance with the standards in RMC 4-3-050.

TABLE C.1.1.A QUESTIONNAIRE/FLOW CHART FOR DETERMINING REQUIREMENTS			
No.	Question	If YES	If NO
5.	Is the project site portion of the site located on land that is entirely outside of the 100-year floodplain boundary and above the base flood elevation determined in Question 1?	Go to the next question.	The project site must be relocated to land that is outside of the 100-year floodplain and above the base flood elevation, or a civil engineer must evaluate and modify the project as needed to comply with the standards in RMC 4-3-050 for development within the floodplain. This may require a major floodplain study in accordance with Section 4.4.2 of the <i>SWDM</i> to determine the floodway boundary of the flood hazard . See Section C.1.2.1 for further details and requirements. Go to the next question.
6.	Has a channel migration zone ⁵ been mapped by King County for the flood hazard ?	This question does not apply to projects in the City. Go to the next question.	This question does not apply to projects in the City. Go to the next question.
7.	Does the site contain or is it adjacent to an erosion hazard area as determined by CED through a “critical area review” per RMC Title IV?	CED may require additional flow control or ESC measures designed by a civil engineer to avoid impacts to these areas. See Section C.1.2.2 for further details. Go to the next question.	Go to the next question.
8.	Does the site contain or is it adjacent to a steep slope hazard area or landslide hazard as determined by CED through a “critical area review” per RMC Title IV?	CED will review the project for compliance with the development standards for these hazard areas as specified in RMC 4-3-050. CED must approve all drainage systems for the project and may require a geotechnical analysis. A tightline designed by a civil engineer may be required to safely convey any concentrated runoff through the hazard area. See Section C.1.2.3 for further details. Go to the next question.	Go to the next question.

⁵ Footnote 5 is not used.

TABLE C.1.1.A QUESTIONNAIRE/FLOW CHART FOR DETERMINING REQUIREMENTS			
No.	Question	If YES	If NO
9.	Is the project located in an Aquifer Protection Area , a basin planning area, community planning area, and/or other area with adopted area-specific drainage requirements AND does the project exceed the minimum thresholds for these drainage requirements as determined by CED (see Section C.1.2.4)?	The project must meet the Aquifer Protection Area and/or area-specific drainage requirements, some of which may require drainage systems or measures designed by a civil engineer . CED will determine which requirements are applicable and if engineering plans signed and stamped by a civil engineer are required. Go to the next question	Go to the next question.
10.	Is the project proposing 1 acre or more of land disturbing activity (see Section C.1.2.5)?	CSWPP plans signed and stamped by a civil engineer are required to address compliance with the ESC standards for larger projects specified in the <i>SWDM</i> . Go to the next question.	Go to the next question.
11.	Is the project proposing to construct or modify a drainage pipe or ditch that is 12 inches or more in diameter/depth, or does the project site receive surface or storm water from a drainage pipe or ditch that is 12 inches or more in diameter/depth (see Section C.1.2.6)?	Engineering plans signed and stamped by a civil engineer are required to address compliance with the Targeted Drainage Review requirements pertaining to constructed or modified conveyance systems in the <i>SWDM</i> . Go to the next question.	Go to the next question.
12.	Are there any other drainage features onsite (swales, ditches, etc.) that may impact the proposed project or downstream properties or be impacted by the project?	Engineering analysis by a civil engineer may be required. CED staff will need to assess features. Go to the next question.	Go to the next question.

TABLE C.1.1.A QUESTIONNAIRE/FLOW CHART FOR DETERMINING REQUIREMENTS			
No.	Question	If YES	If NO
13.	Is the proposed project on a site/lot smaller than 22,000 square feet?	<p>Apply on-site BMPs in accordance with the Small Lot BMP Requirements in Section C.1.3.1 and the On-Site BMP Implementation Requirements in Section C.1.3.4.</p> <p>Apply ESC and SWPPS measures in accordance with Section C.1.4.</p> <p>Comply with the Simplified submittal requirements in Section C.1.5.</p>	<p>Apply on-site BMPs in compliance with the Large Lot BMP Requirements in Section C.1.3 and the On-Site BMP Implementation Requirements in Section C.1.3.4.</p> <p>Apply ESC and SWPPS measures in accordance with Section C.1.4.</p> <p>Comply with the Simplified submittal requirements in Section C.1.5.</p>

C.1.2 TARGETED DRAINAGE REVIEW REQUIREMENTS

Targeted Drainage Review is usually required in addition to **Simplified Drainage Review** for any projects that have one or more of the following characteristics as determined by CED:

- The project's drainage or improvements may impact or be impacted by the presence of certain critical areas (i.e., streams, lakes, wetlands, *aquifer protection areas*, *flood hazard areas*, *erosion hazard areas*, *steep slope hazard areas*, and *landslide hazards*).
- The project is subject to additional drainage requirements by virtue of its location in areas where special drainage requirements have been adopted.
- The project proposes 1 acre or more of *land disturbing activity*.
- The project proposes to construct or modify a drainage pipe/ditch that is 12 inches or more in size or depth or receives runoff from a drainage pipe/ditch that is 12 inches or more in size or depth.
- The project has other concerns that require evaluation, analysis, and/or design by *civil engineer*.

For some projects in **Targeted Drainage Review**, CED review staff may be able to address some of the above concerns/requirements without a *civil engineer* through approval of the on-site BMPs/CSWPP measures in this appendix combined with increased setbacks, geotechnical review, or permit approval conditions. In other cases, a *civil engineer* will be required to address specific requirements in the *SWDM* and submit engineering plans.

Note: Targeted Drainage Review is not a substitute for a Critical Area Review. Simplified Drainage Review project proposals are not exempted from applicable requirements of RMC 4-3-050 (critical areas regulations) including critical area reports, notices on title, buffers, building setbacks, and development standards/alterations.

C.1.2.1 FLOOD HAZARD AREAS

Some **Simplified Drainage Review** projects may be on *sites* that contain or are adjacent to a **flood hazard area** for a stream, lake, wetland, *closed depression*,⁶ marine shoreline, or other water feature as determined by CED through a critical area review. If the project is on such a *site*, the 100-year **floodplain boundary** and **base flood elevation**, at a minimum, must be determined and shown on the project's *site* plans⁷ and on the face of any recorded documents for a subdivision. The floodplain and base flood elevation may be identified from an **already completed 100-year floodplain study** approved by CED in accordance with RMC 4-3-050. Examples of approved floodplain studies include the Federal Emergency Management Agency (FEMA) mapping of the 100-year floodplain and base flood elevation, and floodplain mapping completed by the King County Department of Natural Resources, Water and Land Resources Division (WLRD).

If an **approved floodplain study does not exist** for the *site*, one must be prepared by a *civil engineer* in accordance with the methods and procedures in Section 4.4.2 of the *SWDM*. For some *sites*, if the *project site* is at least 10 feet above the ordinary high water mark or 2 feet above the downstream overflow elevation of a water feature, a Simplified study per Section 4.4.2 may be used to identify an "approximate" floodplain boundary and base flood elevation. In some cases, CED review staff, in lieu of a *civil engineer*, may identify this approximate floodplain boundary and base flood elevation based on elevation information provided by the applicant's *land surveyor*.⁸

⁶ *Closed depression* means an area greater than 5,000 square feet at overflow elevation that is low-lying and that has no or such a limited surface water outlet that the area acts as a stormwater retention facility. The primary loss of water volume from a closed depression is through evapotranspiration and discharge into the ground rather than surface flow.

⁷ *Note: for single family residential permits, CED may waive the requirement for floodplain delineation on the site plan, provided the plan notes that a floodplain exists and indicates the base flood elevation.*

⁸ *Land surveyor* means a person licensed by the State of Washington as a professional land surveyor.

If any portion of the project is within the 100-year floodplain, the 100-year **floodway** boundary must also be determined and shown on the project's *site* plans and on the face of any recorded documents for a subdivision. As with the floodplain boundary and base flood elevation, a floodplain study may be required in accordance with Section 4.4.2 of the *SWDM* to determine the floodway if one has not already been completed and approved by CED for the *site*.

CED uses all of the **flood hazard area information** determined above to review a project for compliance with FEMA regulations and the City's **flood hazard area** regulations in RMC 4-3-050. If CED staff determines that the proposed project meets these regulations for building in or near a floodplain, the permit may be approved with specific conditions to ensure the project does not impact the floodplain and that a flood will have minimal impact on the **project site**. Examples of conditions could include:

- Building on a portion of the *site* where the existing ground is higher than the 100-year flood elevation,
- Building within the flood fringe using a pier or pile foundation to provide unrestricted flow through the foundation area,
- Placing no fill within any portion of the floodplain without providing equivalent compensating storage.

For permits proposing a building within the 100-year floodplain, a "**FEMA Elevation Certificate**" must be completed by a **civil engineer** or **land surveyor** and submitted to CED after the foundation is constructed but prior to the framing approval. The certificate documents the elevation of the lowest finished floor of the building as determined by or under the direction of a **civil engineer** or **land surveyor**. This certificate is often required by mortgage companies, and it helps the homeowner obtain proper flood insurance and maintain accurate insurance ratings for flood-prone areas.

Prior to permit approval (or in the case of a subdivision, at or before recording), a **notice on title** must be recorded for the *site* (or the individual lots of a subdivision). The notice on title must note that a **flood hazard area** exists and that no fill or alteration is allowed within the **flood hazard area**. The base flood elevation must also be noted.

If CED staff determines that the proposed project does not meet FEMA or City regulations for building in or near a floodplain, the applicant may be required to hire a **civil engineer** to address compliance with these regulations. If the **project site** is partially or fully located in the mapped 100-year floodway, the permit may be denied as federal and City regulations prohibit building structures in the floodway.

C.1.2.2 EROSION HAZARD AREAS

Some projects may drain to or are on *sites* that contain an **erosion hazard area**, which is a critical area defined and regulated in RMC 4-3-050. Vegetation removal and grading make **erosion hazard areas** prone to erosion and sediment transport, and the *point discharge*⁹ of stormwater runoff can cause erosion in such areas even if they are well vegetated. Projects in Simplified Drainage Review that are determined to drain to these areas may be required to provide additional on-site BMPs or other measures that must be engineered. If flow control and erosion and sediment control cannot be adequately addressed by the on-site BMPs and ESC measures in this appendix, CED may require a **civil engineer** to provide a *site*-specific construction sequence and engineered site improvement/ESC plans.

C.1.2.3 STEEP SLOPE AND LANDSLIDE HAZARDS

Some projects may drain to or are on *sites* that contain or are adjacent to a **steep slope hazard area** or a **landslide hazard**. Storm runoff not properly controlled can cause erosion, landslides, raveling, and instability. Point discharge of runoff is not allowed near or onto these areas. On-site BMPs may be allowed if installed according to the design requirements and specifications in Section C.2.

⁹ *Point discharge* means a concentrated flow from a pipe, ditch, or other similar drainage feature.

All drainage systems on or near **steep slope hazard areas** or **landslide hazard** must be approved by CED.

If on-site BMPs are not adequate to prevent adverse impacts to a **steep slope hazard area** or **landslide hazard** as determined by the CED, a *tightline*¹⁰ may be constructed to convey the runoff to a stable discharge point with adequate energy dissipation. The location of the discharge point must be onsite or within a drainage easement or public right-of-way. The tightline must conform to the materials and design requirements of Section 4.2 of the *SWDM* and must be approved by a **geotechnical engineer, engineering geologist**, or CED.

Tightlines typically require design by a **civil engineer** in accordance with Section 4.2.2.1 of the *Surface Water Design Manual*. However, for a simple installation serving one lot, CED may provide a standardized design if they determine that the standardized tightline and energy dissipation system is appropriate.

Note: For most projects in Simplified Drainage Review with less than 10,000 square feet of impervious surface, the tightline system may be constructed using 6-inch diameter solid wall polyethylene (solid wall PE) pipe with a standard outfall. See Figure 4.2.2.D of the SWDM for an example tightline outfall.

C.1.2.4 ADOPTED AREA-SPECIFIC DRAINAGE REQUIREMENTS

Some projects may be subject to additional drainage requirements and/or engineering analysis by virtue of their location in an area subject to aquifer protection, or where special drainage requirements have been adopted via a basin plan, salmon conservation plan, stormwater compliance plan, lake management plan, flood hazard reduction plan, etc. Projects located in such areas must comply with these requirements if the requirements are more stringent than the requirements of this appendix as determined by CED.

Aquifer Protection Areas (APA) are identified in RMC 4-3-050. If a proposed project is located within the APA, Special Requirement #6 in Section 1.3.6 of the *SWDM* applies. Reference Section 15-B includes a map of the City's Aquifer Protection Area, Zones 1 and 2.

Engineering analysis and/or engineering plans signed and stamped by a **civil engineer** may be required to comply with these requirements or show that the project is exempt or below the threshold for application of specific requirements. CED staff will determine which requirements apply and the extent of engineering analysis required. When engineering analysis shows that a requirement threshold will not be exceeded, the project's applicant, contractors, and inspectors must be notified of any actions or limitations necessary to prevent that threshold from being exceeded.

C.1.2.5 ONE ACRE OR MORE OF LAND DISTURBING ACTIVITY

Projects in **Simplified Drainage Review** that are proposing 1 acre or more of **land disturbing activity** typically necessitate more expert attention to required ESC and SWPPS pollution prevention measures. Consequently, a construction stormwater pollution prevention (CSWPP) plan will need to be prepared in accordance with the CSWPP plan requirements for larger projects specified in Chapter 2 of the *SWDM*. In order to comply with these requirements, an engineered CSWPP plan and limited scope Technical Information Report (TIR) signed and stamped by a **civil engineer** will be required. CED may waive this requirement if the **site's** topography is such that no more than 1 acre of disturbed area will drain to one location.

C.1.2.6 PIPES/DITCHES TWELVE INCHES OR MORE IN SIZE/DEPTH

Projects in **Simplified Drainage Review** that propose to construct or modify a drainage pipe that is 12 inches or more in size or a ditch that is 12 inches or more in depth, or modify a drainage pipe/ditch that receives runoff from a drainage pipe/ditch that is 12 inches or more in size/depth, must submit engineering

¹⁰ *Tightline* means a continuous length of pipe that conveys water from one point to another (typically down a steep slope) with no inlets or collection points in between.

plans meeting the requirements outlined for Targeted Drainage Review Category #2 (see Section 1.1.2.2 of the *SWDM*). This requirement may be waived by CED for driveway culverts less than 25 feet in length that match downstream and upstream culvert sizes.

C.1.3 APPLICATION OF ON-SITE BMPS

On-site BMPs are methods and designs for dispersing, infiltrating, or otherwise reducing or preventing development-related increases in runoff at or near the sources of those increases. On-site BMPs include, but are not limited to, preservation and use of *native vegetated surfaces* to fully disperse runoff; use of other pervious surfaces to disperse runoff; roof downspout infiltration; permeable pavements; bioretention; and reduction of development footprint.

For projects subject to **Simplified Drainage Review**, the application of on-site BMPs is mandatory. For individual lot projects, on-site BMPs must be applied as specified by one of the following three sets of BMP requirements, whichever is applicable based on the size of *site/lot*, the extent of impervious surface coverage resulting from the project on the *site/lot*, and the location of the project:

- Small Lot BMP Requirements (for *sites/lots* <22,000 square feet), Section C.1.3.1
- Large Lot BMP Requirements (for *sites/lots* ≥22,000 square feet), Section C.1.3.2

These requirements specify both the order of preference for selection of on-site BMPs and their extent of application to the developed surfaces of an **individual lot project**. The implementation of on-site BMPs by projects on the individual *site/lot* must be in accordance with the “On-site BMP Implementation Requirements” detailed in Section C.1.3.4.

On-site BMP requirements for **subdivision projects** and **projects within rights-of-way** (e.g., road improvements) are detailed in Section 1.2.9 of the *SWDM*.

❑ EVALUATING WHETHER A BMP IS REQUIRED: INFEASIBILITY AND COMPETING NEEDS

Proper application of the requirements is intended to result in on-site BMPs implemented to the *maximum extent feasible* on the *site/lot*. Whether a BMP is considered feasible or not is determined by evaluation of specific criteria provided for each BMP in the detailed BMP sections of this manual. In addition to a determination of infeasibility, a BMP may not be required if implementation of the BMP would be in conflict with:

- Requirements of the following federal or state laws, rules, and standards: Historic Preservation Laws and Archaeology Laws as listed at <<http://www.dahp.wa.gov/learn-and-research/preservation-laws>>, Federal Superfund or Washington State Model Toxics Control Act, Federal Aviation Administration requirements for airports, Americans with Disabilities Act.
- Where a BMP requirement has been found to be in conflict with special zoning district design criteria adopted and being implemented pursuant to a community planning process, the existing local codes may supersede or reduce the BMP requirement.
- Public health and safety standards.
- Transportation regulations to maintain the option for future expansion or multi-modal use of public rights-of-way.
- A local Critical Area Ordinance that provides protection of tree species.
- A local code or rule adopted as part of a Wellhead Protection Program established under the Federal Safe Drinking Water Act; or adopted to protect a Critical Aquifer Recharge Area established under the State Growth Management Act.

❑ REQUIRED SOIL REPORT, INVESTIGATION AND INFILTRATION RATE TESTING

Determining the feasibility of infiltrative BMPs requires soils investigation and testing of the subgrade to identify soil types, soil characteristics, depth to impermeable layers (hardpan) or maximum wet season groundwater level, and infiltration rates of the native soil.

Specific requirements for the soils report and infiltration testing are as follows:

Required Soil Report

Where full dispersion of runoff from target surfaces for each site/lot is not feasible or applicable as specified in Section C.2.1.1 and C.2.1.2, a soils report is a required for the purpose of determining the feasibility of full infiltration of roof runoff and other infiltrative BMPs that may need to be evaluated to meet the project's defined BMP requirements.

Soils reports must be prepared by or under the direction of a licensed onsite sewage system designer or geotechnical professional (e.g., licensed engineer with geotechnical and/or hydrogeologic experience, licensed geologist, hydrogeologist, or engineering geologist).

A soils report produced for siting and design of an **onsite sewage system** may also be used to satisfy this soils report requirement, provided that the report includes all of the information required and described below.

- The soils report shall reference a sufficient number of soils logs to establish the type and limits of soils on the project site. The report should at a minimum identify the limits of any outwash type soils (e.g., textural classes ranging from coarse sand and cobbles to medium sand). Soils reports for individual lots must include at least one **soils log** for each proposed infiltration location. Each log shall be a minimum of 4 feet deep and at least 1 foot below the expected bottom elevation of the infiltrative BMP. The report shall describe the SCS series of the soil and the textural class of each horizon through the depth of the log, and it shall include notes of any evidence of a high groundwater table, such as mottling.
- Evaluation of native soils for determination of groundwater protective characteristics (see Section 5.2.1 "Groundwater Protection" in the *SWDM*) is required in the soils report to demonstrate the feasibility of full infiltration, limited infiltration, and permeable pavement BMPs where treating pollution generating surfaces. This evaluation is not required if treating non-pollution generating surfaces only, or if a water quality facility chosen from the Basic Water Quality Treatment menu in Chapter 6 of the *SWDM* provides treatment prior to infiltration.
- Infiltration testing, as described below, is required to be included in the soils report to demonstrate the feasibility of bioretention and permeable pavement BMPs for the site/lot. The report on infiltration testing should include a recommended correction factor to be applied to the required in-situ, small-scale infiltration test results. The correction factor recommended should be determined by considering the number of infiltration tests performed in relation to the number of bioretention areas and site variability. Correction factors can range from 0.33 to 1 (no correction) and are determined by a geotechnical professional.

Note: For either a single infiltration system or an infiltrative BMP serving:

- more than one lot, 10,000 square feet or more of impervious surface,
- $\frac{3}{4}$ acre or more of pervious surface,
- 5,000 square feet or more of pollution generating impervious surface, OR
- for any infiltrative BMP used in modeling to demonstrate compliance with the LID Performance Standard (see Section 1.2.9 of *SWDM*),

the requirements detailed in Section 5.2.1 of the SWDM shall be met for the following: "Soils, Measured Infiltration Rates, and Design Infiltration Rate." Those sections detail higher level requirements for soils investigation, permeable soil and depth to seasonal high groundwater, determination of initial infiltration

rates, calculation of design infiltration rates, and preparation of soils reports consistent with the larger size and risk associated with these systems.

Infiltration Testing Requirements

The testing procedure described below is for bioretention and permeable pavement serving a single lot, less than 10,000 square feet of impervious area, less than 5,000 square feet of pollution generating impervious surface, less than $\frac{3}{4}$ acre of pervious area, and less than 1 acre total tributary area.

Where required to determine feasibility/infeasibility based on native soil infiltration rates, the following test procedure is required:

Infiltration Testing Procedure

1. Excavations shall be made to the bottom elevation of the proposed infiltration BMP. The measured infiltration rate of the underlying soil shall be determined using one of the following: the **EPA falling head percolation test procedure** (*Onsite Wastewater Treatment and Disposal Systems*, EPA, 1980; see Reference Section 6-A), the **double ring infiltrometer test** (ASTM D3385), a **single ring percolation test** using a ring at least 3 feet in diameter (see Reference Section 6-A), or a small or large scale **Pilot Infiltration Test (PIT)** as described in the 2014 Stormwater Management Manual for Western Washington and Reference Section 6-A of this manual. The larger PIT tests have been shown to more closely match actual full-scale facility performance than the single ring and smaller test methods.
2. The test hole or apparatus shall be filled with water and maintained at depths above the test elevation for the **saturation periods** specified for the appropriate test.
3. Following the saturation period, the rate shall be determined in accordance with the specified test procedures, with a **head** of 6 inches of water.
4. The design engineer shall perform sufficient tests at multiple locations in a proposed BMP footprint to determine a representative infiltration rate. At least one **test** shall be performed (two if using the smaller-sized EPA falling head or ASTM D3385 double ring infiltrometer test methods) for each proposed bioretention BMP location. Proposed bioretention swales require 1 test per 200 linear feet of swale with a minimum of one test (two if using the smaller-sized EPA falling head or ASTM D3385 double ring infiltrometer test methods) performed. Proposed permeable pavement requires 1 test per 5,000 square feet of proposed footprint with a minimum of one tests (two if using the smaller-sized EPA falling head or ASTM D3385 double ring infiltrometer test methods) performed.

☐ MITIGATION OF WATER QUALITY IMPACTS

For projects subject to **Simplified Drainage Review**, most water quality impacts will be adequately addressed through proper application of on-site BMPs to impervious and pervious surface as specified below. Projects in **Simplified Drainage Review** are required to have less than 5,000 square feet targeted **pollution generating impervious surfaces** and less than $\frac{3}{4}$ acres of new **pollution generating pervious surfaces**—therefore, water quality facilities are not required.

C.1.3.1 SMALL LOT BMP REQUIREMENTS

IF the proposed project is on a **site/lot smaller than 22,000 square feet**, THEN on-site BMPs must be applied as specified in the requirements below OR the project must demonstrate compliance with the LID Performance Standard (described in Section 1.2.9 of the *SWDM*) using an approved continuous runoff model. Projects on small lots are typically single family residential improvements (e.g., homes, outbuildings, etc.) but could be a small commercial development.

1. The feasibility and applicability of full dispersion as detailed in Appendix C, Section C.2.1 must be evaluated for all target impervious surfaces. If feasible and applicable, **full dispersion** must be

- implemented as part of the proposed project. Typically, small lot full dispersion will be applicable only in subdivisions where enough forest was preserved by tract, easement, or covenant to meet the minimum design requirements for full dispersion in Appendix C, Section C.2.1.1
2. Where full dispersion of target impervious roof areas is not feasible or applicable, or will cause flooding or erosion impacts, the feasibility and applicability of full infiltration as detailed in Appendix C, Section C.2.2 must be evaluated (*note, this will require a soils report for the site/lot*). If feasible and applicable, **full infiltration of roof runoff** must be implemented as part of the proposed project.
 3. All target impervious surfaces not mitigated by Requirements 1 and 2 above, must be mitigated to the maximum extent feasible using one or more BMPs from the following list. Use of a given BMP is subject to evaluation of its feasibility and applicability as detailed in Appendix C. Feasible BMPs are required to be implemented. The BMPs listed below may be located anywhere on the *site/lot* subject to the limitations and design specifications for each BMP. These BMPs must be implemented as part of the proposed project.
 - **Full Infiltration** per Appendix C, Section C.2.2, or per Section 5.2, whichever is applicable
 - **Limited Infiltration** per Appendix C, Section C.2.3,
 - **Rain Gardens** per Appendix C, Section C.2.12, sized as follows:
 - Rain gardens have a maximum contributing area of 5,000 square feet.
 - Rain gardens must have a minimum horizontal projected surface area below the overflow which is at least 5% of the area draining to it.
 - **Bioretention** per Appendix C, Section C.2.6, sized as follows:
 - Rainfall region SeaTac 1.0: In till soils, provide bioretention volume based on 0.6 inches of equivalent storage depth; in outwash soils provide bioretention volume based on 0.1 inches of equivalent storage depth.
 - Rainfall regions greater than SeaTac 1.0: In till soils, provide bioretention volume based on 0.8 inches of equivalent storage depth; in outwash soils, provide bioretention volume based on 0.4 inches of equivalent storage depth.
 - **Permeable Pavement** per Appendix C, Section C.2.7,
 4. All target impervious surfaces not mitigated by Requirements 1, 2 and 3 above, must be mitigated to the maximum extent feasible using the Basic Dispersion BMP described below. Use of Basic Dispersion is subject to evaluation of its feasibility and applicability as detailed in Appendix C. Feasible BMPs are required to be implemented. Basic Dispersion BMPs may be located anywhere on the *site/lot* subject to the limitations and design specifications cited in Appendix C. The BMP must be implemented as part of the proposed project.
 - **Basic Dispersion** per Appendix C, Section C.2.4,
 5. BMPs must be implemented, at minimum, for an impervious area equal to at least 10% of the *site/lot* for *site/lot* sizes up to **11,000 square feet** and at least 20% of the *site/lot* for *site/lot* sizes between **11,000 and 22,000 square feet**. For projects located in *critical aquifer recharge areas*, these impervious area amounts must be doubled. Doubling of the minimum impervious area required for BMP implementation in a CARA is not required for projects located within 200 ft. of a *steep slope hazard area, landslide hazard, or erosion hazard area*. If these minimum areas are not mitigated using feasible BMPs from Requirements 1, 2, 3, and 4 above, one or more BMPs from the following list are required to be implemented to achieve compliance. These BMPs must be implemented as part of the proposed project.
 - **Reduced Impervious Surface Credit** per Appendix C, Section C.2.9,
 - **Native Growth Retention Credit** per Appendix C, Section C.2.10.
 - **Tree Retention Credit** per Appendix C, Section C.2.14
 6. The soil moisture holding capacity of **new pervious surfaces** (target pervious surfaces) must be protected in accordance with the soil amendment BMP as detailed in Appendix C, Section C.2.13.

7. Any proposed connection of roof downspouts to the *local drainage system* must be via a **perforated pipe connection** as detailed in Appendix C, Section C.2.11.

C.1.3.2 LARGE LOT BMP REQUIREMENTS

IF the proposed project is on a *site/lot* that is **22,000 square feet or larger**, THEN on-site BMPs must be applied as specified in the requirements below OR the project must demonstrate compliance with the LID Performance Standard (described in Core Requirement #9, Section 1.2.9 of the *SWDM*) using an approved continuous runoff model.

1. The feasibility and applicability of **full dispersion** as detailed in Appendix C, Section C.2.1 must be evaluated for all **target impervious surfaces**. If feasible and applicable for any such surface, then full dispersion must be applied to that surface and implemented as part of the proposed project. Typically, full dispersion will be applicable only on the largest *sites/lots* where there may be enough forest area available within a **threshold discharge area** to meet the 15% ratio of **fully dispersed** impervious area to **native vegetated surface**.
2. Where full dispersion of target impervious roof areas is not feasible or applicable, or will cause flooding or erosion impacts, the feasibility and applicability of **full infiltration of roof runoff** must be evaluated in accordance with Appendix C, Section C.2.2, or Section 5.2 of the *SWDM*, whichever is applicable based on the type of project.¹¹ If feasible and applicable, full infiltration of roof runoff must be implemented as part of the proposed project.
3. All target impervious surfaces not mitigated by Requirements 1 and 2 above, must be mitigated to the maximum extent feasible using one or more BMPs from the following list. Use of a given BMP is subject to evaluation of its feasibility and applicability as detailed in Appendix C. Feasible BMPs are required to be implemented. The BMPs listed below may be located anywhere on the site/lot subject to the limitations and design specifications for each BMP. These BMPs must be implemented as part of the proposed project.
 - **Full Infiltration** per Appendix C, Section C.2.2, or per *SWDM* Section 5.2, whichever is applicable
 - **Limited Infiltration** per Appendix C, Section C.2.3,
 - **Bioretention** per Appendix C, Section C.2.6, sized as follows:
 - Rainfall region SeaTac 1.0: In till soils, provide bioretention volume based on 0.6 inches of equivalent storage depth; in outwash soils provide bioretention volume based on 0.1 inches of equivalent storage depth
 - Rainfall regions greater than SeaTac 1.0: In till soils, provide bioretention volume based on 0.8 inches of equivalent storage depth; in outwash soils, provide bioretention volume based on 0.4 inches of equivalent storage depth,
 - **Permeable Pavement** per Appendix C, Section C.2.7,
4. All target impervious surfaces not mitigated by Requirements 1, 2 and 3 above, must be mitigated to the maximum extent feasible using the Basic Dispersion BMP described below. Use of Basic Dispersion is subject to evaluation of its feasibility and applicability as detailed in Appendix C. Feasible BMPs are required to be implemented. Basic Dispersion BMPs may be located anywhere on the *site/lot* subject the limitations and design specifications cited in Appendix C. The BMP must be implemented as part of the proposed project.
 - **Basic Dispersion** per Appendix C, Section C.2.4,

¹¹ For projects subject to Simplified Drainage Review, and for any **single family residential project** subject to Full or Large Project Drainage Review, the design requirements and specifications in Appendix C, Section C.2.2 may be used for evaluation and design of full infiltration on individual lots. For all other projects, full infiltration must be evaluated and designed in accordance with the infiltration facility standards in Section 5.2.

5. BMPs must be implemented, at minimum, for impervious area amounts defined as follows:
- For projects that will result in an impervious surface coverage on the buildable portion of the site/lot of less than 45%, on-site BMPs must be applied to 50% of target impervious surfaces.
 - For projects that will result in an impervious surface coverage of 45% to 65% on the buildable portion of the site/lot, on-site BMPs must be applied to 50% of target impervious surfaces reduced by 1.5% for each 1% of impervious surface coverage above 45% (e.g., impervious coverage of 55% results in a requirement of on-site BMPs applied to 35% of target impervious surfaces). See Table C.1.3.A below for calculated totals.
 - For projects that will result in an impervious surface coverage greater than 65% on the buildable portion of the site/lot, on-site BMPs must be applied to 20% of the target impervious surfaces or to an impervious area equal to at least 10% of the site/lot, whichever is less.

TABLE C.1.3.A ON-SITE BMP APPLICATION RATES		
Impervious Surface Coverage	Reduction	On-Site BMP Application
30%	N/A	50% of target impervious surfaces
35%	N/A	50% of target impervious surfaces
40%	N/A	50% of target impervious surfaces
45%	N/A	50% of target impervious surfaces
50%	50% - 45% = 5% 5% x 1.5% = 7.5%	50% - 7.5% = 42.5% of target impervious surfaces
55%	55% - 45% = 10% 10 x 1.5% = 15%	50% - 15% = 35% of target impervious surfaces
60%	60% - 45% = 15% 15 x 1.5% = 22.5%	50% - 22.5% = 27.5% of target impervious surfaces
65%	65% - 45% = 20% 20 x 1.5% = 30%	50% - 30% = 20% of target impervious surfaces
70%	70% - 45% = 25% 25 x 1.5% = 37.5%	50% - 37.5% = 12.5% of target impervious surfaces
75%	75% - 45% = 30% 30 x 1.5% = 45%	50% - 45% = 5% of target impervious surfaces
80%	N/A	N/A
85%	N/A	N/A

The buildable portion of the site/lot is the total area of the site/lot minus any critical areas and minus 200-foot buffer areas from a *steep slope hazard area*, *landslide hazard*, or *erosion hazard area*. If these minimum areas are not mitigated using feasible BMPs from Requirements 1, 2, 3, and 4 above,

one or more BMPs from the following list are required to be implemented to achieve compliance. These BMPs must be implemented as part of the proposed project.

- **Reduced Impervious Surface Credit** per Appendix C, Section C.2.9,
 - **Native Growth Retention Credit** per Appendix C, Section C.2.10,
 - **Tree Retention Credit** per Appendix C, Section C.2.14.
6. The soil moisture holding capacity of **new pervious surfaces** must be protected in accordance the soil amendment BMP as detailed in Appendix C, Section C.2.13.
 7. Any proposed connection of roof downspouts to the *local drainage system* must be via a **perforated pipe connection** as detailed in Appendix C, Section C.2.11.

C.1.3.3 LARGE RURAL LOT BMP REQUIREMENTS

This requirement does not apply in the City of Renton.¹²

C.1.3.4 ON-SITE BMP IMPLEMENTATION REQUIREMENTS

The on-site BMPs required in Section C.1.3.1, C.1.3.2, and C.1.3.3 above must be implemented in accordance with the following requirements:

1. **Implementation Responsibility.** All on-site BMPs required for the *site/lot* must be implemented (installed) by the applicant as part of the proposed project unless they have already implemented as part of a subdivision project (e.g., plat or short plat) that created the lot.
2. **Maintenance Responsibility.** Maintenance of all required on-site BMPs is the responsibility of the owner of the *site/lot* served by these BMPs. The responsibility for such maintenance must be clearly assigned to the current and future owners of the *site/lot* through a “declaration of covenant and grant of easement” as described in Requirement 3 below.
3. **Declaration of Covenant and Grant of Easement.** A declaration of covenant and grant of easement must be recorded for each *site/lot* that contains on-site BMPs. A draft of the proposed covenant must be reviewed and approved by CED prior to recording. All required covenants must be recorded prior to final construction approval for the proposed project. The covenant in Reference Section C.5.2 (or equivalent) must be used, and is designed to achieve the following:
 - a) Provide **notice** to future owners of the presence of on-site BMPs on the lot and the responsibility of the owner to retain, uphold, and protect the on-site BMP devices, features, pathways, limits, and restrictions.
 - b) Include as an **exhibit**, a *recordable version*¹³ of the following drainage plan information:
 - The **site plan** showing all developed surfaces (impervious and pervious) and the location and dimensions of on-site BMPs, features, flowpaths (if applicable), and limits of native growth retention areas (if applicable). This plan(s) must be to scale and include *site* topography in accordance with the specifications for such plans in Section C.4.2. Also indicate any areas where City access is excluded (see paragraph 3.d below). *Note: CED may waive this element if, for example, the only on-site BMP proposed is a limit on impervious surface (reduced footprint).*
 - The **on-site BMP design and maintenance details** for each on-site BMP per Section C.4.3. This includes a diagram (if applicable) of each on-site BMP and written maintenance and

¹² Footnote 12 is not used.

¹³ *Recordable version* means one that meets King County’s “Standard Formatting Requirements for Recording Documents” pursuant to RCW 36.18.010 and 65.04.045, available online and from the King County Recorder’s Office. These requirements include specifications for such things as page size (8½” x 14” or smaller), font size (at least 8-point), and margin width (1” on all sides of every page if there is a standard cover sheet).

operation instructions and restrictions for each device, feature, flowpath (if applicable), native growth retention area (if applicable) and impervious surface coverage (if applicable). See Reference Section 8-M for prepared 8-1/2" x 11" maintenance instruction sheets. See <http://rentonwa.gov/government/default.aspx?id=7122> for downloadable BMP details. Ensure the exhibits are correctly cross-referenced in the declaration of covenant (the site plan is typically Exhibit A and the design/maintenance details are typically Exhibit B).

- c) Require that each on-site BMP be operated and **maintained at the owner's expense** in accordance with the above exhibit.
- d) Grant the City or its successor the **right to enter** the property at reasonable times for purposes of inspecting the on-site BMPs and to perform any corrective maintenance, repair, restoration, or mitigation work on the on-site BMPs that has not been performed by the property owner within a reasonable time set by CED, and to charge the property owner for the cost of any maintenance, repair, restoration, or mitigation work performed by the City.

The right to enter typically applies to the entire property, but occasionally accepts areas on the property agreed upon by the City to be excluded from access. Such areas are to be shown on the site plan described above.

- e) Prohibit any **modification or removal** of on-site BMPs without written approval from the City of Renton. In cases where the modification or removal is done under a City of Renton development permit, the approval must be obtained from CED (or its successor) and a covenant must be recorded to reflect the changes. In all other cases, the approval must be obtained from CED and a covenant must be recorded to reflect the changes. Approval will be granted only if equivalent protection in terms of hydrologic performance is provided by other means.
4. **Timing of Implementation.** All required on-site BMPs must be installed prior to final inspection approval of constructed improvements. For BMPs that rely on vegetation, the vegetation must be planted and starting to grow prior to final construction approval.
 5. **Acceptance Standards.** On-site BMPs may be inspected during and/or following construction. Approval of the constructed BMPs will be based on verification that the materials and placement appear to meet the specifications and that the BMPs appear to function as designed. Onsite observations may be used to verify that materials are as specified and material receipts checked. Performance may be evaluated by a *site* visit while it is raining or by testing with a bucket of water or garden hose to check pavement permeability or proper connection to BMP devices/features, etc.
 6. **Drainage Concerns.** If CED determines that there is a potential for drainage impacts to a neighboring property or critical area, then additional measures may be required. Some on-site BMPs may not be appropriate in certain situations, and will not be allowed by CED where they may cause drainage problems.
 7. **Geotechnical Concerns.** A geotechnical engineer, engineering geologist, or CED must evaluate and approve on-site BMPs that are proposed: (A) on slopes steeper than 15%; (B) within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15%; or (C) within 200 feet of a **steep slope hazard area, erosion hazard area, or landslide hazard**. In addition, CED may require review by a geotechnical engineer or engineering geologist of any proposed BMP that infiltrates, disperses, or directs overflow adjacent to or towards a **steep slope hazard area, erosion hazard area, or landslide hazard**. CED may also require some projects to route flows down or around such slopes using non-perforated pipes. Some on-site BMPs may not be appropriate for these locations, and will not be allowed by CED where flows may cause erosion problems.
 8. **Sewage System Concerns.** If CED determines that there is a potential conflict between onsite sewage systems and on-site BMPs, additional measures may be required. Some projects may need to route flows past onsite sewage systems using non-perforated pipes. Also, some on-site BMPs may not be appropriate for these *sites*, and will not be allowed where sewage systems may be impacted.

9. **Engineering Concerns.** While most of the on-site BMPs in this appendix can be implemented by a non-engineer, there are some that have structural components that must be designed or evaluated by a *civil engineer* or *structural engineer*.¹⁴ When a BMP is proposed that has such components as identified in Section C.2, CED may require submittal of engineering plans for that component signed and stamped by a *civil engineer* or structural engineer.
10. **Connection to Subsurface Drains.** On-site BMPs **should not** be connected to subsurface drains (e.g., footing drains) as these connections may adversely affect the performance of the BMPs, and in some cases may cause reverse flow into the footing drains during storm events.
11. **Simplified Drainage Plan.** The type, size, and placement of proposed on-site BMPs are to be shown on the **site plan** submitted for the proposed project. This plan must be in accordance with the specifications for such plans outlined in Section C.4 unless otherwise directed by CED.

C.1.4 APPLICATION OF CSWPP MEASURES

It is the responsibility of both the applicant and contractor to prevent the erosion and transport of sediment and other construction-related pollutants to the maximum extent practicable. Erosion and sediment control (ESC) measures and stormwater pollution prevention and spill control (SWPPS) measures must be used both during and after construction as specified in this section.

For projects subject to Simplified Drainage Review and disturbing less than 1 acre of land, the application of ESC and SWPPS measures must be in accordance with the “Small Site CSWPP Requirements” in Section C.1.4.1 and the “CSWPP Implementation Requirements” in Section C.1.4.2. The CSWPP Simplified Site Requirements specify the types of measures that must be considered for application to the construction site based on project-specific *site* features, soil conditions, weather conditions, time of year, and construction activities. The CSWPP implementation requirements are generally applicable to all projects in Simplified Drainage Review disturbing less than 1 acre.

C.1.4.1 SMALL SITE CSWPP REQUIREMENTS

For projects in **Simplified Drainage Review** that disturb less than 1 acre of land, all of the following Small Site ESC and SWPPS requirements must be evaluated for applicability to the proposed project:

A. MARK CLEARING LIMITS/MINIMIZE CLEARING

Prior to beginning land disturbing activities, all clearing limits, sensitive areas and their buffers, and trees that are to be preserved within the construction area and any existing or proposed LID facility areas shall be clearly marked, both in the field and on the **Small Site CSWPP plan**, to prevent damage and offsite impacts. Also, clearing shall be minimized to the maximum extent practicable. See “**Mark Clearing Limits/Minimize Clearing**,” Section C.3.5, for more detailed specifications.

B. MINIMIZE SEDIMENT TRACKED OFFSITE

1. Establish a stabilized entrance for construction vehicle access to minimize the tracking of sediment onto public roads. Entrance and exit shall be limited to one route, if possible. See “**Stabilized Construction Entrance**,” Section C.3.1, for detailed specifications.
2. If sediment is tracked offsite, public roads shall be cleaned thoroughly at the end of each day, or more frequently during wet weather, if necessary to prevent sediment from entering waters of the state. Sediment shall be removed from roads by shoveling or pickup sweeping and shall be transported to a controlled sediment disposal area. Street washing will be allowed only after sediment is removed in this manner. Street wash wastewater shall be controlled by pumping back onsite, or otherwise be

¹⁴ *Structural engineer* means a person licensed by the State of Washington as a professional civil engineer specializing in structural engineering.

prevented from discharging into drainage systems tributary to surface waters. This requirement **shall be included as a note** on the **Small Site CSWPP plan**.

C. CONTROL SEDIMENT

Runoff from disturbed areas must pass through a sediment control measure to prevent the transport of sediment downstream until the disturbed area is fully stabilized. Sediment controls must be installed as one of the first steps in grading and shall be functional before other land disturbing activities take place. One or more the following sediment controls may be used to meet this requirement:

- Silt Fence (See Section C.3.6)
- Vegetated Strip (See Section C.3.7)
- Triangular Silt Dike (See Section C.3.8)
- Storm Drain Inlet Protection (See Section C.3.9)

D. STABILIZE EXPOSED SOILS

All exposed and unworked soils shall be stabilized through the application of **cover measures** to protect the soil from the erosive forces of raindrop impact, flowing water, and wind erosion. One or more of the following **cover measures** may be used to meet this requirement during the construction phase:

- **Mulching** (See Section C.3.2)
- **Nets and Blankets** (See Section C.3.3)
- **Plastic Covering** (See Section C.3.4)
- **Seeding** (See Section C.3.10)
- **Sodding** (See Section C.3.11)

Cover measures shall be **applied in accordance with the following requirements**:

1. Cover measures must be installed if an area is to remain unworked for more than seven days during the dry season (May 1 to September 30) or for more than two consecutive working days during the wet season (October 1 to April 30). These time limits may be relaxed if an area poses a low risk of erosion due to soil type, slope gradient, anticipated weather conditions, or other factors. Conversely, the City may reduce these time limits if site conditions warrant greater protection (e.g., adjacent to significant aquatic resources or highly erosive soils) or if significant precipitation is expected.
2. Any area to remain unworked for more than 30 days shall be seeded or sodded unless the City determines that winter weather makes vegetation establishment infeasible. During the wet season, exposed ground slopes and stockpile slopes with an incline of 3 horizontal to 1 vertical (3H:1V) or steeper and with more than ten feet of vertical relief shall be covered if they are to remain unworked for more than 12 hours. Also during the wet season, the material necessary to cover all disturbed areas must be stockpiled on site. The intent of these cover requirements is to have as much area as possible covered during any period of precipitation.

E. CONTROL RUNOFF

Stormwater runoff originating on the *site* and/or entering the *site* from offsite areas must be controlled so as to minimize erosion of disturbed areas and exposed cut and fill slopes, and to minimize erosive impacts on existing or proposed LID facility areas. The following runoff control measures shall be used as needed per the conditions of use and specifications for each measure:

- **Interceptor Dikes and Swales** (see Section C.3.12 for conditions of use and specifications)
- **Ditches** (see Section C.3.13 for conditions of use and specifications)
- **Pipe Slope Drain** (see Section C.3.14 for conditions of use and specifications)

F. CONTROL DEWATERING

Accumulated water in foundation areas, excavations, and utility trenches shall be removed and disposed of in a manner that does not pollute surface waters or cause downstream erosion or flooding. See “**Dewatering Control**,” Section C.3.15 for detailed specifications.

G. CONTROL OTHER POLLUTANTS (SWPPS)

All construction activities shall be done in a manner that prevents pollution of surface waters and ground waters as specified in the *Construction Stormwater Pollution Prevention Standards* (detached Appendix D of the *SWDM*) and King County’s *Stormwater Pollution Prevention Manual (SPPM)*. See “**Control of Other Pollutants (SWPPS)**,” Section C.3.16, for specific measures and references to Appendix D and applicable activity sheets in the *SPPM*. References to applicable measures in Appendix D and activity sheets in *SPPM* shall be included in the **Small Site CSWPP plan**.

H. PROTECT EXISTING AND PROPOSED STORMWATER FACILITIES AND ON-SITE BMPS

Protection measures shall be applied/installed and maintained so as to prevent adverse impacts to existing stormwater facilities and on-site BMPs and areas of proposed stormwater facilities and on-site BMPs for the project. Adverse impacts can prompt the requirement to restore or replace affected stormwater facilities and on-site BMPs.

Purpose: The purpose of protecting existing and proposed stormwater facility and on-site BMP areas is to avoid sedimentation and soil compaction that would adversely affect infiltration, and also avoid contamination by other pollutants.

When to Install: Stormwater facility and on-site BMP area protection shall be installed or otherwise provided prior to any clearing and/or grading of the site, except that required to construct stormwater facilities and on-site BMPs.

Measures to Use:

1. Protect all stormwater facilities and on-site BMPs and proposed stormwater facility and on-site BMP footprints from sedimentation through installation and maintenance of erosion and sediment control BMPs on portions of the site that drain into the stormwater facilities and on-site BMPs.
2. Stormwater facilities and on-site BMPs shall be restored to their fully functioning condition if they accumulate sediment during construction. Restoring the stormwater facilities and on-site BMPs shall include, at a minimum, removal of sediment and any sediment-laden bioretention soils, and replacing the removed soils with soils meeting the design specification. Replacement with a new fully-functioning stormwater facility and/or on-site BMP may be required if restoration to the fully-functioning condition can’t be accomplished.
3. Prevent compacting Bioretention BMPs/facilities by excluding construction equipment and foot traffic. Protect completed lawn and landscaped areas from compaction due to construction equipment.
4. Control erosion and avoid introducing sediment from surrounding land uses onto permeable pavement BMPs. Do not allow muddy construction equipment on the base material or pavement. Do not allow sediment-laden runoff onto permeable pavements.
5. Permeable pavement BMPs fouled with sediments or no longer passing an initial infiltration test must be cleaned using procedures from Appendix A or the manufacturer’s procedures.
6. Keep all heavy equipment off existing soils under stormwater facilities and on-site BMPs that have been excavated to final grade to retain the infiltration rate of the soils.

I. MAINTAIN BMPS DURING CONSTRUCTION AND FINAL SITE STABILIZATION

1. TESC BMPs shall be maintained and repaired as needed throughout construction to ensure continued performance of their intended function in accordance with the BMP specifications.
2. Prior to final construction approval, the *project site* shall be stabilized to prevent sediment-laden water from leaving the *project site* after project completion. All disturbed areas of the *project site* shall be vegetated or otherwise permanently stabilized. At a minimum, disturbed areas must be seeded and mulched to ensure that sufficient cover will develop shortly after final approval. Mulch without seeding is adequate for small areas to be landscaped before October 1.
3. All temporary ESC and SWPPS measures shall be removed within 30 days after final site stabilization is achieved or after the temporary measures are no longer needed. Trapped sediment shall be removed or stabilized onsite. LID facilities impacted during construction shall be restored. Disturbed soil areas resulting from removal of measures or vegetation shall be permanently stabilized with seeding or sodding.

C.1.4.2 CSWPP IMPLEMENTATION AND MANAGEMENT REQUIREMENTS

Projects in **Simplified Drainage Review** that disturb less than 1 acre of land must implement the CSWPP measures determined necessary in Section C.1.4.1 in accordance with the following requirements:

1. The placement and type of proposed ESC and SWPPS measures are to be shown on the **Small Site CSWPP plan** portion of the Simplified Drainage Plan submitted for the proposed project. This plan must be in accordance with the specifications for such plans outlined in Section C.4 unless otherwise directed by CED.
2. If CED finds that implementation of the proposed **Small Site CSWPP plan is insufficient** to prevent the discharge of sediment or other pollutants to the maximum extent practicable, additional measures will be required by CED. In some cases, an ESC plan or a complete Construction Stormwater Pollution Plan prepared by a *civil engineer* per Chapter 2 of the *SWDM* may be required.
3. The contractor or other persons performing construction activities shall comply with the **stormwater pollution prevention and spill control measures/BMPs** specified for such activities in Appendix D and/or the King County *Stormwater Pollution Prevention Manual*. A note to this effect must be put on the approved CSWPP plan.
4. Prior to commencing construction, the applicant must identify to the City a **contact person** responsible for overseeing the installation and maintenance of required ESC and SWPPS measures and compliance with Appendix D and the *Stormwater Pollution Prevention Manual* during construction. The name and contact information for this person must be on or attached to **Small Site CSWPP plan** at the time of construction.
5. Both the **applicant and contractor are responsible** for implementation and maintenance of the approved **Small Site CSWPP plan** and any additional measures required by the City.
6. The **Small Site CSWPP plan shall be retained onsite** or within reasonable access to the site. The plan shall be modified whenever there is a significant change in the design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to surface waters. The plan shall be modified, if during inspections or investigations conducted by the City, it is determined that the plan is ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site. The plan shall be modified as necessary to include additional or modified measures designed to correct problems identified.

C.1.5 SIMPLIFIED SUBMITTAL REQUIREMENTS

For projects in **Simplified Drainage Review**, the items listed below must be submitted to CED for review unless the item is not applicable or necessary as specified for that item below or as determined by CED. See Section C.5.1 for a description of the CED permit review process for Simplified Drainage Review.

1. A **Simplified Drainage Plan**, which includes the components specified in Section C.4 unless otherwise directed by CED. These components vary depending on whether the project is an individual lot development or a subdivision. For most projects in **Simplified Drainage Review** (i.e., individual lot projects), the required components of a Simplified Drainage Plan include a site plan, on-site BMP design and maintenance details, a **Small Site CSWPP plan**, and a written drainage assessment with supporting documentation (e.g., soils report, special studies, etc.).

Note: subdivisions in Simplified Drainage Review that do not require engineering plans or analysis will typically be asked to complete Simplified Drainage Plans prior to preliminary approval of the subdivision. Projects submitting Simplified Drainage Plans after preliminary approval must include in the written assessment a discussion of any changes made to the project after preliminary approval.

2. A draft of the **declaration of covenant and grant of easement** required to be recorded for application of on-site BMPs on an individual *site/lot* in accordance with Requirement 3 of Section C.1.3.4.
3. A copy of any **recorded covenant** that limits the amount of impervious surface or clearing on the *site* for purposes of qualifying for **Simplified Drainage Review**. If one does not exist or does not include provisions for City inspection, it must be combined with the covenant required for application of on-site BMPs.
4. An **engineering plan** and **technical information report** signed and stamped by a *civil engineer* if needed to address targeted drainage review requirements identified in Section C.1.1 and described in Section 0. The specifications for such plans and reports are found in Chapter 2 of the *SWDM*.

C.2 ON-SITE BMPS

This section presents the minimum design requirements, specifications, and infeasibility criteria for each type of on-site BMP. *On-site BMPs* are methods and designs for dispersing, infiltrating, or otherwise reducing or preventing development-related increases in runoff at or near the sources of those increases. On-site BMPs include, but are not limited to, preservation and use of *native vegetated surface* to fully disperse runoff; use of other pervious surfaces to disperse runoff; roof downspout infiltration; permeable pavements; rainwater harvesting; rain gardens; bioretention; and reduction of development footprint.

Intent of On-Site BMPS

The primary intent of on-site BMPs is to mitigate the hydrologic impacts of impervious surface, which means preventing or reducing the increased runoff peaks, volumes, and loss of groundwater recharge associated with conversion of forest or grassland to impervious surface. Such impacts are known to cause or contribute to downstream flooding, erosion, sedimentation, loss of aquatic habitat, and loss of groundwater available for human consumption and summer stream flows necessary for fish use.

The secondary intent of on-site BMPs is to mitigate the water quality impacts of impervious surface and in some cases, *new pervious surface*, where the *new pervious surface* exceeds $\frac{3}{4}$ acre.

Some on-site BMPs are more effective than others at minimizing hydrologic impacts and are given preference in the BMP application requirements. For example, where substantial amounts of native vegetation are being retained onsite, “full dispersion” of runoff is the preferred or required BMP if it can be implemented onsite per the minimum design requirements and specifications in Section C.2.1.

Organization of Section C.2

Section C.2 is organized as follows:

- Section C.2.1, “Full Dispersion”
- Section C.2.2, “Full Infiltration”
- Section C.2.3, “Limited Infiltration”
- Section C.2.4, “Basic Dispersion”
- Section C.2.5, “Farmland Dispersion”
- Section C.2.6, “Bioretention”
- Section C.2.7, “Permeable Pavement”
- Section C.2.8, “Rainwater Harvesting”
- Section C.2.9, “Reduced Impervious Surface Credit”
- Section C.2.10, “Native Growth Retention Credit”
- Section C.2.11, “Perforated Pipe Connection”
- Section C.2.12, “Rain Gardens”
- Section C.2.13, “Soil Amendment”
- Section C.2.14, “Tree Retention Credit”
- Section C.2.15, “Vegetated Roofs”

C.2.1 FULL DISPERSION

Full dispersion is a BMP strategy for minimizing the area of onsite developed surface (i.e., impervious or nonnative pervious surface) relative to *native vegetated surface* (e.g., forested surface) together with the application of dispersion techniques that utilize the natural capacity of the *native vegetated surface* to mitigate the runoff quantity and quality impacts of the developed surfaces. Developed surfaces that meet the minimum design requirements and specifications for full dispersion as set forth in this section are

referred to as *fully dispersed surfaces*. As specified in the *SWDM*, fully dispersed impervious surface is not subject to the “flow control facility requirement.” Similarly, any *pollution-generating impervious surface* or pervious surface that is fully dispersed is not subject to the water quality facility requirements of the *SWDM*.

Applicable Surfaces

Full dispersion may be applied to any impervious surface such as a roof, driveway, parking area, or road, and to any nonnative pervious surface such as a lawn, landscaped area, or pasture.

Infeasibility Criteria

Full dispersion is considered infeasible and not required for projects that cannot meet the minimum design requirements listed below. Where geotechnical evaluation and approval is required for full dispersion that proposes to discharge towards or is within described setbacks of a *steep slope hazard area, erosion hazard area, landslide hazard, or slopes greater than 15%*, full dispersion is considered infeasible and not required. Though not required in these circumstances, a project proponent may still opt to use full dispersion as long as the geotechnical evaluation and approval requirement is met.

Operation and Maintenance

See Section C.2.1.9.

C.2.1.1 MINIMUM DESIGN REQUIREMENTS FOR FULL DISPERSION

All of the following requirements must be met in order for full dispersion to be feasible and applicable to a *target impervious surface* or *new pervious surface*:

1. The **total area of impervious surface** being fully dispersed must be no more than 15% of the total area of *native vegetated surface* being preserved by a recorded tract, easement, or covenant on the *site*. This area of *native vegetated surface* must be delineated on the *site* as specified in and subject to the restrictions in Section C.2.1.2. The total area of impervious surface plus *nonnative pervious surface*¹⁵ being fully dispersed must be no more than 35% of the *site*.

Note: for sites that span the divide between two or more stream basins, CED may require that these percentages be applied by “threshold discharge area” as defined in the SWDM.

2. The runoff from a fully dispersed surface must be discharged using one of the following **dispersion devices** in accordance with the design specifications and maximum area of fully dispersed surface for each device as set forth in Sections C.2.1.3 through C.2.1.6:
 - Splash blocks (see Section C.2.1.3)
 - Rock pads (see Section C.2.1.4)
 - Gravel filled trenches (see Section C.2.1.5)
 - Sheet flow (see Section C.2.1.6)
3. A **native vegetated flowpath segment** of at least 100 feet in length (25 feet for sheet flow from a nonnative pervious surface) must be available along the flowpath that runoff would follow upon discharge from a dispersion device listed in Minimum Design Requirement 2 above. The native vegetated flowpath segment **must meet all of the following criteria**:
 - a) The flowpath segment must be over *native vegetated surface*.
 - b) The flowpath segment must be **onsite** or in an **offsite tract or easement area** reserved for such dispersion.

¹⁵ *Nonnative pervious surface* means a pervious surface that does not meet the definition of a *native vegetated surface* and is not a natural water body or critical area.

- c) The **slope** of the flowpath segment must be no steeper than 15% for any 20-foot reach of the flowpath segment.
 - d) The flowpath segment must be located between the dispersion device and any **downstream drainage feature** such as a pipe, ditch, stream, river, pond, lake, or wetland. All or a portion of the flowpath segment may be located within a critical area buffer.
 - e) The flowpath segments for adjacent dispersion devices must be sufficiently spaced in order to prevent overlap of flows in the segment areas. The **minimum spacing** between flowpath segments is specified for each dispersion device in subsequent sections, and includes an exception made in cases where sheet flow from a nonnative pervious surface overlaps with other flowpath segments.
4. For **sites** with **septic systems**, the discharge of runoff from dispersion devices must be located down slope of the primary and reserve drainfield areas. CED review staff can waive this requirement if site topography clearly prohibits discharged flows from intersecting the drainfield.
 5. Dispersion devices are not allowed in critical area **buffers** (unless approved by CED) or on **slopes** steeper than 20%.
 6. Dispersion devices are not allowed within 50 feet of a **steep slope hazard area, erosion hazard area, or landslide hazard**.
 7. Dispersion devices proposed on slopes steeper than 15% must be approved by a **geotechnical engineer or engineering geologist** unless otherwise approved by the CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
 8. Dispersion devices proposed near slopes steeper than 15% must be approved by a **geotechnical engineer or engineering geologist** unless otherwise approved by the CED if the facility is located within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15%. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
 9. Dispersion devices that direct runoff toward a slope steeper than 15% may require evaluation and approval of the proposal by a **geotechnical engineer or engineering geologist** as determined by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
 10. Dispersion devices proposed within 200 feet of a **steep slope hazard area, erosion hazard area, or landslide hazard** must be approved by a **geotechnical engineer or engineering geologist** unless otherwise approved by the CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
 11. The dispersion of runoff must not create **flooding or erosion impacts** as determined by the CED. If runoff is discharged toward a **landslide hazard, erosion hazard area, or steep slope hazard area**, CED may require evaluation and approval of the proposal by a **geotechnical engineer or engineering geologist**. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.

C.2.1.2 DELINEATION OF NATIVE VEGETATED AREA FOR FULL DISPERSION

The area of **native vegetated surface** used for full dispersion must be delineated as a “**native growth retention area**” on the site plan that will be attached to the required declaration of covenant and grant of easement per Requirement 3 of Section C.1.3.4. Delineation of the native growth retention area is subject to the following **restrictions**:

1. The principle restriction on native growth retention areas is **removal of vegetation and trees**. All trees within the native growth retention area at the time of permit application shall be retained, aside from approved timber harvest activities and the removal of dangerous and diseased trees.
2. The native growth retention area may include any *unsubmerged*¹⁶ critical areas and any critical area buffers.
3. The native growth retention area may include previously cleared areas replanted by the proposed project in accordance with the **native vegetated landscape** specifications in Section C.2.1.8.
4. The native growth retention area **may be used for passive recreation** and related facilities, including pedestrian and bicycle trails, nature viewing areas, fishing and camping areas, and other similar activities that do not require permanent structures, provided that cleared areas and areas of compacted soil associated with these areas and facilities do not exceed eight percent of the native growth retention area.
5. The native growth retention area **may contain utilities and utility easements**, including other on-site BMPs, but not septic systems.

C.2.1.3 USE OF SPLASH BLOCKS FOR FULL DISPERSION

Splash blocks such as that shown in Figure C.2.1.A may be used to disperse the runoff collected from small amounts of roof area and discharged via a downspout.

Design Specifications

1. No more than 700 square feet of roof area may be drained to a single splash block unless the native vegetated flowpath segment is longer than the 100-foot minimum length specified in Minimum Design Requirement 3 of Section C.2.1.1.
2. A maximum roof area of 1,400 square feet may be discharged to a single splash block if the native vegetated flowpath segment is at least 200 feet in length.
Note: for roof areas larger than 700 square feet, the splash block should be located away from building or other provisions should be made to prevent flooding/erosion problems.
3. For roof areas of between 700 square feet and 1,400 square feet, the length of the flowpath segment may vary proportionally between 100 and 200 feet.
4. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the native vegetated flowpath segment for the splash block must have at least 50 feet of separation from an adjacent flowpath segment at the downstream end of whichever segment is the shorter. **Exception:** where sheet flow from a nonnative pervious surface overlaps with the flowpath of a splash block, the splash block flowpath segment must be extended at least 1 foot for every 3 feet of nonnative pervious surface area **width** draining to the same flowpath.

Note that width is measured in the general direction that runoff flows across the nonnative pervious surface.

C.2.1.4 USE OF ROCK PADS FOR FULL DISPERSION

Pads of crushed rock, 2 feet wide (perpendicular to flow) by 3 feet long by 6 inches deep, may be used as a dispersion device to discharge small amounts of concentrated runoff from impervious surface or nonnative pervious surface.

¹⁶ *Unsubmerged* means outside the ordinary high water mark of streams, lakes, and wetlands.

Design Specifications

1. No more than 700 square feet of impervious surface may be drained to a single rock pad unless the native vegetated flowpath segment is longer than the 100-foot minimum length specified in Minimum Design Requirement 3 of Section C.2.1.1. If the developed surface is nonnative pervious surface other than pasture, no more than 2,500 square feet may be drained to a single rock pad with a 100-foot native vegetated flowpath segment. For pasture, the maximum is 8,000 square feet. Combinations of different surfaces draining to a single rock pad are allowed provided that the sum of each surface area divided by its maximum (e.g., impervious area divided by 700) is less than or equal to 1.0.
2. A maximum impervious surface area of 1,400 square feet may be drained to a single rock pad if the native vegetated flowpath segment is at least 200 feet in length. For nonnative pervious surface other than pasture, the maximum area is 5,000 square feet. For pasture, the maximum is 16,000 square feet. Again, combinations of different surfaces are allowed as explained in Item 1 above.
3. For impervious surface areas of between 700 and 1,400 square feet, the length of the flowpath segment may vary proportionally between 100 and 200 feet. This variation is also allowed for nonnative pervious surfaces (i.e., between 2,500 and 5,000 square feet for surfaces other than pasture, and between 8,000 and 16,000 square feet for pasture).
4. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the native vegetated flowpath segment for the rock pad must have at least 50 feet of separation from an adjacent flowpath segment at the downstream end of whichever segment is the shorter. **Exception:** where sheet flow from a nonnative pervious surface overlaps with the flowpath of a rock pad, the rock pad flowpath segment must be extended at least 1 foot for every 3 feet of nonnative pervious surface area **width** draining to the same flowpath.

Note that width is measured in the general direction that runoff flows across the nonnative pervious surface.

C.2.1.5 USE OF GRAVEL FILLED TRENCHES FOR FULL DISPERSION

Either of the two types of gravel filled trenches (also called “**dispersion trenches**”) shown in Figure C.2.1.C and Figure C.2.1.D may be used as a dispersion device to spread the discharge of concentrated runoff from any type of developed surface.

General Design Specifications

1. All trenches are filled with $\frac{3}{4}$ -inch to $1\frac{1}{2}$ -inch washed rock.
2. In outwash soils, a treatment liner to protect groundwater quality per Section 6.2.4 should be provided underneath the trench.
3. All trenches must be placed at least 10 feet from any building and must be as parallel as possible to the contour of the ground.
4. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the outer edge of the native vegetated flowpath segment for the dispersion trench must have at least 50 feet of separation from an adjacent flowpath segment at the downstream end of whichever segment is the shorter. **Exception:** where sheet flow from a nonnative pervious surface overlaps with the flowpath of a dispersion trench, the dispersion trench flowpath segment must be extended at least 1 foot for every 3 feet of nonnative pervious surface area **width** draining to the same flowpath.

Note that width is measured in the general direction that runoff flows across the nonnative pervious surface.

Design Specifications for Simple 10-Foot Trench (Full Dispersion)

1. The simple 10-foot-long trench illustrated in Figure C.2.1.B and Figure C.2.1.C (must be at least 2 feet wide by 18 inches deep).
2. The 10-foot trench length is the maximum allowed without a notch grade board as shown in Figure C.2.1.D.
3. No more than 1,400 square feet of impervious area may be drained to a single 10-foot trench unless the native vegetated flowpath segment is longer than the 100-foot minimum length specified in Minimum Design Requirement 3 of Section C.2.1.1. If the developed surface is nonnative pervious surface other than pasture, no more than 5,000 square feet may be drained to a single 10-foot trench with a 100-foot native vegetated flowpath segment. For pasture, the maximum is 16,000 square feet. Combinations of different surfaces draining to a single 10-foot trench are allowed provided that the sum of each surface area divided by its maximum (e.g., impervious area divided by 1,400) is less than or equal to 1.0.
4. A maximum impervious surface area of 2,800 square feet may be drained to a single 10-foot trench if the native vegetated flowpath segment is at least 200 feet in length. For nonnative pervious surface other than pasture, the maximum area is 10,000 square feet. For pasture, the maximum is 32,000 square feet. Again, combinations of different surfaces are allowed as explained in Item 3 above.
5. For impervious surface areas of between 1,400 and 2,800 square feet, the length of the flowpath segment may vary proportionally between 100 and 200 feet. This variation is also allowed for nonnative pervious surfaces (i.e., between 5,000 and 10,000 square feet for surfaces other than pasture, and between 16,000 and 32,000 square feet for pasture).

Design Specifications for 50-Foot Trench with Notch Board (Full Dispersion)

1. The 50-foot-long trench with notch grade board detailed in Figure C.2.1.D must be at least 2 feet wide by 24 inches deep.
2. The 50-foot trench length is the longest allowed.
3. No more than 5,000 square feet of impervious area may be drained to a single 50-foot trench unless the native vegetated flowpath segment is longer than the 100-foot minimum length specified in Minimum Design Requirement 3 of Section C.2.1.1. If the developed surface is nonnative pervious surface other than pasture, no more than 17,500 square feet may be drained to a single 50-foot trench with a 100-foot native vegetated flowpath segment. For pasture, the maximum is 1.25 acres (54,450 square feet). Combinations of different surfaces draining to a single 50-foot trench are allowed provided that the sum of each surface area divided by its maximum (e.g., impervious area divided by 5,000) is less than or equal to 1.0.
4. A maximum impervious surface area of 10,000 square feet may be drained to a single 50-foot trench if the native vegetated flowpath segment is at least 200 feet in length. For nonnative pervious surface other than pasture, the maximum area is 35,000 square feet. For pasture, the maximum is 2.5 acres (108,900 square feet). Again, combinations of different surfaces are allowed as explained in Item 3 above.
5. For between 5,000 square feet and 10,000 square feet of impervious area, the length of the flowpath segment may vary proportionally between 100 and 200 feet for a 50-foot trench. The trench length may also vary proportionally between the 10-foot trench values above and the 50-foot values given here. For impervious surface areas of between 5,000 and 10,000 square feet, the length of the flowpath segment may vary proportionally between 100 and 200 feet. This variation is also allowed for nonnative pervious surfaces (i.e., between 17,500 and 35,000 square feet for surfaces other than pasture, and between 1.25 and 2.5 acres for pasture).
6. Manifolds may be used to split flows between up to four 50-foot trenches.

C.2.1.6 USE OF SHEET FLOW FOR FULL DISPERSION

Sheet flow, as a dispersion device, is the grading of a developed surface (either a strip of impervious surface or a patch of nonnative pervious surface) as needed to avoid the concentration of runoff before and after discharge from the surface. Two types of sheet flow, one for impervious surface and one for pervious surface, are detailed below.

Design Specifications for Impervious Surface Sheet Flow (Full Dispersion)

1. The strip of impervious surface may be either roof (with no gutter) or pavement. The edge of the impervious strip and the ground adjacent to or immediately below the edge must be level or sloped no more than 5% along the edge as shown in Figure C.2.1.E.
2. A 2-foot-wide, 4-to-6 inch-deep, strip of crushed rock or the extended base course of a road or driveway must be provided at or below the edge of the impervious strip to facilitate dispersal of runoff. In outwash soils, a treatment liner to protect groundwater quality per Section 6.2.4 should be provided underneath this flow spreader.
3. No more than a 25-foot-wide strip of impervious surface may be sheet flowed in this manner unless the native vegetated flowpath segment is longer than the 100-foot minimum length specified in Minimum Design Requirement 3 of Section C.2.1.1.
4. A maximum 50-foot-wide strip may be sheet flowed if the flowpath segment is at least 200 feet in length.
5. For strip widths of between 25 and 50 feet, the length of the flowpath segment may vary proportionally between 100 and 200 feet in length.
6. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the outer edge of the native vegetated flowpath segment for the strip of impervious surface must have at least 50 feet of separation from an adjacent flowpath segment at the downstream end of whichever segment is the shorter. **Exception:** where sheet flow from a nonnative pervious surface overlaps with the flowpath for sheet flow from an impervious surface, the impervious surface flowpath segment must be extended at least 1 foot for every 3 feet of nonnative pervious surface area **width** draining to the same flowpath.

Note that width is measured in the general direction that runoff flows across the nonnative pervious surface.

Design Specifications for Pervious Surface Sheet Flow (Full Dispersion)

1. The area of nonnative pervious surface being dispersed by sheet flow must have a *width*¹⁷ of no more than 25 feet unless the native vegetated flowpath segment is longer than the 25-foot minimum length specified in Minimum Design Requirement 3 of Section C.2.1.1.
2. If the width of the nonnative pervious surface is greater than 25 feet, the vegetated flowpath segment must be extended 1 foot for every 3 feet of width beyond 25 feet up to a maximum width of 250 feet.
3. The topography of the nonnative pervious surface must be such that runoff will not concentrate prior to discharge from surface.
4. The vegetated flowpath segment for sheet flow from nonnative pervious surface may overlap with the flowpath segments for other dispersion devices provided adjustments are made to the length of those segments as specified in the design specifications for each dispersion device.

¹⁷ *Width* is measured in the general direction that runoff flows across the area of nonnative pervious surface. For irregular-shaped areas, the width may be an average of distances along multiple paths of runoff across the nonnative pervious surface.

C.2.1.7 FULL DISPERSION FIGURES AND SUMMARY INFORMATION

This section contains the figures referenced in the preceding sections for details on full dispersion devices and includes a useful summary table of the flowpath lengths and capacities of the dispersion devices.

Table C.2.1.A applies to BMPs that are used to meet Full Dispersion requirements only. See Section C.2.4 for Basic Dispersion requirements.

TABLE C.2.1.A SUMMARY OF DISPERSION DEVICE FLOWPATH LENGTHS AND CAPACITIES				
Full Dispersion Device	Native Vegetated Flowpath Length	Maximum Impervious Surface Amount	Maximum Nonnative Pervious Surface Amount	
			Non-Pasture	Pasture
Splash Block	100 feet	700 sq ft	NA	NA
	200 feet	1,400 sq ft	NA	NA
Rock Pad	100 feet	700 sq ft	2,500 sq ft	8,000 sq ft
	200 feet	1,400 sq ft	5,000 sq ft	16,000 sq ft
10-foot Gravel Trench	100 feet	1,400 sq ft	5,000 sq ft	16,000 sq ft
	200 feet	2,800 sq ft	10,000 sq ft	32,000 sq ft
50-foot Gravel Trench	100 feet	5,000 sq ft	17,500 sq ft	54,450 sq ft
	200 feet	10,000 sq ft	35,000 sq ft	108,900 sq ft
Sheet Flow from Impervious Surface	100 feet	25-ft strip width	NA	NA
	200 feet	50-ft strip width	NA	NA
Sheet Flow from Nonnative Pervious Surface	25 feet	NA	25 feet of width in direction of flow	
	50 feet	NA	100 feet of width in direction of flow	
	75 feet	NA	175 feet of width in direction of flow	
	100 feet	NA	250 feet of width in direction of flow	

FIGURE C.2.1.A SCHEMATIC REPRESENTATION OF A TYPICAL SPLASH BLOCK




FIGURE C.2.1.B SCHEMATIC REPRESENTATION OF A DRIVEWAY APPLICATION OF DISPERSION TRENCH AND ROCK PAD




FIGURE C.2.1.C SCHEMATIC REPRESENTATION OF A 10-FOOT DISPERSION TRENCH CROSS-SECTION AND ROOF APPLICATION






FIGURE C.2.1.E SCHEMATIC REPRESENTATION OF AN APPLICATION OF SHEET FLOW DISPERSION



C.2.1.8 NATIVE VEGETATED LANDSCAPE SPECIFICATIONS

Native vegetated landscape is basically the **manmade version of a native vegetated surface**. It may be used in situations where an applicant wishes to convert a previously developed surface to a **native vegetated surface** for purposes of meeting full dispersion requirements or code requirements for forest retention. Native vegetated landscape is intended to have the soil, vegetation, and runoff characteristics approaching that of natural forestland.

Conversion of a developed surface to native vegetated landscape requires the removal of impervious surface, de-compaction of soils, and the planting of native trees, shrubs, and ground cover in compost-amended soil according to all of the following specifications:

1. **Existing impervious surface** and any underlying base course (e.g., crushed rock, gravel, etc.) must be completely removed from the conversion area(s).
2. **Underlying soils** must be broken up to a depth of 18 inches. This can be accomplished by excavation or ripping with either a backhoe equipped with a bucket with teeth, or a ripper towed behind a tractor.
3. At least 4 inches of well-decomposed **compost** must be tilled into the broken up soil as deeply as possible. The finished surface should be gently undulating and must be only lightly compacted.
4. The area of native vegetated landscape must be **planted with native species** trees, shrubs, and ground cover from Table C.2.1.B. Species must be selected as appropriate for *site* shade and moisture conditions, and in accordance with the following requirements:
 - a) **Trees:** a minimum of two species of trees must be planted, one of which is a conifer. Conifer and other tree species must cover the entire landscape area at the spacing given in Table C.2.1.B.

- b) **Shrubs:** a minimum of two species of shrubs should be planted. Space plants to cover the entire landscape area, excluding points where trees are planted.
- c) **Groundcover:** a minimum of two species of ground cover should be planted. Space plants so as to cover the entire landscape area, excluding points where trees or shrubs are planted.

Note: for landscape areas larger than 10,000 square feet, planting a greater variety of species than the minimum suggested above is strongly encouraged. For example, an acre could easily accommodate three tree species, three species of shrubs, and two or three species of groundcover.

5. At least 4 inches of **hog fuel** or other suitable mulch must be placed between plants as mulch for weed control. It is also possible to mulch the entire area before planting; however, an 18-inch diameter circle must be cleared for each plant when it is planted in the underlying amended soil.

Note: plants and their root systems that come in contact with hog fuel or raw bark have a poor chance of survival.

6. Plantings must be **watered** consistently once per week during the dry season for the first two years.
7. The **plantings must be well established** on at least 90% of the converted area in order to be considered a **native vegetated surface**. A minimum of 90% plant survival is required after 3 years.

Conversion of an area that was under cultivation to native vegetated landscape requires a different treatment. Elimination of cultivated plants, grasses and weeds is required before planting and will be required on an on-going basis until native plants are well-established. The soil should be tilled to a depth of 18 inches. A minimum of 8 inches of soil having an organic content of 6 to 12 percent is required, or a four inch layer of compost may be placed on the surface before planting, or 4 inches of clean wood chips may be tilled into the soil, as recommended by a landscape architect or forester. After soil preparation is complete, continue with steps 4 through 7 above. Placing 4 inches of compost on the surface may be substituted for the hog fuel or mulch. For large areas where frequent watering is not practical, bare-root stock may be substituted at a variable spacing from 10 to 12 feet o.c. (with an average of 360 trees per acre) to allow for natural groupings and 4 to 6 feet o.c. for shrubs. Allowable bare-root stock types are 1-1, 2-1, P-1 and P-2. Live stakes at 4 feet o.c. may be substituted for willow and red-osier dogwood in wet areas.

TABLE C.2.1.B SELECTED NATIVE VEGETATION, SIZE, AND SPACING REQUIREMENTS

Species	Type	Sun and Moisture Preferences	Planted Size	Spacing
TREES				
Douglas fir (<i>Pseudotsuga menziesii</i>)	conifer	Sun, dry to moist soil	5 gallon, 6'-7' B&B	12' o.c.
Western red cedar (<i>Thuja plicata</i>)	conifer	Sun or shade, moist to wet soil	5 gallon, 6'-7' B&B	12' o.c.
Western hemlock (<i>Tsuga heterophylla</i>)	conifer	Sun or shade, well-drained soil	5 gallon, 6'-7' B&B	12' o.c.
Sitka spruce (<i>Picea sitchensis</i>)	conifer	Sun or shade, moist mineral soils to wet soils	5 gallon, 6'-7' B&B	12' o.c.
Shore Pine (<i>Pinus contorta</i> var. <i>contorta</i>)	conifer	Sun to partial shade, dry to wet	5 gallon, 6'-7' B&B	12' o.c.
Western white pine (<i>Pinus monticola</i>)	conifer	Sun to part shade, dry to moist	5 gallon, 6'-7' B&B	12' o.c.
Grand fir (<i>Abies grandis</i>)	conifer	Sun to shade, dry to moist	5 gallon, 6'-7' B&B	12' o.c.

TABLE C.2.1.B SELECTED NATIVE VEGETATION, SIZE, AND SPACING REQUIREMENTS

Species	Type	Sun and Moisture Preferences	Planted Size	Spacing
Red alder (<i>Alnus rubra</i>)	tree	Sun, a nitrogen fixer	5 gallon, 5'-6' B&B	12' o.c.
Bigleaf maple (<i>Acer macrophyllum</i>)	tree	Sun or shade, dry to moist soil	5 gallon, 5'-6' B&B	12' o.c.
Black cottonwood (<i>Populus trichocarpa</i>)	tree	Sun, wet soil	5 gallon, 5'-6' B&B	12' o.c.
Cascara (<i>Rhamnus purshiana</i>)	tree/shrub	Sun to partial shade, dry to moist soil	5 gallon, 5'-6' B&B	8' o.c.
Pacific willow (<i>Salix lucida</i>)	tree/shrub	Sun, damp soil	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
SHRUBS				
Sitka willow (<i>Salix sitchensis</i>)	shrub	Sun or shade, dry to damp soil	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Vine maple (<i>Acer circinatum</i>)	shrub	Shade, moist to damp soils	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Filbert (hazelnut) (<i>Corylus cornuta</i>)	shrub	Sun to shade, dry soil	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Red-osier dogwood (<i>Cornus sericea</i>)	shrub	Sun to shade, moist to wet soil	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Salmonberry (<i>Rubus spectabilis</i>)	shrub	Sun to shade, moist to wet soil	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Thimbleberry (<i>Rubus parviflorus</i>)	shrub	Sun to partial shade, dry to moist soil	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Ocean spray (<i>Holodiscus discolor</i>)	shrub	Sun to partial shade, dry	1 gallon 2 gallon 5 gallon	4' o.c. 6' o.c. 8' o.c.
Tall Oregon grape (<i>Berberis aquifolium</i>)	shrub	Sun to shade, dry to moist soil	1 gallon	4' o.c.
Snowberry (<i>Symphoricarpos albus</i>)	shrub	Sun to shade, dry to wet soil	1 gallon, 30"-36"	4' o.c.
Service berry (<i>Amelanchier alnifolia</i>)	shrub	Sun to shade, dry to wet soil	1 gallon	6' o.c.
Indian plum (<i>Oemleria cerasiformis</i>)	shrub	Sun to shade, moist soil	1 gallon	4' o.c.
Twinberry (<i>Lonicera involucrata</i>)	shrub	Sun to partial shade, moist soil	1 gallon	4' o.c.
GROUND COVER				
Evergreen huckleberry (<i>Vaccinium ovatum</i>)	groundcover	Sun to partial shade, moist soil	1 gallon	2' o.c.
Kinnikinick (<i>Arctostaphylos uva-ursa</i>)	groundcover	Sun to partial shade, dry soil	1 gallon	2' o.c.
Salal (<i>Gaultheria shallon</i>)	groundcover	Sun to shade, dry to moist soil	1 gallon	18" o.c.

TABLE C.2.1.B SELECTED NATIVE VEGETATION, SIZE, AND SPACING REQUIREMENTS

Species	Type	Sun and Moisture Preferences	Planted Size	Spacing
Low Oregon grape (<i>Mahonia repens</i>)	groundcover	Sun to partial shade, dry to moist soil	9"–12"	18" o.c.
Sword fern (<i>Polystichum munitum</i>)	groundcover	Sun to deep shade, dry to moist soil	2 gallon	3' o.c.

C.2.1.9 MAINTENANCE INSTRUCTIONS FOR FULL DISPERSION

If full dispersion is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on the City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.2 FULL INFILTRATION

This section presents the minimum design requirements and design specifications for "full infiltration" of runoff from impervious surfaces. *Full infiltration* means the use of BMPs that can "fully and reliably" infiltrate (i.e., soak) runoff into the ground. "Fully" in this context means all the runoff from nearly all storm events is soaked into the ground. "Reliably" means that the soil conditions are favorable enough to ensure that the device used to soak water into the ground (e.g., gravel filled trench, drywell, etc.) will perform as expected for a reasonable number of years before having to be replaced.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, full infiltration may be applied to any non-pollution generating impervious surface (e.g., approved non-pollution generating roof systems, sidewalks or patios) and to those pollution generating impervious surfaces (e.g., driveways, roads, parking areas, and pollution generating roof systems) where either the soil beneath the infiltration BMP has properties that reduce the risk of groundwater contamination from typical stormwater runoff or where a water quality facility provides treatment prior to infiltration as specified in Core Requirement #8 and Special Requirement #5 of the *SWDM*.

Infeasibility Criteria

Full infiltration is considered infeasible and not required for projects that cannot meet the minimum design requirements listed below. Where geotechnical evaluation and approval is required for full infiltration that proposes to discharge towards or is within described setbacks of a ***steep slope hazard area, erosion hazard area, landslide hazard, or slopes greater than 15%***, full infiltration is considered infeasible and not required. Though not required in these circumstances, a project proponent may still opt to use full infiltration as long as the geotechnical evaluation and approval requirement is met.

Operation and Maintenance

See Section C.2.2.6.

C.2.2.1 REQUIRED SOILS REPORT

Many locations in the City have soils that are underlain by a compacted layer of soil (i.e., glacial till or hardpan) which severely limits soaking capacity and causes water to perch on the relatively impervious layer during the wet season. In other areas, soil does not have the properties that reduce the risk of groundwater contamination from typical stormwater runoff from pollution generating surfaces. These factors can make full infiltration of runoff impracticable, cost prohibitive, unreliable, or deleterious to groundwater quality. Thus, a soils report is necessary to identify soil types, soil characteristics, and depth to impermeable layers (hardpan) or the maximum wet season groundwater level.

For the purposes of determining if full infiltration of roof runoff is **mandatory** as outlined in Section C.1.3, the report is a requirement for any **site/lot** where full dispersion of runoff from **target impervious surface** is not feasible or applicable as specified in the individual lot BMP requirements in Sections C.1.3.1 and C.1.3.2. The report is also required for any **optional** use of full infiltration.

Detailed requirements for the soils report are found under “Required Soils Report” in Section 1.3.

C.2.2.2 MINIMUM DESIGN REQUIREMENTS FOR FULL INFILTRATION

All of the following requirements must be met in order for full infiltration to be feasible and applicable to a **target impervious surface**:

1. As determined from the soils report required in Section C.2.2.1, all of the following soil conditions must be met in vicinity of where the infiltration system would be located:
 - a) Existing soils must be **coarse sands or cobbles or medium sands** and cannot be comprised of fill materials where the infiltration device will be located.

*Note: full infiltration may be possible in other types of soils or fill materials if designed by a **civil engineer** in accordance with the infiltration facility standards in Section 5.2 of the SWDM.*

- b) For purposes of determining whether full infiltration of roof runoff is mandatory as outlined in Section C.1.3, the distance measured down from the bottom of the infiltration device to the maximum wet season water table or hardpan must be at least 3 feet. For any optional or mandatory application of full infiltration, the distance measured down from the bottom must be at least 1 foot for a gravel filled infiltration system and 3 feet for a ground surface depression.
2. For purposes of determining whether full infiltration of roof runoff is feasible as outlined in Section C.1.3, one of the following **infiltration devices** must be used in accordance with the design specifications for each device set forth in Sections C.2.2.3, C.2.2.4, and C.2.2.5.

*Note: full infiltration may be possible using other types and sizes of infiltration devices if designed by a **civil engineer** in accordance with the infiltration facility standards in Section 5.2 of the SWDM.*

- **Gravel filled trenches** (see Section C.2.2.3)
 - **Drywells** (see Section C.2.2.4)
 - **Ground surface depressions** (see Section C.2.2.5)
3. A minimum 5-foot **setback** shall be maintained between any part of an infiltration device and any structure or property line. Larger setbacks from structures may be specified in the design specifications for each infiltration device.
 4. For **sites** with **septic systems**, infiltration devices must be located downgradient of the primary and reserve drainfield areas. CED review staff can waive this requirement if site topography clearly prohibits subsurface flows from intersecting the drainfield.
 5. Infiltration devices may not be placed in sensitive area buffers. Infiltration devices are not allowed in critical area **buffers** or on **slopes** steeper than 25% (4 horizontal to 1 vertical).

6. Infiltration devices are not allowed within 50 feet of a *steep slope hazard area, erosion hazard area, or landslide hazard*.
7. Infiltration devices proposed on slopes steeper than 15% must be approved by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
8. Infiltration devices proposed near slopes steeper than 15% must be approved by a *geotechnical engineer* or *engineering geologist* if the facility is located within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15% unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
9. Infiltration devices that direct overflow toward a slope steeper than 15% may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist* as determined by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
10. Infiltration devices proposed within 200 feet of a *steep slope hazard area, erosion hazard area, or landslide hazard* must be approved by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
11. The infiltration of runoff must not create **flooding or erosion impacts** as determined by CED. If runoff is infiltrated near or directs overflow towards a *landslide hazard, erosion hazard area, or steep slope hazard area*, CED may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist*. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
12. Infiltration of runoff from pollution generating surfaces (e.g., roadways, driveways, parking areas, and pollution generating roof systems) is only allowed when soil beneath the BMP has properties that reduce the risk of groundwater contamination from typical stormwater runoff. Such properties are defined in Section 5.2.1 of the *SWDM*. Where soils do not have the required groundwater protection properties, applicants have the option to provide a water quality facility that provides treatment prior to infiltration as specified in Core Requirement #8 and Special Requirement #5 of the *SWDM*. However, for determining feasibility of this BMP, this option is not required to be considered.
13. Underground Injection Control Program (UIC) administered by WA Ecology protects groundwater quality by regulating discharges to UIC wells. WA Ecology adopted revisions to Chapter 173-218 WAC, the Underground Injection Control (UIC) program rules, on January 3, 2006. The newly adopted revisions went into effect on February 3, 2006. These rules require the registration of new injection wells that manage stormwater. Information regarding these new regulations may be found at Ecology's Underground Injection Control Program website, <http://www.ecy.wa.gov/programs/wq/grndwtr/uic/index.html>.
14. UIC wells are manmade structures used to discharge fluids into the subsurface. Examples are drywells, infiltration trenches with perforated pipe, and any structure deeper than the widest surface dimension (see Reference 6 or Ecology's UIC Program website for the Underground Injection Control (UIC) Program Class V Well Identification Guide provided by WA Ecology). In general, infiltration systems that have buried pipe, tanks, or vaults would be considered injection wells, but systems managing runoff only from single-family or duplex roofs, or used to control basement flooding, are exempt. Open ponds are not considered injection wells.
15. If Underground Injection Control (UIC) registration is required by Ecology for the proposed design, a copy of the registration, or the Ecology-issued System ID provided at registration, shall be provided by the applicant prior to plan approval or permit issuance by the City (see Section 2.3.1.1 Technical Information Report (TIR), TIR Section 7 Other Permits and Section 5.4.1 of the *SWDM*).

C.2.2.3 USE OF GRAVEL FILLED TRENCHES FOR FULL INFILTRATION

Gravel filled trenches (also called “**infiltration trenches**”) are a good option where the depth to the maximum wet-season water table or hardpan is between 3 and 6 feet. Figure C.2.2.A and Figure C.2.2.B illustrate the specifications for gravel filled trench systems as outlined below:

1. When located in coarse sands or cobbles, infiltration trenches must be at least 20 feet in **length** per 1,000 square feet of impervious surface served. When located in medium sands, infiltration trenches must be at least 30 feet in length per 1,000 square feet of impervious surface served.
2. **Maximum trench length** must not exceed 100 feet from the inlet sump.
3. The **trench width** must be a minimum of 2 feet.
4. The trench must be filled with at least 18 inches of $\frac{3}{4}$ -inch to $1\frac{1}{2}$ -inch **washed drain rock**. The drain rock may be covered with backfill material as shown in Figure C.2.2.A or remain exposed at least 6 inches below the lowest surrounding ground surface as shown in Figure C.2.2.B.
5. **Filter fabric** (geotextile) must be placed on top of the drain rock (if proposed to be covered with backfill material) and on the trench sides prior to filling with the drain rock.
6. **Spacing** between trench centerlines must be at least 6 feet.
7. Infiltration trenches must be **setback** at least 15 feet from buildings with crawl space or basement elevations that are below the overflow point of the infiltration system.
8. To prevent damage to overlying pavement, **trenches located beneath pavement** shall be constructed such that the trench pipe is connected to a small yard drain or catch basin with a grate cover so that if the trench infiltration capacity is exceeded, the overflow would occur out of the catch basin at an elevation at least one foot below that of any overlying pavement, and in a location that provides a safe path for the overflow.
9. Runoff from roadways, driveways, and parking areas shall pass through a yard drain or catch basin fitted with a **down-turned elbow** prior to entering the infiltration trench (see Figure C.2.2.A). The elbow is intended to trap spilled material in the catch basin sump so that the spilled material can be cleaned up more easily by the homeowner.

C.2.2.4 USE OF DRYWELLS FOR FULL INFILTRATION

Drywells are gravel filled holes as opposed to trenches and therefore may allow for a more compact design in areas where the depth to the maximum wet-season water table is relatively deep (e.g., 6 feet or greater). Figure C.2.2.C illustrates the specifications for drywell infiltration systems as outlined below:

1. When located in coarse sands and cobbles, drywells must contain a **volume of gravel** equal to or greater than 60 cubic feet per 1,000 square feet of impervious surface served. When located in medium sands, drywells must contain at least 90 cubic feet of gravel per 1,000 square feet of impervious surface served.
2. Drywells must be at least 48 inches in **diameter** and deep enough to contain the gravel amounts specified above for the soil type and impervious surface area served.
3. The gravel used for drywells must be $1\frac{1}{2}$ -inch to 3-inch **washed drain rock**. The drain rock may be covered with backfill material as shown in Figure C.2.2.C or remain exposed at least 6 inches below the lowest surrounding ground surface.
4. **Filter fabric** (geotextile) must be placed on top of the drain rock (if proposed to be covered with backfill material) and on the drywell sides prior to filling with the drain rock.
5. **Spacing** between drywells shall be a minimum of 10 feet.
6. Drywells must be **setback** at least 15 feet from buildings with crawl space or basement elevations that are below the overflow point of the drywell.

C.2.2.5 USE OF GROUND SURFACE DEPRESSIONS FOR FULL INFILTRATION

Ground surface depressions (also called “**infiltration depressions**”) are another option for full infiltration if the maximum wet-season water table or hardpan is at least 3 feet below the bottom of the depression. Figure C.2.2.D illustrates the specifications for infiltration depressions as outlined below:

1. When located in coarse sands or cobbles, infiltration depressions must be able to store at least 40 cubic feet of stormwater per 1,000 square feet of impervious surface served. When located in medium sands, ground surface depressions must be able to store at least 60 cubic feet of stormwater per 1,000 square feet of impervious surface served. This **volume of water storage** must be achieved through the excavation of existing native soil, not through the construction of berms.
2. The stormwater storage areas of infiltration depressions must be at least 12 inches in **depth** with a minimum 6 inches of freeboard before overflow.
3. The depression **overflow point** must be at least 6 inches below any adjacent pavement area and must be situated so that overflow does not cause erosion damage or unplanned inundation.
4. The depression **side slopes** must be no steeper than 3 horizontal to 1 vertical.
5. **Spacing** between multiple infiltration depressions shall be a minimum of 4 feet.
6. Infiltration depressions must be **setback** at least 15 feet from buildings with crawl space or basement elevations that are below the overflow point of the infiltration depression.
7. Infiltration depressions may be any **size** or **shape** provided the above specifications and the minimum design requirements in Sections C.2.2.2 and C.2.2.2 are met.
8. The ground surface of the infiltration depression must be **vegetated** with grass or other dense ground cover.

C.2.2.6 MAINTENANCE INSTRUCTIONS FOR FULL INFILTRATION

If the full infiltration on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on City of Renton’s *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

FIGURE C.2.2.A SCHEMATIC REPRESENTATION OF A TYPICAL TRENCH INFILTRATION SYSTEM




FIGURE C.2.2.B SCHEMATIC REPRESENTATION OF AN ALTERNATIVE TRENCH INFILTRATION SYSTEM





FIGURE C.2.2.C SCHEMATIC REPRESENTATION OF A TYPICAL DRYWELL INFILTRATION SYSTEM






FIGURE C.2.2.D SCHEMATIC REPRESENTATION OF A TYPICAL GROUND SURFACE DEPRESSION INFILTRATION SYSTEM



**SECTION
NTS**



**SECTION
NTS**

C.2.3 LIMITED INFILTRATION

Limited infiltration is the use of infiltration devices from Section C.1.1 in soils that are not as permeable as the medium sands or coarse sands/cobbles targeted for full infiltration in Section C.1.1. These less desirable soils include fine sands, loamy sands, sandy loams, and loams, which tend to be more variable in permeability, more frequently saturated during the wet season, and more prone to plugging over time. While full infiltration may be possible under the best of these soil conditions, in the long run, these conditions will conspire to limit average infiltration capacity to something much less than that of full infiltration. Therefore, using limited infiltration as specified in this section will not be credited the same as using full infiltration as specified in Section C.1.1.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, limited infiltration may be applied to any non-pollution generating impervious surface (e.g., approved roofs, sidewalks, or patio) and to those pollution generating impervious surfaces (e.g., driveway, road, or parking area) where the soil beneath the infiltration BMP has properties that reduce the risk of groundwater contamination from typical stormwater runoff or where a water quality facility provides treatment prior to infiltration as specified in Core Requirement #8 and Special Requirement #5 of the *SWDM*.

Infeasibility Criteria

Limited infiltration is considered infeasible and not required for projects that cannot meet the minimum design requirements listed below. Where geotechnical evaluation and approval is required for limited infiltration that proposes to discharge towards or is within described setbacks of a *steep slope hazard area*, *erosion hazard area*, *landslide hazard*, or *slopes greater than 15%*, limited infiltration is considered infeasible and not required. Though not required in these circumstances, a project proponent may still opt to use limited infiltration as long as the geotechnical evaluation and approval requirement is met.

Operation and Maintenance

See Section C.2.3.5.

C.2.3.1 REQUIRED SOILS REPORT

In order to properly design limited infiltration devices, a soils report is required to identify soil types, soil characteristics, the depth to impermeable layers (i.e., hardpan) and to the maximum wet season groundwater level. Detailed requirements for the soils report are found under “Required Soils Report” in Section C.1.3. In many cases, this report will have already been prepared as required in Sections C.1.3.1 and C.1.3.2 for lots where full dispersion is not feasible or applicable to *target impervious surface* per Section C.2.1.

C.2.3.2 MINIMUM DESIGN REQUIREMENTS FOR LIMITED INFILTRATION

The minimum design requirements for limited infiltration are the same as those for full infiltration, except infiltration depressions are excluded and existing soils in the location of the infiltration device may be fine sands, loamy sands, sandy loams, or loams as opposed to only medium sands or better.

Note that gravel and medium sand soils used for full infiltration correspond to Soil Types 1A, 1B, 2A, and 2B in the Soil Textural Classification system used for onsite septic system design; fine sands are Type 3; and loamy sands, sandy loams and loams are Type 4 soils. Silt and clay loams, and cemented till (hardpan) are not suitable for limited infiltration systems.

C.2.3.3 USE OF GRAVEL FILLED TRENCHES FOR LIMITED INFILTRATION

The specifications for use of gravel filled trenches for limited infiltration are the same as those used for full infiltration, except that the required **trench lengths** are as follows:

For each 1,000 square feet of tributary impervious surface:

Rainfall region SeaTac 1.0 and less: (a) 21 feet if the soil is a fine sand/loamy sand, (b) 36 feet if the soil is a sandy loam, or (c) 52 feet if the soil is a loam.

Rainfall regions greater than SeaTac 1.0: (d) 48.3 feet if the soil is a fine sand/loamy sand, (e) 60.5 feet if the soil is a sandy loam, or (f) 73 feet if the soil is a loam.

C.2.3.4 USE OF DRYWELLS FOR LIMITED INFILTRATION

The specifications for use of drywells for limited infiltration are the same as those used for full infiltration, except that the required **gravel volumes** are as follows:

For each 1,000 square feet of tributary impervious surface:

(a) 315 cubic feet if the soil is a fine sand/loamy sand, (b) 360 cubic feet if the soil is a sandy loam, or (c) 407 cubic feet if the soil is a loam.

Note: For projects using the BMP list approach to comply with Core Requirement #9 (On-Site BMPs), the drywell sizing cited is restricted to configurations with a maximum depth of 5 feet and a minimum area footprint of 12.56 square feet. Projects that are using hydraulic modeling to demonstrate compliance with the LID Performance Standard to meet Core Requirement #9 (On-Site BMPs) may propose deeper configurations subject to other applicable design criteria and limitations.

C.2.3.5 MAINTENANCE INSTRUCTIONS FOR LIMITED INFILTRATION

If the limited infiltration on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.4 BASIC DISPERSION

Basic dispersion is the application of dispersion devices that utilize any available capacity of onsite vegetated areas to mitigate the runoff quantity and quality impacts from developed surfaces (i.e., impervious and nonnative pervious surfaces). The requirements for basic dispersion are less restrictive than full dispersion (Section C.2.1) in that any type of vegetation cover is allowed, the flowpath lengths through the vegetation are shorter, and there is no requirement to preserve **native vegetated surface** (e.g., forested surface) or minimize developed surface. As such, its mitigation of runoff impacts is significantly lower than that of full dispersion.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, basic dispersion may be applied to any impervious surface such as a roof, driveway, parking area, road, or sidewalk. Basic dispersion may also be used to disperse runoff from nonnative pervious surface (e.g., lawns, landscaped areas, or pastures) if runoff from these surfaces is concentrated.

Infeasibility Criteria

Basic dispersion is considered infeasible and not required for projects that cannot meet the minimum design requirements listed below. Where geotechnical evaluation and approval is required for basic dispersion that proposes to discharge towards or is within described setbacks of a *steep slope hazard area*, *erosion hazard area*, *landslide hazard*, or *slopes greater than 15%*, basic dispersion is considered infeasible and not required. Though not required in these circumstances, a project proponent may still opt to use basic dispersion as long as the geotechnical evaluation and approval requirement is met.

Operation and Maintenance

See Section C.2.4.6.

C.2.4.1 MINIMUM DESIGN REQUIREMENTS FOR BASIC DISPERSION

All of the following requirements must be met in order for basic dispersion to be applicable to a target impervious or pervious surface:

1. Runoff from the target impervious or pervious surface must be discharged using one of the following **dispersion devices** in accordance with the design specifications and maximum area of developed surface for each device as set forth in Sections C.2.4.2 through C.2.4.5:
 - **Splash blocks** (see Section C.2.4.2)
 - **Rock pads** (see Section C.2.4.3)
 - **Gravel filled trenches** (see Section C.2.4.4)
 - **Sheet flow** (see Section C.2.4.5)
2. Each device must discharge runoff such that it flows over a minimum distance of vegetated area called the “**vegetated flowpath segment**.” The minimum distance, or length of the flowpath segment, is specified in the design specifications for each device. The “vegetated flowpath segment” itself must meet all of the following criteria:
 - a) The flowpath segment must be over well-established lawn or pasture, landscaping with well-established groundcover, or native vegetation with natural groundcover. The groundcover must be dense enough to help disperse and infiltrate flows and to prevent erosion.
 - b) The flowpath segment must be **onsite or in an offsite tract or easement** area reserved for such dispersion.
 - c) The **slope** of the flowpath segment must be no steeper than 15% for any 20-foot reach of the flowpath segment.
 - d) The flowpath segment must be **located** between the dispersion device and any downstream impervious surface or drainage feature such as a pipe, ditch, stream, river, pond, lake, or wetland. All or a portion of the flowpath segment may be located within a critical area buffer.
3. For *sites* with **septic systems**, the discharge of runoff from dispersion devices must be located down slope of the primary and reserve drainfield areas. CED review staff may waive this requirement if *site* topography clearly prohibits discharged flows from intersecting the drainfield.
4. Dispersion devices are not allowed in critical area **buffers** or on **slopes** steeper than 20%.
5. Dispersion devices are not allowed within 50 feet of a *steep slope hazard area*, *erosion hazard area*, or *landslide hazard*.
6. Dispersion devices proposed on slopes steeper than 15% must be approved by a **geotechnical engineer** or **engineering geologist** unless otherwise approved by the CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.

7. Dispersion devices proposed near slopes steeper than 15% must be approved by a *geotechnical engineer* or *engineering geologist* if the facility is located within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15% unless otherwise approved by the CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
8. Dispersion devices that direct runoff toward a slope steeper than 15% may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist* as determined by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
9. Dispersion devices proposed within 200 feet of a *steep slope hazard area*, *erosion hazard area*, or *landslide hazard* must be approved by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by the CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
10. The dispersion of runoff must not create **flooding or erosion impacts** as determined by the CED. If runoff is discharged toward a *landslide hazard*, *erosion hazard area*, or *steep slope hazard area*, CED may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist*. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.

C.2.4.2 USE OF SPLASH BLOCKS FOR BASIC DISPERSION

Splash blocks are the simplest way to disperse flows from a roof area. Downspout splash blocks or downspout/drain extensions with splash blocks are often the only hardware required for this type of system. Vegetated flowpaths do the work of slowing and cleaning stormwater runoff. In general, if the ground is sloped away from the foundation, and there is adequate vegetation and area for effective dispersion, splash blocks will adequately disperse storm runoff. If the ground is fairly level, or if the structure includes a basement, or if foundation drains are proposed, splash blocks with downspout extensions may be a better choice because the discharge point is moved away from the foundation. Downspout extensions may include piping to a splash block that is a considerable distance from the roof downspout, provided the runoff can travel through a well-vegetated area as described below.

Uses: Roofs where runoff is collected and discharged via downspouts.

Design Specifications

Figure C.2.4.A shows details of a roof downspout and splash block. The following specifications apply to use of splash blocks for basic dispersion:

1. No more than 700 square feet of roof area may be drained to a single splash block.
2. A “vegetated flowpath segment” of at least 50 feet in length must be available along the flowpath that runoff would follow upon discharge from the splash block.
3. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the vegetated flowpath segment for the splash block must not overlap with other flowpath segments, except those associated with sheet flow from a nonnative pervious surface.

C.2.4.3 USE OF ROCK PADS FOR BASIC DISPERSION

Pads of crushed rock, 2 feet wide (perpendicular to flow) by 3 feet long by 6 inches deep, may be used as a dispersion device to discharge concentrated runoff from small amounts of impervious surface or nonnative pervious surface.

Uses: Roofs, driveways, lawns, pasture, etc. from which runoff is concentrated in a downspout, gutter, pipe, yard drain, ditch, swale, etc.

Design Specifications

Figure C.2.4.C shows two possible ways of spreading flows from steep driveways. The following specifications apply to use of rock pads for basic dispersion:

1. No more than 700 square feet of impervious surface (or 5,000 square feet of nonnative pervious surface) may be drained to a single rock pad.
2. A “vegetated flowpath segment” of at least 50 feet in length as illustrated in Figure C.2.4.C must be available along the flowpath that runoff would follow upon discharge from the rock pad.
3. The pad of crushed rock shall be 2 feet wide by 3 feet long by 6 inches deep.
4. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the vegetated flowpath segment for the rock pad must not overlap with other flowpath segments, except those associated with sheet flow from a nonnative pervious surface.

C.2.4.4 USE OF GRAVEL FILLED TRENCHES FOR BASIC DISPERSION

Where dispersion of concentrated flows through 50 feet of vegetation is not feasible, such as on a small or highly constrained *site*, a gravel filled trench (also called a **dispersion trench**) may be used to “unconcentrate” flows. Dispersion trenches provide some storage for runoff, promote infiltration, and spread concentrated flows so that a shorter vegetated flowpath length can be used at the trench outlet. This BMP is more expensive than the simple dispersion systems described above, and must be carefully constructed to be effective.

Uses: Roofs, driveways, lawns, pasture, etc. from which runoff is concentrated in a downspout, yard drain, pipe, drainage tile, etc.

Design Specifications

Figure C.2.4.B shows two types of dispersion trenches that may be used, a “simple 10-foot trench” and a maximum “50-foot trench with notch board.” The 50-foot trench with notch board is further detailed in Figure C.2.1.D. These gravel filled trenches must meet the following specifications for basic dispersion:

1. No more than 700 square feet of impervious surface (or 5,000 square feet of nonnative pervious surface) may be drained to a simple 10-foot dispersion trench. Up to 3,500 square feet of impervious surface (or 25,000 square feet of nonnative pervious surface) may be drained to a 50-foot trench with notch board. Smaller lengths of trench with notch board may be used at a ratio of 10 feet of trench per 700 square feet of impervious surface (or 5,000 square feet of nonnative pervious surface).
2. A “vegetated flowpath segment” of at least 25 feet in length must be available along the flowpath that runoff would follow upon discharge from a dispersion trench. This length must be increased to 50 feet if the discharge is toward a *steep slope hazard area* or a *landslide hazard* steeper than 15%. All or a portion of the vegetated flowpath segment may be within the buffer for the *steep slope hazard area* or *landslide hazard*.
3. The simple 10-foot trench illustrated in Figure C.2.4.B must be at least 2-feet wide by 18-inches deep. The maximum 50-foot trench with notch board detailed in Figure C.2.1.D must be at least 2-feet wide by 24-inches deep.
4. All trenches must be filled with $\frac{3}{4}$ to 1 $\frac{1}{2}$ -inch washed rock.
5. All trenches must be placed at least 10 feet from any building and must be parallel as possible to the contour of the ground. A setback of at least 5 feet must be maintained between any edge of a trench and the property line.
6. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the outer edge of the vegetated flowpath segment for the dispersion trench must not overlap

with other flowpath segments, except those associated with sheet flow from a nonnative pervious surface.

C.2.4.5 USE OF SHEET FLOW FOR BASIC DISPERSION

Sheet flow, as a dispersion device, is the grading of a developed surface (either a strip of impervious surface or a width of nonnative pervious surface) as needed to avoid the concentration of runoff before and after discharge from the surface. Two types of sheet flow, one for impervious surface and one for pervious surface, are detailed in this section.

Uses: Flat or moderately sloping surfaces (<15% slope) such as driveways, sport courts, patios, roofs without gutters, lawns, pastures, etc.; or any situation where concentration of flows can be avoided.

Design Specifications for Impervious Surface Sheet Flow (Basic Dispersion)

Figure C.2.4.D illustrates a typical use of sheet flow dispersion for impervious surface in accordance with the following specifications:

1. The strip of impervious surface may be either roof (with no gutter) or pavement. The edge of the target impervious strip and the ground adjacent to or immediately below the edge must be either level or sloped such that the direction of sheet flow is perpendicular to the edge or no more than 45 degrees from perpendicular.
2. A 2-foot-wide, 4-to-6 inch-deep, strip of crushed rock or the extended base course of a road or driveway must be provided at or below the edge of the impervious strip to facilitate dispersal of runoff. This requirement may be waived for use of *reverse slope sidewalks*¹⁸ and other impervious strips that are 10-foot wide or less.
3. A “vegetated flowpath segment” of at least 10 feet in length must be available along the flowpath that runoff would follow upon discharge from the strip of crushed rock.
4. No more than a 20-foot-wide strip of impervious surface may be sheet flowed in this manner unless the length of vegetated flowpath segment is increased 10 feet for each additional 20 feet of impervious surface width or fraction thereof.
5. For purposes of maintaining adequate separation of flows discharged from adjacent dispersion devices, the outer edge of the vegetated flowpath segment for the strip of impervious surface must not overlap with other flowpath segments, except those associated with sheet flow from a nonnative pervious surface.

Design Specifications for Pervious Surface Sheet Flow (Basic Dispersion)

The runoff from any *new pervious surface* is considered dispersed by sheet flow if the runoff is not concentrated by a manmade or natural conveyance system (e.g., pipe, yard drain, drain tile, ditch, swale, etc.) within 25 feet of leaving the *new pervious surface* area or prior to leaving the *site* or entering a critical area buffer on the *site*.

C.2.4.6 MAINTENANCE INSTRUCTIONS FOR BASIC DISPERSION

If the basic dispersion on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be

¹⁸ *Reverse slope sidewalk* is one that slopes away from rather than onto the roadway it abuts as required by City road standards. If this technique is proposed within City right-of-way, a Road Variance will be required for its use.

a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

FIGURE C.2.4.A SCHEMATIC REPRESENTATION OF A TYPICAL SPLASHBLOCK FOR BASIC DISPERSION






FIGURE C.2.4.B SCHEMATIC REPRESENTATION OF A TYPICAL GRAVEL-FILLED DISPERSION TRENCH FOR BASIC DISPERSION



TRENCH SECTION
NTS



PLAN VIEW OF ROOF
NTS

FIGURE C.2.4.C SCHEMATIC REPRESENTATION OF BASIC DISPERSION FOR STEEP DRIVEWAYS







FIGURE C.2.4.D SCHEMATIC REPRESENTATION OF A BASIC DISPERSION FOR DRIVEWAYS



PLAN - DRIVEWAY DISPERSION TRENCH
DRIVEWAY SLOPE VARIES AND SLOPES TOWARD STREET
NTS



PLAN - SHEET FLOW DISPERSION FROM A DRIVEWAY
FLAT TO MODERATELY STOPPING DRIVEWAYS
NTS

C.2.5 FARMLAND DISPERSION

This BMP does not apply to the City of Renton.

C.2.6 BIORETENTION

Note: This section is intended to apply only to bioretention designed to meet Core Requirement #9. Additional design requirements apply to bioretention designed to meet Core Requirement #8 (described in Chapter 6 of the SWDM).

Bioretention areas are shallow landscaped depressions, with a designed soil mix and plants adapted to the local climate and soil moisture conditions that receive stormwater from a contributing area. Four types of bioretention designs are discussed in this section: bioretention cells, bioretention swales, bioretention planters, and a road-side ditch bioretention alternative design. These are briefly described below:

Bioretention Cells:

Shallow depressions with a designed planting soil mix and a variety of plant material, including trees, shrubs, grasses, and/or other herbaceous plants. Bioretention cells are not designed as a conveyance system. (See Figures C.2.6.A and C.2.6.B)

Bioretention Swales:

Incorporate the same design features as bioretention cells; however, bioretention swales are designed as part of a system that can convey stormwater when maximum ponding depth is exceeded. Bioretention swales have relatively gentle side slopes and water storage depths that are typically 2 to 12 inches.

Bioretention Planters:

Designed soil mix and a variety of plant material including trees, shrubs, grasses, and/or other herbaceous plants within a vertical walled container usually constructed from formed concrete, but could include other materials. Planters have an open bottom and allow infiltration to the subgrade. These designs are often used in ultra-urban settings.

Road-Side Bioretention Ditch:

This BMP is not approved for use in the city without an adjustment. This feature uses a designed soil mix underlain by drain rock for increased storage, low maintenance vegetation typical of road-side ditches, and requires no permanent ponding-- allowing for road side conveyance to function per current design and maintenance standards without need for weirs or excess standing water along the road.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, bioretention may be applied to any impervious surface such as a roof, driveway, parking area, road, or sidewalk, and to any nonnative pervious surface such as a lawn, landscaped area, or pasture. Bioretention proposed in road rights-of-way must be per the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable or as otherwise approved by the City.

Infeasibility Criteria

Bioretention is considered infeasible and not required for projects that cannot meet the minimum design requirements for bioretention or via the bioretention infeasibility criteria list that follows in this section. Where the minimum design requirements call for geotechnical evaluation and approval for bioretention that proposes to discharge towards or is within described setbacks of a *steep slope hazard area*, *erosion*

hazard area, landslide hazard, or slopes greater than 15%, bioretention is considered infeasible and not required. Though not required in these circumstances, a project proponent may still opt to use bioretention as long as the geotechnical evaluation and approval requirement is met.

Additional Requirements for Large Bioretention Facilities:

Bioretention that receives runoff from:

- Impervious surfaces totaling 10,000 square feet or more; *or*
- New pervious surfaces totaling $\frac{3}{4}$ acre or more, *or*
- A combination of impervious and pervious surfaces that results in a 0.15 cfs increase (using 15-minute time steps) or 0.1 cfs (using 1-hour time steps) in the 100-year peak flow when comparing predeveloped (historical) and developed conditions,

must meet the following additional requirements to address their larger size, risk, and maintenance needs:

Bioretention Cells:

- **SWDM Section 5.2:** 100 year overflow conveyance (if applicable); Spill Control Device; Presettling, Protection from Upstream Erosion; Facility Construction Guidelines; Offsite Groundwater Impacts; Groundwater Protection; Infiltration near Water Supply Wells; and Infiltration near Steep Slopes and Landslide Hazards.
- **SWDM Section 5.2.2.1** Infiltration Ponds Design Criteria: General, Setbacks.

Bioretention Swales:

- **SWDM Section 5.2:** 100 year overflow conveyance (if applicable); Protection from Upstream Erosion; Facility Construction Guidelines; Offsite Groundwater Impacts; Groundwater Protection; Infiltration near Water Supply Wells; and Infiltration near Steep Slopes and Landslide Hazards.
- **SWDM Section 6.3:** Vegetated Flowpath Facility Designs: Access; Construction Considerations; Flow Velocity, Energy Dissipation, and Flow Spreading (#2, 3, 4 and 5)

Other Site Suitability Factors

Utility conflicts: Perpendicular utility crossing within bioretention facilities is allowed with the following conditions:

- Horizontal separation between water main wall and top of slope of the bioretention facility shall be no less than 7 feet
- 30 inches of cover for service line shall be maintained.
- Fire hydrants shall be at least 5 feet from bioretention footprint.
- Water meter shall be located outside bioretention facility footprint
- Manholes shall be located outside bioretention facility footprint
- A minimum 1-foot separation between sanitary sewer crossings and underdrains shall be maintained. When separation requirements cannot be met, designs should include appropriate mitigation measures, such as impermeable liners over the utility, sleeving utilities, fixing known leaky joints or cracked conduits, and/or adding an underdrain to the bioretention facility.

Transportation safety: The design configuration and selected plant types should provide adequate sight distances, clear zones, and appropriate setbacks for roadway applications in accordance with RMC 4-6-060.

Ponding depth and surface water draw-down: Flow control needs, as well as location in the development, and mosquito breeding cycles will determine draw-down timing. For example, front yards and entrances to residential or commercial developments may require rapid surface dewatering for aesthetics.

Impacts of surrounding activities: Human activity influences the location of the facility in the development. For example, locate bioretention areas away from traveled areas on individual lots to prevent soil compaction and damage to vegetation or provide elevated or bermed pathways in areas where foot traffic is inevitable, and provide barriers, such as wheel stops, to restrict vehicle access in roadside applications.

Visual buffering: Bioretention facilities can be used to buffer structures from roads, enhance privacy among residences, and for an aesthetic site feature.

Site growing characteristics and plant selection: Appropriate plants should be selected for sun exposure, soil moisture, and adjacent plant communities. Native species or hardy cultivars are recommended and can flourish in the properly designed and placed Bioretention Soil Mix with no nutrient or pesticide inputs and 2 to 3 years' irrigation for establishment. Invasive species control may be necessary.

Required Soils Report

Many locations in the City have soils that are underlain by a compacted layer of soil (i.e., glacial till or hardpan) which severely limits soaking capacity and causes water to perch on the relatively impervious layer during the wet season. This can make bioretention impracticable, unreliable, and reduce plant survivability in the bioretention system. Thus, a soils report is necessary to identify soil types, depth to impermeable layers (hardpan) or the maximum wet season groundwater level, and infiltration rates. Detailed requirements for the soils report are found under "Required Soils Report" in Section C.1.3.

Operation and Maintenance

See Section 2.6.3.

Bioretention Infeasibility Criteria List

These are conditions that make bioretention not required to be implemented as part of the prescriptive BMP lists detailed in Core Requirement #9 of the SWDM and Section 1.3 of Appendix C. The lists require BMPs to be evaluated and installed to the maximum extent feasible. Where determined infeasible by these criteria, an applicant has the option to propose a functional design via the adjustment process described in Section 1.4 of the SWDM in order to: (a) use the on-site BMP facility modeling credits described in SWDM Section 1.2.9.4; (b) to use in achieving the LID Performance Standard (where required or optional); or (c) to meet the minimum on-site BMP implementation requirements enconced in the "Small Lot and Large Lot requirements" lists located in SWDM Section 1.2.9.2 and Appendix C, Section 1.3.

Note: Criteria with setback distances are as measured from the outermost edge of the bioretention soil mix.

Citation of any of the following infeasibility criteria (#1–7) must be based on an evaluation of site-specific conditions and a written recommendation from an appropriate licensed professional (e.g., engineer, geologist, hydrogeologist):

1. Where professional geotechnical evaluation recommends infiltration not be used due to reasonable concerns about erosion, slope failure, or down gradient flooding.
2. Within an area whose ground water drains into an erosion hazard area or landslide hazard.
3. Where the only area available for siting would threaten the safety or reliability of pre-existing underground utilities, pre-existing underground storage tanks, pre-existing structures, or pre-existing road or parking lot surfaces.
4. Where the only area available for siting does not allow for a safe overflow pathway to the municipal separate storm sewer system or private storm sewer system.
5. Where there is a lack of usable space for bioretention facilities at re-development sites, or where there is insufficient space within the existing public right-of-way on public road projects.

6. Where infiltrating water would threaten existing below grade basements.
7. Where infiltrating water would threaten shoreline structures such as bulkheads.

The following criteria can be cited as reasons for a finding of infeasibility without further justification (though some require professional services):

8. Within setbacks from structures as established by the RMC.
9. Where the project drains to an existing stormwater collection system whose elevation or location precludes connection to a properly functioning bioretention facility (e.g., installation required that an existing major publicly or privately-owned infrastructure or utility element to be relocated, the facility cannot be built and operated to discharge stormwater from the site under gravity flow conditions while meeting the applicable engineering standards).
10. Where land for bioretention is within area designated as an *erosion hazard area* or *landslide hazard*.
11. Where the site cannot be reasonably designed to locate bioretention facilities on slopes less than 8%.
12. Within 50 feet from the top of slopes that are greater than 20% and over 10 feet of vertical relief.
13. For properties with known soil or ground water contamination (typically federal Superfund sites or state cleanup sites under the Model Toxics Control Act [MTCA]):
 - a) Within 100 feet of an area known to have deep soil contamination;
 - b) Where ground water modeling indicates infiltration will likely increase or change the direction of the migration of pollutants in the ground water;
 - c) Wherever surface soils have been found to be contaminated unless those soils are removed within 10 horizontal feet from the infiltration area;
 - d) Any area where these facilities are prohibited by an approved cleanup plan under the state Model Toxics Control Act or Federal Superfund Law, or an environmental covenant under Chapter 64.70 RCW.
14. Within 100 feet of a closed or active landfill.
15. Within 100 feet of a drinking water well, or a spring used for drinking water supply. Within *Zone 1 of the Aquifer Protection Area*.
16. Within 10 feet of small onsite sewage disposal drainfield, including reserve areas, and grey water reuse systems. For setbacks from a "large onsite sewage disposal system," see Chapter 246-272B WAC.
17. Within 10 feet of an underground storage tank and connecting underground pipes when the capacity of the tank and pipe system is 1100 gallons or less. (As used in these criteria, an underground storage tank means any tank used to store petroleum products, chemicals, or liquid hazardous wastes of which 10% or more of the storage volume (including volume in the connecting piping system) is beneath the ground surface.
18. Within 100 feet of an underground storage tank and connecting underground pipes when the capacity of the tank and pipe system is greater than 1100 gallons.
19. Where the minimum vertical separation of 1 foot to the seasonal high water table, bedrock, or other impervious layer would not be achieved below bioretention that would serve a drainage area that is: 1) less than 5,000 sq. ft. of pollution-generating impervious surface, and 2) less than 10,000 square feet of impervious surface; and, 3) less than three-quarters (3/4) acres of pervious surface.
20. Where the a minimum vertical separation of 3 feet to the seasonal high water table, bedrock or other impervious layer would not be achieved below bioretention that: 1) would serve a drainage area that meets or exceeds: a) 5,000 square feet of pollution-generating impervious surface, or b) 10,000 square

- feet of impervious surface, or c) three-quarters (3/4) acres of pervious surfaces; and 2) cannot reasonably be broken down into amounts smaller than indicated in (1).
21. Where the field testing indicates potential bioretention sites have a measured (a.k.a., initial) native soil saturated hydraulic conductivity less than 0.30 inches per hour.
 22. The minimum bottom width (18 inches) cannot be met due to, but not limited to: encroachment within the critical root zone of an existing tree(s) or minimum setbacks to structures, utilities, or property lines.
 23. In the right-of-way, installation requires a vertical walled facility.

C.2.6.1 MINIMUM DESIGN REQUIREMENTS (CELLS, SWALES, AND PLANTERS)

All of the following requirements must be met in order for bioretention to be applicable to a target impervious or target pervious surface:

1. A **minimum water storage volume** shall be provided in the bioretention BMP that is calculated by multiplying the equivalent storage depth by the square footage of the target surface area served.

For target impervious areas:

- Rainfall region SeaTac 1.0: In till soils, provide bioretention volume based on 0.6 inches of equivalent storage depth; in outwash soils provide bioretention volume based on 0.1 inches of equivalent storage depth
- Rainfall regions greater than SeaTac 1.0: In till soils, provide bioretention volume based on 0.8 inches of equivalent storage depth; in outwash soils, provide bioretention volume based on 0.4 inches of equivalent storage depth,

For target pervious areas: In till soils, provide bioretention volume based on 0.7 inches of equivalent storage depth; in outwash soils, provide bioretention volume based on 0.006 inches of equivalent storage depth.

2. The **water storage area**, containing the minimum required storage volume, shall be 6-12 inches deep at overflow and have side slopes no steeper than 2.5 horizontal to 1 vertical (except where the storage area is structurally contained, e.g., a planter configuration). The overflow point of the water storage area shall be at least 6 inches below any adjacent pavement area. The overflow point must be situated so that overflow does not cause erosion damage or unplanned inundation.
3. The bioretention footprint as measured at the overflow elevation shall be a minimum of 5% of the impervious surface directed to the bioretention BMP. The bottom area of an individual cell shall be no less than 4 square feet. The bottom area of an individual cell shall be no larger than 800 square feet (limitation is to ensure that bioretention facilities are small-scale and distributed).
4. The maximum allowable drawdown time of the water storage area is 24 hours. A correction factor of 0.33 to 1 (no correction factor) as recommended by a licensed geotechnical professional should be applied to initial measured infiltration rates of the in situ soils to determine the design rate for this drawdown calculation. The designed depth of ponding (2" minimum to 12" maximum) must be considered in light of the drawdown time requirement (e.g., in slow draining soils, the designed ponding depth may need to be decreased "in order to meet the drawdown criteria). As an example, a 6" deep pool with an initial measured rate of 0.5"/hour and a correction factor of 0.5 applied will achieve drawdown in exactly 24 hours (0.5 in/hour x 0.5 correction factor x 24 hours = 6 inches).
5. Bioretention with underdrains is not allowed for Core Requirement #9 unless approved via a *SWDM* adjustment per Section 1.4 that, at minimum, addresses comparable hydraulic performance, water quality concerns, and maintainability. Bioretention with underdrains is allowed for Core Requirement #8.

6. Bioretention areas should have a minimum shoulder of 6 inches between the road edge and beginning of the bioretention side slope where flush curbs are used.
7. Flow entrance techniques for energy dissipation shall be utilized. Flow entrances shall be per design criteria in Section 6.8.1.1..
8. If a **containment berm** is used to form the water storage area, the berm must be at least 6 inches wide and 6 inches above the 12 inches of water depth. A **catch basin** or **rock pad** must be provided to release water when the pond's water level exceeds the 12 inches of water depth. The catch basin may discharge to the *local drainage system* or other acceptable discharge location via a 6-inch rigid pipe (private) or 8-inch rigid pipe (public). The rock pad may be used with or without a constructed drainage system downstream. If a rock pad is used, it must be composed of crushed or fractured rock, 6-inches deep and 2 feet wide (perpendicular to flow) and must extend at least 4 feet or beyond the containment berm, whichever is greater. The rock pad must be situated so that overflow does not cause erosion damage or unplanned inundation.
9. **An 18" thick bioretention soil mix liner extending up slopes to maximum storage depth** is required in the bioretention cell, swale, or planter. The bioretention soil mix shall be per Reference Section 11-C. Compost shall meet Specification 1 described in Reference Section 11-C.
10. Do not use filter fabrics between the subgrade and the Bioretention Soil Mix. The gradation between existing soils and Bioretention Soil Mix is typically not great enough to allow significant migration of fines into the Bioretention Soil Mix. Additionally, filter fabrics may clog with downward migration of fines from the Bioretention Soil Mix.
11. On-site soil mixing or placement shall not be performed if Bioretention Soil Mix or subgrade soil is saturated. The bioretention soil mixture should be placed and graded by machinery operating adjacent to the bioretention facility.
12. If machinery must operate in the bioretention cell for soil placement, use light weight equipment with low ground-contact pressure. The soil mixture shall be placed in horizontal layers not to exceed 12 inches per lift for the entire area of the bioretention facility.
13. Compact the Bioretention Soil Mix to a relative compaction of 85 percent of modified maximum dry density (ASTM D1557). Compaction can be achieved by boot packing (simply walking over all areas of each lift), and then apply 0.2 inches (0.5 cm) of water per 1 inch (2.5 cm) of Bioretention Soil Mix depth. Water for settling should be applied by spraying or sprinkling.
14. Prior to placement of the Bioretention Soil Mix, the finished subgrade shall: (a) Be scarified to a minimum depth of 3 inches; (b) have any sediment deposited from construction runoff removed (to remove all introduced sediment, subgrade soil should be removed to a depth of 3 to 6 inches and replaced with Bioretention Soil Mix); and (c) be inspected by the responsible engineer to verify required subgrade condition.
15. If using the default Bioretention Soil Mix described in Reference Section 11-C, pre-placement laboratory analysis for saturated hydraulic conductivity of the bioretention soil mix is not required. Verification of the mineral aggregate gradation, compliance with the compost specifications, and the mix ratio must be provided.
16. Custom bioretention soil mixes may be considered under the adjustment process described in Section 1.4.
17. **Water tolerant plants** such as those in Table C.2.6.A shall be planted in the bottom of the bioretention facility. Plants native to Western Washington are preferred. Trees outside of the saturated zone are allowed as part of bioretention facility designs.
18. A minimum 5-foot **setback** shall be maintained between the outermost edge of the bioretention soil mix and any building structure or property line.

19. Bioretention constructed with imported compost materials are not allowed within one-quarter mile of a sensitive lake if the underlying native soil does not meet the soil suitability criteria for treatment in Section 5.2.1.
20. Bioretention constructed with imported compost materials are not allowed within ¼ mile of those waterbodies listed as category 2, 4, or 5 for either nutrients or low DO determined to be caused by nutrients. These waterbodies are found on Ecology's combined 303(d)/305(b) Water Quality Assessment list. The exception to this prohibition is where phosphorous is the identified nutrient and the underlying native soil meets soil suitability criteria for treatment described in Section 5.2.1.
21. Bioretention swales shall have a minimum 18-inch bottom width. Swales shall be flat in cross section to promote even flow across the width of the swale. See the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable for design details for bioretention swales in the ROW.
22. Bioretention swales shall meet the conveyance requirements described in Section 1.2.4.1 of the SWDM. Maximum 100 year peak flow velocity through bioretention swales is 3 feet per second.
23. Maximum longitudinal (along direction of flow) slope of bioretention swales shall be 6%.
24. For *sites* with **septic systems**, bioretention must be located downgradient of the primary and reserve drainfield areas. CED review staff can waive this requirement if site topography clearly prohibits subsurface flows from intersecting the drainfield.
25. Bioretention is not allowed in critical area **buffers** or on **slopes** steeper than 20%.
26. Bioretention is not allowed within 50 feet of a ***steep slope hazard area, erosion hazard area, or landslide hazard.***
27. Bioretention proposed on slopes steeper than 15% must be approved by a ***geotechnical engineer or engineering geologist*** unless otherwise approved by the CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
28. Bioretention proposed near slopes steeper than 15% must be approved by a ***geotechnical engineer or engineering geologist*** if the facility is located within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15% unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
29. Bioretention that directs overflow towards slopes steeper than 15% may require evaluation and approval of the proposal by a ***geotechnical engineer or engineering geologist*** as determined by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
30. Bioretention proposed within 200 feet of a ***steep slope hazard area, erosion hazard area, or landslide hazard*** must be approved by a ***geotechnical engineer or engineering geologist*** unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
31. Bioretention must not create **flooding or erosion impacts** as determined by CED. If bioretention is proposed near or directs overflows towards a ***landslide hazard, erosion hazard area, or a steep slope hazard area***, CED may require evaluation and approval of the proposal by a ***geotechnical engineer or engineering geologist***. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.

TABLE C.2.6.A WATER TOLERANT PLANTS		
Common Name	Scientific Name	Spacing (on center)
California brome	<i>Bromus carinatus</i>	12 inches
Tufted hair grass	<i>Deschampsia cespitosa</i>	12 inches
Dewey sedge	<i>Carex deweyanna</i>	12 inches
Spike rush	<i>Eleocharis</i> spp.	12 inches
Slough sedge	<i>Carex obnupta</i>	24 inches
Sawbeak sedge	<i>Carex stipata</i>	12 inches
Sedge	<i>Carex</i> spp.	12 inches
Dagger-leaf rush	<i>Juncus ensifolius</i>	12 inches
Spreading rush	<i>Juncus patens</i>	12 inches
Slender rush	<i>Juncus tenuis</i>	12 inches
Small-fruited bulrush	<i>Scirpus microcarpus</i>	12 inches
Yellow-eyed grass	<i>Sisyrinchium californicum</i>	12 inches

C.2.6.2 MINIMUM DESIGN REQUIREMENTS (ROADSIDE BIORETENTION DITCH)

This BMP is not approved for use in the City without an adjustment.

All of the following requirements must be met in order for bioretention to be applicable to a target impervious surface:

1. The roadside bioretention ditch is only allowed to serve road and sidewalk improvements.
2. The roadside bioretention ditch is considered optional only and not required for purposes of complying with the prescriptive BMP list approach from Core Requirement #9 where a standard bioretention cell is deemed infeasible.
3. The longitudinal slope of the road side bioretention ditch shall be consistent with the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable which allow a maximum slope of 6% for grass-lined ditches. Grades between 3% and 6% may require check dams to reduce potential erosion.
4. The roadside bioretention ditch shall meet the conveyance requirements described in Section 1.2.4.1 of the *SWDM*.
5. Flow entrance techniques for energy dissipation shall be utilized and may include where applicable: flow spreaders described in Section 6.2.6 of the *SWDM*, gravel flow spreaders described in Section 6.3.4.2 of the *SWDM*, rock pads for pipe flow entrances, and/or catch basins preceding bioretention where high sediment loads are anticipated. Other equivalent options may be considered. Consideration should be given as to whether the design details specified in Section 4.2.2 (Outfalls) are applicable to a given design.
6. Side slopes shall be per the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable for roadside ditches.
7. Vegetation in the roadside bioretention ditch shall conform to the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable for grass lined road ditches.
8. A minimum 2 ft. wide, 18" thick bioretention soil mix liner is required along the full length of the roadside bioretention ditch. The bioretention soil mix shall be per Reference Section 11-C. Compost shall meet Specification 1 described in Reference Section 11-C.

9. A linear trench of washed rock that is 1.5 ft. deep x 2 ft. wide (typical ditch bottom width) shall be placed underneath the bioretention soil mix liner. The length of the trench shall be that specified in Section C.2.3.3 “Use of Gravel Filled Trenches for Limited Infiltration” based on the tributary area to the roadside bioretention ditch. Where this length is not achievable, the width of the gravel trench may be widened as allowed by ROW or tract width to provide an equivalent area footprint. To slow flows and encourage infiltration, the gravel filled trench shall be broken up along every 50 feet its length by a minimum 4 foot long plug of native, unexcavated soil or native material (or equivalent) free of wood waste, debris, clods or rocks greater than 6” in any dimension, compacted to 95% maximum density (ASTM D1557).
10. Do not use filter fabrics between the subgrade and the Bioretention Soil Mix. The gradation between existing soils and Bioretention Soil Mix is not great enough to allow significant migration of fines into the Bioretention Soil Mix. Additionally, filter fabrics may clog with downward migration of fines from the Bioretention Soil Mix.
11. On-site soil mixing or placement shall not be performed if Bioretention Soil Mix or subgrade soil is saturated. The bioretention soil mixture should be placed and graded by machinery operating adjacent to the bioretention facility.
12. If machinery must operate in the bioretention cell for soil placement, use light weight equipment with low ground-contact pressure. The soil mixture shall be placed in horizontal layers not to exceed 12 inches per lift for the entire area of the bioretention facility.
13. Compact the Bioretention Soil Mix to a relative compaction of 85 percent of modified maximum dry density (ASTM D 1557). Compaction can be achieved by boot packing (simply walking over all areas of each lift), and then apply 0.2 inches (0.5 cm) of water per 1 inch (2.5 cm) of Bioretention Soil Mix depth. Water for settling should be applied by spraying or sprinkling.
14. Prior to placement of the Bioretention Soil Mix, the finished subgrade shall: (a) Be scarified to a minimum depth of 3 inches; (b) have any sediment deposited from construction runoff removed (to remove all introduced sediment, subgrade soil should be removed to a depth of 3 to 6 inches and replaced with Bioretention Soil Mix); and (c) be inspected by the responsible engineer to verify required subgrade condition.
15. If using the default Bioretention Soil Mix described in Reference Section 11-C, pre-placement laboratory analysis for saturated hydraulic conductivity of the Bioretention Soil Mix is not required. Verification of the mineral aggregate gradation, compliance with the compost specifications, and the mix ratio must be provided.
16. Custom bioretention soil mixes may be considered under the adjustment process described in Section 1.4 of the *SWDM*.
17. Bioretention with underdrains is not allowed for Core Requirement #9 unless approved via a *SWDM* adjustment per Section 1.4 that, at minimum, addresses comparable hydraulic performance, water quality concerns, and maintainability. Bioretention with underdrains is allowed for Core Requirement #8.
18. Bioretention constructed with imported compost materials are not allowed within one-quarter mile of a sensitive lake if the underlying native soil does not meet the soil suitability criteria for treatment in Section 5.2.1 of the *SWDM*.
19. Bioretention constructed with imported compost materials are not allowed within ¼ mile of those waterbodies listed as category 2, 4, or 5 for either nutrients or low DO determined to be caused by nutrients. These waterbodies are found on Ecology’s combined 303(d)/305(b) Water Quality Assessment list. The exception to this prohibition is where phosphorous is the identified nutrient and the underlying native soil meets soil suitability criteria for treatment described in Section 5.2.1 of the *SWDM*.

20. For *sites* with **septic systems**, bioretention must be located downgradient of the primary and reserve drainfield areas. CED review staff can waive this requirement if site topography clearly prohibits subsurface flows from intersecting the drainfield.
21. Bioretention is not allowed in critical area **buffers** or on **slopes** steeper than 20%.
22. Bioretention is not allowed within 50 feet of a **steep slope hazard area**, **erosion hazard area**, or **landslide hazard**.
23. Bioretention proposed on slopes steeper than 15% must be approved by a **geotechnical engineer** or **engineering geologist** unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
24. Bioretention proposed near slopes steeper than 15% must be approved by a **geotechnical engineer** or **engineering geologist** if the facility is located within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15% unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
25. Bioretention that directs overflow towards slopes steeper than 15% may require evaluation and approval of the proposal by a **geotechnical engineer** or **engineering geologist** as determined by CED.
26. Bioretention proposed within 200 feet of a **steep slope hazard area**, **erosion hazard area**, or **landslide hazard** must be approved by a **geotechnical engineer** or **engineering geologist** unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
27. Bioretention must not create **flooding or erosion impacts** as determined by CED. If bioretention is proposed near or directs overflow towards a **landslide hazard**, **erosion hazard area**, or a **steep slope hazard area**, CED may require evaluation and approval of the proposal by a **geotechnical engineer** or **engineering geologist**. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.

C.2.6.3 MAINTENANCE INSTRUCTIONS FOR BIORETENTION

If a bioretention on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on the City of Renton's *SWDM* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.6.4 EXAMPLE SIZING CALCULATION

Runoff Source: 20-foot by 20-foot driveway

Equivalent Storage Depth = 1.0 inches (0.083 feet)

Bioretention Storage Volume Needed = 20 feet x 20 feet x 0.083 feet = 33 cubic feet


Note that if the design soil percolation rate is 0.5 inches per hour, a pond 1-foot deep will take 24 hours to drain when filled.

C.2.6.5 CONSTRUCTION SEQUENCING

There are many potential applications and site scenarios where bioretention can be applied. The following techniques highlight the most broadly applicable techniques to be used to protect bioretention during construction. Refer to Appendix D for general site protection measures and Appendix D, Section D.2.1.10 for protection measures specific to existing and proposed on-site BMPs. In addition to those techniques, the following techniques apply specifically for protection of bioretention during construction:

- Prior to construction:
 - The bioretention area shall be clearly identified (e.g., using flagging or high visibility fencing) and protected prior to construction to prevent compaction of underlying soils by vehicle traffic.
 - The Construction SWPPP sheets must outline construction sequencing that will protect the bioretention area during construction.
 - Stabilize upslope construction areas (e.g., using silt fences, berms, mulch, or other Construction SWPPP BMPs) and minimize overland flow distances.
- Excavation:
 - Excavation of bioretention areas shall be performed by machinery operating adjacent to the BMP. No heavy equipment with narrow tracks, narrow tires, or large lugged high pressure tires shall be allowed on the bioretention area footprint.
 - If machinery must operate in the bioretention area for excavation, use lightweight, low ground-contact pressure equipment and rip the base at completion to scarify soil to a minimum of 12 inches.
 - Where feasible, excavate bioretention areas to final grade only after all disturbed areas in the up-gradient project drainage area have been permanently stabilized. (If bioretention areas must be excavated before permanent site stabilization, initial excavation must be conducted to no less than 6 inches of the final elevation of the facility floor.)
 - Excavation of bioretention areas shall not be allowed during wet or saturated conditions.
 - The use of draglines and trackhoes should be considered for constructing bioretention areas.
 - The sidewalls and bottom of a bioretention excavation must be raked or scarified to a minimum depth of 3 inches after final excavation to restore infiltration rates.
- Sediment control:
 - Bioretention shall not be used as a sediment control facility, and all drainage shall be directed away from the bioretention area after initial rough grading.
 - Direct construction site flow away from the bioretention area using applicable Construction SWPPP BMPs (e.g., temporary diversion swales).
- Protect bioretention soil mix from compaction during construction
 - Do not place bioretention soil mix if saturated or during wet periods.
 - Check for compaction prior to planting. If compaction occurs, aerate the bioretention soil and then proceed to plant.

FIGURE C.2.6.A SCHEMATIC REPRESENTATION OF A TYPICAL BIORETENTION CELL



NOTES:

- WATER STORAGE VOLUME PER SECTION C.2.6.1.
- WATER SURFACE AREA AT OVERFLOW ELEVATION MUST BE EQUAL TO AT LEAST 5% OF THE IMPERVIOUS AREA TRIBUTARY TO THE FACILITY.
- BIORETENTION THAT RECEIVES DRAINAGE FROM IMPERVIOUS AND/OR PERVIOUS AREA EXCEEDING THE THRESHOLDS IN SECTION C.2.6 MUST MEET "ADDITIONAL REQUIREMENTS FOR LARGE BIORETENTION FACILITIES" DESCRIBED IN THAT SECTION.






FIGURE C.2.6.B SCHEMATIC REPRESENTATION OF A TYPICAL BIORETENTION WITH CONTAINMENT BERM



NOTES:

- WATER STORAGE VOLUME PER SECTION C.2.6.1.
- WATER SURFACE AREA AT OVERFLOW ELEVATION MUST BE EQUAL TO AT LEAST 5% OF THE IMPERVIOUS AREA TRIBUTARY TO THE FACILITY.
- BIORETENTION THAT RECEIVES DRAINAGE FROM IMPERVIOUS AND/OR PERVIOUS AREA EXCEEDING THE THRESHOLDS IN SECTION C.2.6 MUST MEET "ADDITIONAL REQUIREMENTS FOR LARGE BIORETENTION FACILITIES" DESCRIBED IN THAT SECTION.



C.2.7 PERMEABLE PAVEMENT

Permeable pavements include porous concrete, porous asphalt, cellular confinement gravel systems, unit pavers with a gravel bed, and grassed modular grid systems. There are many types of permeable pavement on the market today. Permeable pavement systems require careful design, construction, and maintenance in order to provide good service life and proper drainage. Manufacturer's recommendations should be strictly followed for proprietary systems.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, permeable pavement may be applied to *non-pollution generating impervious surface* (sidewalks or patio) and to those *pollution generating impervious surfaces* (e.g., driveway, road, or parking area) where the soil beneath the BMP meets the following properties:

- Minimum organic matter content of 1.0%, and
- Minimum cation exchange capacity of 8 milliequivalents per 100 grams

A 6" sand layer must be included in the design beneath the permeable pavement if the soil beneath the BMP does not meet the properties listed above. This BMP is not allowed in **Zone 1 of the Aquifer Protection Area**. Permeable pavement proposed for roadway improvements (e.g., roads and sidewalks) shall be per the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable or as otherwise approved by the City Engineer.

Design Considerations

Application of permeable pavement on steeper slopes may not be suitable because water draining through permeable base may daylight downslope. Ideally, permeable pavement slopes should be less than 5%. Areas with a high water table or highly impervious soils may be unsuitable for this pavement type.

Runoff from other impervious areas ("run on") may be directed to permeable pavements that meet the following criteria:

Run-on area is limited to a maximum of 5 times the permeable pavement area to which the run-on is directed, of which no more than 2 times may be from pollution generating impervious surfaces. An area-weighted ratio shall be used for a mix of pollution generating and non-pollution generating impervious surface areas (e.g., a contributing area that is 50% parking lot and 50% roof area would be subject to a maximum run-on of 3.5 times the permeable pavement area).

Run-on is not allowed from pervious surfaces.

For permeable pavement installations on slopes greater than 5%, impermeable check dams are required underneath the pavement. The surface area of the impermeable check dams shall not be counted as part of the permeable pavement when determining the allowable area of run-on.

Target impervious surfaces from which runoff is directed to permeable pavements are considered to have met the minimum on-site BMP implementation requirements contained in the "Small Lot and Large Lot requirements" lists located in the *SWDM* Section 1.2.9.2 and Appendix C, Section C.1.3. No on-site BMP modeling credits for sizing flow control or water quality facilities are given for surfaces that are run-on to permeable pavements.

Infeasibility Criteria

Permeable pavement is considered infeasible and not required for projects that cannot meet the minimum design requirements for permeable pavement described or via the permeable pavement infeasibility criteria list below. Where the minimum design requirements call for geotechnical evaluation and approval for permeable pavement that proposes to discharge towards or is within described setbacks of a *steep slope hazard area, erosion hazard area, landslide hazard, or slopes greater than 15%*, permeable pavement is

considered infeasible and not required. Though not required in these circumstances, a project proponent may still opt to use permeable pavement as long as the geotechnical evaluation and approval requirement is met. Functionally equivalent design alternatives to permeable pavement may be considered to meet BMP requirements if approved by CED. A functionally equivalent design will provide the same infiltrative capacity (storage and infiltration rate) or be demonstrated via modeling to meet the LID Performance Standard. An example of an equivalent design includes a standard impermeable pavement design where runoff is collected and redistributed/infiltrated below or adjacent to the pavement.

Required Soils Report

Many locations in the City have soils that are underlain by a compacted layer of soil (i.e., glacial till or hardpan) which severely limits soaking capacity and causes water to perch on the relatively impervious layer during the wet season. In other areas, soil does not have the properties that reduce the risk of groundwater contamination from typical stormwater runoff from pollution generating surfaces. These factors can make permeable pavements impractical, unreliable, or deleterious to groundwater quality. Thus, a soils report is necessary to identify soil types, soil characteristics, depth to impermeable layers (hardpan) or the maximum wet season groundwater level, and infiltration rates.

Detailed requirements for the soils report are found under “Required Soils Report” in Section 1.3 of the *SWDM*.

Operation and Maintenance

See Section C.2.7.7.

Permeable Pavement Infeasibility Criteria List

These are conditions that make permeable pavement not required to be implemented as part of the prescriptive BMP lists detailed in Core Requirement #9 of the *SWDM* and Section C.1.3 of Appendix C. The lists require BMPs be evaluated and installed to the maximum extent feasible. Where determined infeasible by these criteria, an applicant has the option to propose a functional design via the adjustment process described in Section 1.4 of the *SWDM* in order to: (a) use the on-site BMP facility modeling credits described in *SWDM* Section 1.2.9.4; (b) to use in achieving the LID Performance Standard (where required or optional); or (c) to meet the minimum on-site BMP implementation requirements contained in the “Small Lot and Large Lot requirements” lists located in *SWDM* Section 1.2.9.2 and Appendix C, Section C.1.3.

These criteria also apply to impervious pavements that would employ stormwater collection from the surface of impervious pavement with redistribution below the pavement.

Citation of any of the following infeasibility criteria must be based on an evaluation of site-specific conditions and a written recommendation from an appropriate licensed professional (e.g., engineer, geologist, hydrogeologist).

1. Where professional geotechnical evaluation recommends infiltration not be used due to reasonable concerns about erosion, slope failure, or down gradient flooding.
2. Within an area whose ground water drains into an *erosion hazard area* or *landslide hazard*.
3. Where infiltrating and ponded water below new permeable pavement area would compromise adjacent impervious pavements.
4. Where infiltrating water below a new permeable pavement area would threaten existing below grade basements.
5. Where infiltrating water would threaten shoreline structures such as bulkheads.
6. Down slope of steep, erosion prone areas that are likely to deliver sediment.
7. Where fill soils are used that can become unstable when saturated.

8. Excessively steep slopes where water within the aggregate base layer or at the sub-grade surface cannot be controlled by detention structures and may cause erosion and structural failure, or where surface runoff velocities may preclude adequate infiltration at the pavement surface.
9. Where permeable pavements cannot provide sufficient strength to support heavy loads at industrial facilities such as ports.
10. Where installation of permeable pavement would threaten the safety or reliability of pre-existing underground utilities, pre-existing underground storage tanks, or pre-existing road sub-grades.

The following criteria can be cited as reasons for a finding of infeasibility without further justification (though some require professional services to make the observation):

11. Within an area designated as an *erosion hazard area* or *landslide hazard*.
12. Within 50 feet from the top of slopes that are greater than 20%.
13. For properties with known soil or ground water contamination (typically federal Superfund sites or state cleanup sites under the Model Toxics Control Act [MTCA]):
 - a) Within 100 feet of an area known to have deep soil contamination;
 - b) Where ground water modeling indicates infiltration will likely increase or change the direction of the migration of pollutants in the ground water;
 - c) Wherever surface soils have been found to be contaminated unless those soils are removed within 10 horizontal feet from the infiltration area;
 - d) Any area where these facilities are prohibited by an approved cleanup plan under the state Model Toxics Control Act or Federal Superfund Law, or an environmental covenant under Chapter 64.70 RCW.
14. Within 100 feet of a closed or active landfill.
15. Within 100 feet of a drinking water well, or a spring used for drinking water supply, if the pavement is a pollution-generating surface. Within *Zone 1 of the Aquifer Protection Area*.
16. Within 10 feet of a small on-site sewage disposal drainfield, including reserve areas, and grey water reuse systems. For setbacks from a "large on-site sewage disposal system," see Chapter 246-272B WAC.
17. Within 10 feet of any underground storage tank and connecting underground pipes, regardless of tank size. As used in these criteria, an underground storage tank means any tank used to store petroleum products, chemicals, or liquid hazardous wastes of which 10% or more of the storage volume (including volume in the connecting piping system) is beneath the ground surface.
18. At multi-level parking garages, and over culverts and bridges.
19. Where the site design cannot avoid putting pavement in areas likely to have long-term excessive sediment deposition after construction (e.g., construction and landscaping material yards).
20. Where the site cannot reasonably be designed to have a porous asphalt surface at less than 5 percent slope, or a pervious concrete surface at less than 10 percent slope, or a permeable interlocking concrete pavement surface (where appropriate) at less than 12 percent slope. Grid systems upper slope limit can range from 6 to 12 percent; check with manufacturer and local supplier.
21. Where the native soils below a pollution-generating permeable pavement (e.g., road or parking lot) do not meet the soil suitability criteria for providing treatment:
 - Minimum organic matter content of 1.0%, and
 - Minimum cation exchange capacity of 8 milliequivalents per 100 grams

Note that where the soil beneath the infiltration BMP does not have properties that reduce the risk of groundwater contamination, the applicant has the option of using permeable pavement if a 6" sand layer beneath the permeable pavement is included in the design. This approach is optional and does not make permeable pavement required to be implemented as part of the prescriptive BMP lists detailed in Core Requirement #9 of the *SWDM* and Section C.1.3 of Appendix C.

22. Where seasonal high ground water or an underlying impermeable/low permeable layer would create saturated conditions within one foot of the bottom of the lowest gravel base course.
23. Where underlying soils are unsuitable for supporting traffic loads when saturated. Soils meeting a California Bearing Ratio of 5% are considered suitable for residential access roads.
24. Where appropriate field testing indicates soils have a measured (a.k.a., initial) native soil saturated hydraulic conductivity less than 0.3 inches per hour.
25. Roads that receive more than very low traffic volumes, and areas having more than very low truck traffic. Roads with a projected average daily traffic volume of 400 vehicles or less are very low volume roads (AASHTO, 2001) (U.S. Dept. of Transportation, 2013). Areas with very low truck traffic volumes are roads and other areas not subject to through truck traffic but may receive up to weekly use by utility trucks (e.g., garbage, recycling), daily school bus use, and multiple daily use by pick-up trucks, mail/parcel delivery trucks, and maintenance vehicles.
Note: This infeasibility criterion does not extend to sidewalks and other non-traffic bearing surfaces.
26. Where replacing existing impervious surfaces unless the existing surface is a non-pollution generating surface over an outwash soil with a saturated hydraulic conductivity of four inches per hour or greater.
27. At sites defined as "high use sites."
28. In areas with "industrial activity" as identified in 40 CFR 122.26(b)(14).
29. Where the risk of concentrated pollutant spills is more likely such as gas stations, truck stops, and industrial chemical storage sites.
30. Where routine, heavy applications of sand occur in frequent snow zones to maintain traction during weeks of snow and ice accumulation, including sidewalks within 7 feet of driving lanes with sand application.
31. The areas contributing runoff to the permeable pavement facilities exceed the maximum run-on limits:
 - Pollution-generating impervious surfaces (e.g., roadways, parking lots) exceed the maximum run-on area ratio of 2:1
 - Non-pollution generating impervious surfaces (e.g., roofs, sidewalks) exceed the maximum run-on area ratio of 5:1

C.2.7.1 MINIMUM DESIGN REQUIREMENTS

All of the following requirements must be met in order for permeable pavement to be applicable to a *target impervious surface*:

1. One of the following types of permeable pavement must be used in accordance with the design specifications for each type as set forth in Sections C.2.7.2 through C.2.7.6:
 - **Porous concrete** (see Section C.2.7.2)
 - **Porous asphalt** (see Section C.2.7.3)
 - **Permeable pavers** (see Section C.2.7.4)
 - **Modular grid pavement** (see Section C.2.7.5)
 - **Grassed modular grid pavement** (see Section C.2.7.6)

2. Permeable pavements shall be installed in accordance with the manufacturer's specifications, except when such specifications are less stringent than those set forth in Sections 2.7.2 through C.2.7.6. A schematic representation of permeable pavement is shown on Figure C.2.7.1.A.
3. Permeable pavements shall not be placed on slopes steeper than 5% for porous asphaltic concrete and 10% for all other types.
4. For permeable pavements placed on slopes steeper than 5%, impermeable check dams shall be placed on the subgrade and below the pavement surface with the intent to increase infiltration, improve flow attenuation, and reduce structural problems associated with subgrade erosion on slopes (See Figure C.2.7.1.B). Check dams should have an overflow drain invert placed at the maximum ponding depth created by the check dam. Based on an assumed 5" check dam height in a 6"-thick gravel storage base, check dam spacing shall range from 4 feet on center for 10% slopes to 8 feet on center for 5% slopes and interpolated linearly for slopes in between. At minimum, one check dam shall be provided at the toe of the subgrade/downstream limit of the permeable pavement section. Check dams used to achieve LID Performance modeling shall be placed as required by the design—note that the area of the check dams is not counted as part of the infiltrative footprint when modeling.
5. Permeable pavements that are pollution generating are only allowed where the underlying soils meet criteria for groundwater protection:
 - Minimum organic matter content of 1.0%, and
 - Minimum cation exchange capacity of 8 milliequivalents per 100 grams

Where the soil beneath the infiltration BMP does not have properties that reduce the risk of groundwater contamination, the applicant has the option of using permeable pavement if a 6" sand layer beneath the permeable pavement is included in the design. This approach is optional and does not prompt the requirement that the permeable pavement be implemented as part of the prescriptive BMP lists detailed in Core Requirement #9 of the *SWDM* and Section C.1.3 of Appendix C.

6. Permeable pavement is not allowed within 50 feet of a *steep slope hazard area, erosion hazard area, or landslide hazard*.
7. Permeable pavement proposed near slopes steeper than 15% must be approved by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by CED if the facility is located within a setback from the top of slope equal to the total vertical height of the slope area that is steeper than 15%. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
8. Permeable pavement that directs overflow towards slopes steeper than 15% may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by CED. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.
9. Permeable pavement proposed within 200 feet of a *steep slope hazard area, erosion hazard area, or landslide hazard* must be approved by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by CED.
10. Permeable pavement must not create **flooding or erosion impacts** as determined by CED. If permeable pavement is proposed near or directs overflow towards a *landslide hazard, erosion hazard area, or a steep slope hazard area*, CED may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist*. The geotechnical analysis must consider cumulative impacts from the project and surrounding areas under full built-out conditions.

Underdrain (if required)

Underdrain systems must be installed for private roads and privately maintained facilities if the permeable pavement is:

- Located near sensitive infrastructure (e.g., unsealed basements) and potential for flooding is likely
- Used for filtering stormwater flows from gas stations or other pollutant hotspots (requires an impermeable liner)
- Located above subgrade soils with a measured infiltration rate of less than 0.3 inches per hour.
- In an area that does not provide a minimum of 3 feet of clearance between the lowest elevation of the bioretention soil mix, or any underlying gravel layer, and the seasonal high groundwater elevation or other impermeable layer

The underdrain pipe diameter will depend on hydraulic capacity required. The underdrain shall be connected to an *acceptable discharge point* which can either be an enclosed drainage system (i.e., pipe system, culvert, or tightline) or an open drainage feature (e.g., ditch, channel).

Requirements associated with the underdrain design include:

1. The underdrain must be elevated within the aggregate base course to protect the pavement wearing course from saturation.
2. Slotted subsurface drain PVC per ASTM D1785 SCH 40.
3. Slots should be cut perpendicular to the long axis of the pipe and be 0.04 to 0.069 inches by 1 inch long and be spaced 0.25 inches apart (spaced longitudinally). Slots should be arranged in four rows spaced on 45-degree centers and cover ½ of the circumference of the pipe.
4. Underdrain pipe shall have a minimum diameter of 8 inches in the public ROW and 6 inches for private property.
5. Underdrain pipe slope shall be no less than 0.5 percent unless otherwise specified by an engineer.
6. Pipe shall be placed in filter material and have a minimum cover depth of 12 inches and bedding depth of 6 inches. Cover depth may be reduced up to 6 inches in order to discharge stormwater from the facility under gravity flow conditions while meeting the applicable engineering standards, if approved by the City.
7. Filter material shall meet the specifications in Table 2.7.1.A.

TABLE C.2.7.1.A. UNDERDRAIN AGGREGATE	
Sieve Size	Percent Passing
¾ inch	100 percent
¼ inch	30 to 60 percent
U.S. No. 8	20 to 50 percent
U.S. No. 50	3 to 12 percent
U.S. No. 200	0 to 1 percent

11. Underdrains shall have a maintenance access point (e.g., cleanout, observation port, overflow structure) at each end of a facility and a minimum of every 100 feet along the pipe. Cleanouts and observation ports shall have locking cast iron caps and shall be constructed of non-perforated pipe (sized to match the underdrain diameter).
12. If an orifice is included in the design, the minimum diameter shall be 0.5 inches to minimize clogging and maintenance requirements.

Overflow

Minimum design requirements associated with the overflow design for permeable pavement include the following:

1. Overflow shall be designed to convey any flow exceeding the capacity of the facility. Options include:
 - Subsurface slotted drain pipe(s) set at the design ponding elevation to route flow to a conveyance system
 - Lateral flow through the storage reservoir to a daylighted conveyance system
2. For permeable pavement installed on a sloped subgrade, at least one overflow shall be sited at the downslope extent of the facility.
3. If a slotted overflow pipe is used to collect water in the permeable pavement section, the pipe diameter and spacing shall be designed based on the hydraulic capacity required. A non-perforated cleanout (sized to match underdrain diameter) shall be connected to the underdrain every 100 feet at a minimum.
4. A minimum wearing course surface slope of 1 percent is required (2 percent recommended) to ensure positive surface drainage should the surface become clogged.
5. The designer shall consider the flow path of water when the permeable pavement section is fully saturated to the maximum design depth or when the wearing course is clogged to confirm there are no unanticipated discharge locations (e.g., impact to intersecting utility trenches, sheet flow to adjacent properties). The flow path shall be described on the plan submittal.

FIGURE C.2.7.1.A SCHEMATIC REPRESENTATION OF PERMEABLE PAVEMENT





FIGURE C.2.7.1.B SCHEMATIC REPRESENTATION OF PERMEABLE PAVEMENT WITH CHECK DAMS



C.2.7.2 POROUS CONCRETE

Porous concrete consists of a mix of aggregate, cement paste, water and admixtures, but contains less fine aggregate than conventional concrete. Voids in the hardened concrete allow water to drain through the surface into the subgrade.

Uses: Sidewalks, patios, parking areas, roads and driveways.

Design Specifications

1. A minimum of 6 inches of free-draining sand or gravel base is required under the porous concrete surface.
2. The free-draining base shall have less than 5% fines (material passing the #200 sieve) based on the fraction passing the #4 sieve.
3. The porous concrete pavement shall be permeable enough to absorb water at a minimum rate of 20 inches per hour immediately after the pavement surface has been wetted continuously for at least 10 minutes. Compliance with this minimum rate shall be checked prior to construction approval of the pavement. Compliance may be checked using a simple bucket test in which 5 gallons of water are poured onto the pavement surface all at once from a 5-gallon bucket. If nothing but a scant amount of water puddles or runs off the surface, then the pavement is considered to meet the minimum rate of absorption. If this test is not conclusive, use of ASTM C1701 is recommended using a 12-inch ring sealed at the base to the pavement surface shall be used to measure the actual rate of absorption. At least one test should be conducted per 1,000 square feet of permeable pavement. As an alternative for large areas (e.g., parking areas), testing observation may be accomplished while walking behind a slowly moving water truck discharging water at an acceptable rate for the test (observable volume and rate of application similar, at least, to the bucket test).
4. Porous concrete proposed for roadway improvements (e.g., roads and sidewalks) shall be per the City of Renton Standard Details and the requirements of the City of Renton Transportation Department and Surface Water Utility as applicable or as otherwise approved by the City Engineer.
5. Sidewalks and patios on private property not subject to vehicles shall be a minimum of 4 inches thick and should have a minimum 28-day compressive strength of 2,000 psi.

C.2.7.3 POROUS ASPHALT

Porous asphalt uses a mix that contains less fine aggregate than conventional asphaltic concrete. Voids in the pavement allow water to drain through the surface into the subgrade.

Uses: Sidewalks, patios, parking areas, roads and driveways.

Design Specifications

Same as for porous concrete.

C.2.7.4 PERMEABLE PAVERS

Permeable pavers provide a solid surface but allow natural drainage and migration of water into the earth by permitting water to drain through the spaces between the pavers. On the Internet, there are a number of manufacturers and installers.

Uses: Sidewalks, patios, parking areas, and driveways.

Design Specifications

Same as for porous concrete, except that the pavement thickness shall be as specified by the manufacturer or a *civil engineer*. Use of ASTM C1781 is recommended to confirm the initial surface absorption rate.

C.2.7.5 MODULAR GRID PAVEMENT

Modular grid pavement consists of a lattice of concrete, plastic, or other load bearing material over a permeable base of gravel or sand (or both). Several manufacturers supply the modular grid materials used for such pavement. These materials include plastic lattice, concrete pavers, or special forms for a cast-in-place concrete grid. These systems use a confining structure incorporated into the subgrade with an engineered fill material.

Uses: Low-traffic or infrequently used areas such as low-traffic driveways, overflow parking, event parking, church parking, employee parking, maintenance access roads, etc.; they are not allowed road rights-of-way.

Design Specifications

1. A minimum of 6 inches of free draining base material (sand or gravel) is required under the modular grid material.
2. The modular grid material must be installed according to the manufacturer's instructions.
3. The surface area of the modular grid openings must be at least 50% of the total surface area of the modular grid pavement.
4. The modular grid openings must be filled with gravel, sand, or a mixture of both.
5. Smooth surface walkways may be run across modular grid pavements, provided the impervious surfaced walkways do not exceed 10 percent of the total pavement surface.

C.2.7.6 GRASSED MODULAR GRID PAVEMENT

Grassed modular grid pavement is basically a modular grid pavement with grass planted in the openings or in a thin layer of soil over the grid material. The benefits of this measure are reduced runoff peaks and volumes resulting from the increased infiltration of stormwater, the increased water storage provided in the grid soil and base, and the increased evapotranspiration provided by the grass. The grassed surface also helps remove pollutants that are left behind by vehicles.

Uses: Low-traffic or infrequently used areas such as low-traffic driveways, overflow parking, event parking, church parking, employee parking, maintenance access roads, etc.; they are not allowed in road rights-of-way.

Design Specifications

1. A minimum of 6 inches of free draining base material (sand or gravel) is required under the modular grid material.
2. The modular grid material must be installed according to the manufacturer's instructions.
3. The surface area of the modular grid openings must be at least 50% of the total surface area of the modular grid pavement.
4. The modular grid openings must be filled with a sandy soil mix suitable for growing grass as specified by the manufacturer's instructions or a landscape architect.
5. Smooth surface walkways may be run across modular grid pavements, provided the impervious surfaced walkways do not exceed 10 percent of the total pavement area.

C.2.7.7 MAINTENANCE INSTRUCTIONS FOR PERMEABLE PAVEMENT

If the permeable pavement on-site BMP is proposed for a project, maintenance and operation instructions, plus any provided by the manufacturer or installer, must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions or manufacturer's recommendations. Future updates to these instructions will be posted on the City of Renton's *SWDM* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.7.8 CONSTRUCTION SEQUENCING

There are many potential applications and site scenarios where permeable pavement can be applied. The following techniques highlight the most broadly applicable techniques to be used to protect permeable pavement during construction. Refer to Appendix D for general site protection measures and Appendix D, Section D.2.1.10 for protection measures specific to existing and proposed on-site BMPs. In addition to those techniques, the following techniques apply specifically for protection of permeable pavement during construction:

- Prior to construction:
 - Use procedural BMPs to plan construction. For example, phase construction to minimize compaction, sedimentation, or structural damage to the permeable pavement.
 - The permeable pavement area shall be clearly identified (e.g., using flagging or high visibility fencing) and protected prior to construction to prevent compaction of underlying soils by vehicle traffic.
 - The Construction SWPPP sheets must outline construction sequencing that will protect the permeable pavement during construction.
 - Stabilize upslope construction areas (e.g., using silt fences, berms, mulch, or other Construction SWPPP BMPs) and minimize overland flow distances.
- During construction:
 - Use physical construction BMPs SWPPP BMPs and/or grade the site to avoid sediment laden runoff from reaching permeable pavements.
 - Place protective surfaces (e.g., waterproof tarps and steel plates) over any permeable pavement areas used for construction staging.
 - Do not drive sediment-laden construction equipment on the base material or pavement. Do not allow sediment-laden runoff on permeable pavements or base materials.
 - Once the pavement is finished and set, cover the pavement surface with plastic and geotextile to protect from other construction activities. Close and protect the pavement area until the site is permanently stabilized.
 - Incorporate measures to protect road subgrade from over compaction and sedimentation if permeable pavement roads are used for construction access.
 - Cover the aggregate base or pavement surface with protective geotextile fabric and protect fabric with steel plates or gravel. Gravel should only be used to protect the fabric placed over aggregate base.
- Post construction:
 - Once construction is complete and the site is permanently stabilized, remove protective geotextile, clean, and complete pavement installation.

C.2.8 RAINWATER HARVESTING

Rainwater harvesting means the collection and storage of roof runoff for domestic or irrigation uses. Rainwater harvesting systems include a collection area, a filter, a storage device and an outflow device. Storage may be above ground or below grade and may consist of tanks or vaults. Example configurations are shown in Figure C.2.8.A and Figure C.2.8.B. The stored water may be used for any domestic purpose including irrigation. The distribution system may be gravity or pumped.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, rainwater harvesting systems may be used with any roof area.

Design Considerations

Provisional specifications available in the State Uniform Building Code (UBC) for commercial rainwater systems may be used for guidance in designing the various elements of a non-commercial system.

Note: a water right is not required for on-site storage and use of rooftop or guzzler-collected rainwater. A guzzler is a device used to catch and store rainwater to provide drinking water for wildlife, livestock, or birds.

Operation and Maintenance

See Section C.2.8.2 and Minimum Design Requirement 2 below.

C.2.8.1 MINIMUM DESIGN REQUIREMENTS

All of the following requirements must be met in order for rainwater harvesting to be applicable to a *target impervious surface*:

1. For a rainwater harvesting system proposed to be used towards meeting Core Requirement #3 (Flow Control) or Core Requirement #9 (On-site BMPs) requirements, an approved drainage adjustment is required that demonstrates the system's impact/benefit and specifies conditions of use to achieve the same.
2. To ensure the system functions as designed and provides the required stormwater management, **system-specific maintenance and operation instructions** must be submitted and approved by CED. Such instructions should be prepared by the system's manufacturer or installer.
3. A minimum 5-foot **setback** shall be maintained between any part of the rainwater harvesting system and any property line.

FIGURE C.2.8.A SCHEMATIC REPRESENTATION OF A TYPICAL ABOVE GROUND RESERVOIR CONFIGURATION (STENSROD, 1978)







FIGURE C.2.8.B SCHEMATIC REPRESENTATION OF VARIOUS POSSIBLE RESERVOIR CONFIGURATIONS (STENSROD, 1978)




RESERVED ABOVE GROUND
(INSULATE IF NECESSARY)



PARIALLY BURIED RESERVOIR



RESERVOIR BURIED
OUTSIDE BASEMENT



RESERVOIR IN BASEMENT

C.2.8.2 MAINTENANCE INSTRUCTIONS FOR RAINWATER HARVESTING

If the rainwater harvesting on-site BMP is proposed for a project, maintenance and operation instructions must be incorporated into the maintenance and operation instructions required per Minimum Design Requirement 2. All such instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions or manufacturer's recommendations. Future updates to these instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.9 REDUCED IMPERVIOUS SURFACE CREDIT

Reduced impervious surface credit means a credit toward meeting impervious surface on-site BMP requirements through application of techniques that result in less impervious surface coverage than is typically constructed or allowed for a particular land use. The credit may be used to mitigate for impervious surface to which on-site BMPs must be applied as specified by BMP Requirement 3 in either Section C.1.3.1 or Section C.1.3.2 .

To receive the credit, a reduction in impervious surface below established norms must be assured through covenant and/or alternative design of impervious surfaces as described in the subsections below. For every square foot of reduced impervious surface assured, an equal area of **actual proposed target impervious surface** may be credited as mitigated, provided the runoff from the credited area is either directed to vegetated pervious areas on the *site* or discharged through a perforated pipe connection per Section C.2.11.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, the reduced impervious surface credit may be applied to any impervious surface such as a roof, driveway, parking area, or road.

Operation and Maintenance

See Section C.2.9.7.

C.2.9.1 MINIMUM DESIGN REQUIREMENTS

All of the following requirements must be met in order for the reduced impervious surface credit to be applicable to a *target impervious surface*:

1. **One or more of the following techniques** must be used to reduce, restrict, or otherwise mitigate for impervious surface subject to on-site BMPs:
 - **Restricted footprint** (see Section C.2.9.2)
 - **Wheel strip driveways** (see Section C.2.9.3)
 - **Minimum disturbance foundation** (see Section C.2.9.4)
 - **Open grid decking over pervious surface** (see Section C.2.9.5)
2. The area of *target impervious surface credited as mitigated* by the reduced impervious surface credit must meet all of the following requirements:
 - a) The area credited as mitigated must be no more than 10,000 square feet on any one *site/lot* unless the surface is served by a flow control facility designed by a *civil engineer* in accordance with Section 1.2.3 of the *SWDM*.

- b) Any runoff from the area credited as mitigated must be directed to vegetated pervious areas on the *site/lot* or discharged through a perforated pipe connection per Section C.2.11.
- c) Any portion of the area credited as mitigated that is *pollution-generating impervious surface* must be less than 5,000 square feet on any one *site/lot* unless the surface is served by a water quality treatment facility designed by a *civil engineer* in accordance with Section 1.2.8 of the *SWDM*.

C.2.9.2 RESTRICTED FOOTPRINT

Restricted footprint means the recording of a covenant that limits the amount of future impervious surface coverage on a *site/lot* to an amount less than the norm as specified below:

1. For *sites/lots* that are **smaller than 22,000 square feet**, any recorded limit on total impervious surface less than a norm of 4,000 square feet or the maximum allowed by the *site/lot's* zoning, whichever is smaller, qualifies for a restricted footprint credit equal to the difference in square footage. In other words, for every square foot that the recorded limit is below the norm, an equal area of **actual proposed target impervious surface** is credited as mitigated subject to Minimum Design Requirement 2 in Section C.2.9.1.
2. For *sites/lots* that are **between 22,000 square feet and 250,000 square feet**, any recorded limit of total impervious surface in an amount less than a norm of 4,000 square feet or 4% of the *site/lot* area, whichever is greater, qualifies for a restricted footprint credit equal to the difference in square footage. For every square foot that the recorded limit is below the norm, an equal area of **actual proposed target impervious surface** is credited as mitigated subject to Minimum Design Requirement 2 in Section C.2.9.1.
3. For *sites/lots* that are **greater than 250,000 square feet**, no restricted footprint credit is available.

C.2.9.3 WHEEL STRIP DRIVEWAYS

Wheel strip driveways consist of two pavement strips and grass planted in amended soil, all within a "driveway width norm" of 10 feet. Subject to Minimum Design Requirement 2 in Section C.2.9.1, an area of **actual proposed target impervious surface** equal to the driveway length times 10 feet of width is credited as mitigated if all of the following requirements are met:

1. The **pavement strips** must be no more than 2.5-feet wide.
2. At least 4 feet of the driveway width must be **amended soil planted with grass**. The amended soil must consist of at least 4 inches of well-rotted compost tilled into the upper 8 inches of the soil between the impervious strips.

C.2.9.4 MINIMUM DISTURBANCE FOUNDATION

Minimum disturbance foundations consist of pile or pier supports such that all or a portion of the finished living space is elevated over a pervious surface. The intent of this system is to provide additional storage for runoff in the soil beneath the structure. Subject to Minimum Design Requirement 2 in Section C.2.9.1, this technique qualifies for a 100% credit if the following requirements are met:

1. The **pervious surface beneath** the elevated portion of the structure must be either undisturbed native soil or amended soil. Any amended soil must consist of at least 4 inches of well-rotted compost tilled into the upper 8 inches of the soil.
2. **Runoff** from the structure must be discharged via downspouts or sheet flow onto a vegetated surface or into a 4- to 6-inch gravel bed within close proximity of the elevated structure. Runoff discharging from downspouts onto a vegetated surface must be via splash blocks.

C.2.9.5 OPEN GRID DECKING OVER PERVIOUS SURFACE

Open grid decking over pervious surface is a steel, plastic, or wood deck with regularly spaced openings suspended over a pervious surface. Such decking may be used as an alternative to impervious surface for such applications as parking or other vehicle use, and/or walkways, etc. This technique qualifies for a 100% credit if the following requirements are met:

1. The pervious surface beneath the decking must be either undisturbed native soil, or amended soil in accordance with Section C.2.13 which requires soil amendment to mitigate for lost moisture holding capacity where compaction or removal of some or all of the duff layer or underlying topsoil has occurred.
2. The full area of decking over pervious surface may be used to qualify for a reduced impervious surface credit subject to Minimum Design Requirement 2 in Section C.2.9.1. This means that for every square foot of decking over pervious surface, an equal amount of *target impervious surface* is considered mitigated, except as restricted by Minimum Design Requirement 2 in Section C.2.9.1.
3. The **openings** in the decking must be at least 8% of the surface area and must be evenly distributed across the surface such that there are at least 2 openings per square foot.
4. The decking and its supports shall be designed by a *civil engineer* or structural engineer as deemed necessary by CED.

C.2.9.6 EXAMPLE CREDIT CALCULATIONS

A project proposes to add 3,500 square feet of impervious surface to a 2-acre lot, which includes a 2,575-square-foot house (footprint) with a 1,600 square foot minimum disturbance foundation, a 600-square-foot parking pad, 25-foot-long wheel strip driveway (125 square feet), and a 200-square-foot wood deck. The 3,500 sf of impervious surface includes the two concrete wheel strips, which are each 2.5 feet wide (125 sf). The project is subject to the Large Lot BMP Requirements in Section C.1.3.2, so all new impervious surface (i.e., *target impervious surface*) must be mitigated with on-site BMPs. Full dispersion and full infiltration are not applicable or feasible. Therefore, other on-site BMPs in Section C.2 must be used to mitigate all 3,500 square feet of proposed *target impervious surface*.

Restricted Footprint

Because the 3,500 square feet of proposed impervious surface is less than the established norm for the lot of 4,000 square feet, the project is eligible for a reduced footprint credit if a covenant is recorded that limits impervious surface coverage to the 3,500 square feet proposed.

Therefore, the area of *target impervious surface* credited as mitigated is: $4,000 \text{ sf} - 3,500 \text{ sf} = 500 \text{ sf}$

This leaves a remaining impervious area (restricted footprint) of 3,000 sf ($3,500 \text{ sf} - 500 \text{ sf} = 3,000 \text{ sf}$) that must be mitigated by other on-site BMPs.

Wheel Strip Driveway

If the wheel strip driveway complies with the specifications in Section C.2.9.3, an area of actual proposed *target impervious surface* equal to the area that would be covered by a 10-foot-wide driveway (i.e., the established “driveway width norm”) is credited as mitigated. The wheel strips themselves are considered part of the actual proposed *target impervious surface* area being credited as mitigated.

Thus, the area of *target impervious surface* credited as mitigated is: $10 \text{ ft} \times 25 \text{ ft} = 250 \text{ sf}$

This leaves a remaining impervious area of 2,750 sf ($3,000 \text{ sf} - 250 \text{ sf} = 2,750 \text{ sf}$) that must be mitigated by other on-site BMPs.

Minimum Disturbance Foundation

If the 1,600 square foot minimum disturbance foundation complies with the specifications in Section C.2.9.4, the foundation area is credited at 100%.

Thus, the area of *target impervious surface* credited as mitigated is: **1,600 sf**

This leaves a remaining impervious area of 1,150 sf (2,750 sf – 1,600 sf = 1,150 sf) that must be mitigated by other on-site BMPs.

Open Grid Decking Over Pervious Surface

If the 200 square-foot wood deck complies with the specifications in C.2.9.5, the deck is credited at 100%.

Thus, the total area of *target impervious surface* credited as mitigated is: **200 sf**

This leaves a remaining impervious area of 950 sf (1,150 sf – 200 sf = 950 sf) that must be mitigated by other on-site BMPs.

C.2.9.7 MAINTENANCE INSTRUCTIONS

If a reduced impervious surface on-site BMP is proposed for a project, maintenance and operation instructions must be recorded in or as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on the City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.10 NATIVE GROWTH RETENTION CREDIT

Native growth retention credit means a credit toward meeting impervious surface on-site BMP requirements through voluntary preservation of *native vegetated surface* on otherwise unencumbered land that is flat to moderately sloped. The credit may be used to mitigate for impervious surface to which on-site BMPs must be applied as specified and allowed in Section C.1.3 and Section 1.2.9 of the *SWDM*.

To receive the credit, at least 3.5 square feet of *native vegetated surface* must be preserved for every square foot of impervious surface to be mitigated by the *native vegetated surface*. In other words, for every 3.5 square feet of native vegetated pervious surface preserved, one square foot of *target impervious surface* may be credited as mitigated, provided the runoff from the credited area is either directed to vegetated pervious areas on the *site* or discharged through a perforated pipe connection per Section C.2.11.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, the native growth retention credit may be applied to any impervious surface such as a roof, driveway, parking area, or road.

Operation and Maintenance

See Section C.2.10.3.

C.2.10.1 MINIMUM DESIGN REQUIREMENTS

All of the following requirements must be met in order for the native growth retention credit to be applicable to a **target impervious surface**:

1. The area of native vegetated surface being preserved (donor area) to mitigate for target impervious surface must meet all of the following criteria:
 - a) The donor area must be 3.5 times the area of impervious surface being credited as mitigated by the native vegetated surface.
 - b) The donor area must consist of native vegetated surface, which means that the area may be either existing forest or forest created in accordance with the specifications for “native vegetated landscape” in Section C.2.1.8.
 - c) The donor area must be in addition to any required set-asides for recreation prior to City annexation, critical areas (and applicable buffers) in RMC 4-3-050, or to meet the clearing standards in RMC 4-4-060.
 - d) The donor area must not slope more than 15%.
 - e) The donor area must be set aside as “native growth retention area” as specified in Section C.2.1.9.
Note this area may be used to manage dispersed stormwater from other areas within the site.
4. The area of target impervious surface credited as being mitigated by the native growth retention credit must meet all of the following requirements:
 - a) The area credited as mitigated must be no more than 10,000 square feet on any one **site** unless the surface is served by a flow control facility designed by a **civil engineer** in accordance with Section 1.2.3 of the *SWDM*.
 - b) Any runoff from the area credited as mitigated must be directed to vegetated pervious areas on the **site/lot** or discharged through a perforated pipe connection per Section C.2.11.
 - c) Any portion of the area credited as mitigated that is **pollution-generating impervious surface** must be less than 5,000 square feet on any one **site** unless the surface is served by a water quality treatment facility designed by a **civil engineer** in accordance with Section 1.2.8 of the *SWDM*.

C.2.10.2 EXAMPLE SIZING CALCULATION

Area of **target impervious surface** to be credited as mitigated: 500 square feet

Donor area of **native vegetated surface** that must be preserved: $500 \times 3.5 = 1,750$ square feet

C.2.10.3 MAINTENANCE INSTRUCTIONS

If the native growth retention credit on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on City of Renton’s *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.11 PERFORATED PIPE CONNECTION

Perforated pipe connections are intended to convey concentrated runoff from impervious surfaces (usually roof runoff) directly to a local drainage system while providing some infiltration of that runoff in the process. They are required for any pipe connection of roof downspouts to the local drainage system regardless of the extent to which on-site BMPs are required or being used onsite. Perforated pipe connections are intended to provide for some infiltration during drier periods (late spring through early fall), which may help dampen the flashiness of stream flows in developed areas and provide some groundwater recharge. During the wet winter months, however, this BMP likely provides little or no flow control benefits. Therefore, it is not credited with mitigating *target impervious surface*.

Applicable Surfaces

Subject to the minimum design requirements below, the perforated pipe connection may be applied to concentrated runoff from any impervious surface or nonnative pervious surface.

Operation and Maintenance

See Section C.2.11.2.

C.2.11.1 MINIMUM DESIGN REQUIREMENTS

Figure C.2.11.A illustrates a perforated pipe connection for a typical single family residence. Impervious areas larger than 10,000 square feet and nonnative pervious areas larger than 35,000 square feet may require larger pipe to adequately convey flows and should be designed by a *civil engineer*. Perforated pipe connections must be installed according to the following requirements:

1. Where possible, the perforated pipe connection must be **placed in native soil** to maximize infiltration of water, and must not be located under impervious surfaces, except as a last resort.
2. The **gravel filled trench** must be at least 10-feet in length for every 5,000 square feet of impervious surface or 35,000 square feet of nonnative pervious surface from which runoff is conveyed.
3. The perforated portion of the system may not be placed in a critical area **buffer** or on **slopes** steeper than 25%. Any proposed placement of the perforated portion on slopes steeper than 15% or within 50 feet of a *steep slope hazard area* or *landslide hazard* must be approved by a *geotechnical engineer* or *engineering geologist* unless otherwise approved by CED.
4. For *sites* with **septic systems**, the perforated portion of the system must be down slope of the drainfield primary and reserve areas. CED review staff can waive this requirement if *site* topography clearly prohibits subsurface flows from intersecting the drainfield.
5. The perforated pipe connection must not create **flooding or erosion impacts** as determined by CED. If the system discharges toward or is near a *landslide hazard, erosion hazard area, steep slope hazard area*, or a slope steeper than 15%, CED may require evaluation and approval of the proposal by a *geotechnical engineer* or *engineering geologist*.
6. A minimum of a 5 foot setback is required between any part of the perforated pipe trench and any property line.


C.2.11.2 MAINTENANCE INSTRUCTIONS

If the perforated pipe connection on-site BMP is required for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions.

Future updates to the instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

FIGURE C.2.11.A SCHEMATIC REPRESENTATION OF A PERFORATED PIPE CONNECTION FOR A SINGLE FAMILY RESIDENCE



C.2.12 RAIN GARDENS

Rain gardens are an on-site BMP that can provide effective removal of many stormwater pollutants, and provide reductions in stormwater runoff quantity and surface runoff flow rates. Rain gardens are non-engineered, shallow, landscaped depressions with compost amended soils and adapted plants. The depression ponds and temporarily stores stormwater runoff from adjacent areas. A portion of the influent stormwater passes through the amended soil profile and into the native soil beneath. Stormwater that exceeds the storage capacity is designed to overflow to an adjacent drainage system.

Applicable Surfaces

Rain gardens are an on-site BMP option for projects that have to comply with Core Requirement #9, but not Core Requirements #3 or #8. Rain gardens shall have a maximum contributing area of 5,000 square feet.

Infeasibility Criteria

Infeasibility criteria for rain gardens are the same as for bioretention. Refer to Bioretention infeasibility criteria in Section C.2.6.

Rain gardens constructed with imported compost materials should not be used within one-quarter mile of phosphorus-sensitive waterbodies. Preliminary monitoring indicates that new rain gardens can add phosphorus to stormwater.

C.2.12.1 MINIMUM DESIGN REQUIREMENTS

1. Refer to the *Rain Garden Handbook for Western Washington (2013)* for rain garden specifications and construction guidance.
2. For amending the native soil within the rain garden, compost is recommended that meets the compost specification for bioretention (see Section C.2.6). Compost that includes biosolids or manures shall not be used.
3. Rain gardens must have a horizontally projected surface area below the overflow which is at least 5% of the area draining to it. If lawn/landscape area will also be draining to the rain garden, it is recommended that the rain garden's horizontally projected surface area below the overflow be increased by 2% of the lawn/landscape area.
4. The City does not allow the use of underdrains for rain gardens.

C.2.12.2 MAINTENANCE INSTRUCTIONS

Please refer to the *Rain Garden Handbook for Western Washington (2013)* for tips on mulching, watering, weeding, pruning, and soil management. The "Western Washington Low Impact Development (LID) Operation and Maintenance (O&M) Guidance Document" may be consulted for more detailed guidance.

If a rain garden on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on the City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.12.3 CONSTRUCTION SEQUENCING

There are many potential applications and site scenarios where rain gardens can be applied. The following techniques highlight the most broadly applicable techniques to be used to protect rain gardens during construction. Refer to Appendix D for general site protection measures and Appendix D, Section D.2.1.10 for protection measures specific to existing and proposed on-site BMPs. In addition to those techniques, the following techniques apply specifically for protection of rain gardens during construction:

- Prior to construction:
 - The rain garden shall be clearly identified (e.g., using flagging or high visibility fencing) and protected prior to construction to prevent compaction of underlying soils by vehicle traffic.
 - The Construction SWPPP sheets must outline construction sequencing that will protect the rain garden during construction.
 - Stabilize upslope construction areas (e.g., using silt fences, berms, mulch, or other Construction SWPPP BMPs) and minimize overland flow distances.
- Excavation:
 - Excavation of rain gardens shall be performed by machinery operating adjacent to the BMP. No heavy equipment with narrow tracks, narrow tires, or large lugged high pressure tires shall be allowed on the rain garden footprint.
 - If machinery must operate in the rain garden for excavation, use lightweight, low ground-contact pressure equipment and rip the base at completion to scarify soil to a minimum of 12 inches.
 - Where feasible, excavate rain garden areas to final grade only after all disturbed areas in the up-gradient project drainage area have been permanently stabilized. (If rain gardens must be excavated before permanent site stabilization, initial excavation must be conducted to no less than 6 inches of the final elevation of the facility floor.)
 - Excavation of rain garden areas shall not be allowed during wet or saturated conditions.
 - The use of draglines and trackhoes should be considered for constructing rain gardens.
 - The sidewalls and bottom of a rain garden excavation must be raked or scarified to a minimum depth of 3 inches after final excavation to restore infiltration rates.
- Sediment control:
 - Rain gardens shall not be used as a sediment control facility, and all drainage shall be directed away from the rain garden after initial rough grading.
 - Direct construction site flow away from the rain garden using applicable Construction SWPPP BMPs (e.g., temporary diversion swales).
- Protect rain gardens from compaction during construction
 - Check for compaction prior to planting. If compaction occurs, aerate the rain garden soil and then proceed to plant.

C.2.12.4 EXAMPLE SIZING CALCULATION

Runoff Source: 20-foot by 20-foot driveway

Rain Garden Surface Area (below the overflow): $0.05 \times (20 \text{ feet} \times 20 \text{ feet}) = 20 \text{ square feet}$

C.2.13 SOIL AMENDMENT

Naturally occurring (undisturbed) soil and vegetation provide important stormwater functions including: water infiltration; nutrient, sediment, and pollutant adsorption; sediment and pollutant biofiltration; water interflow storage and transmission; and pollutant decomposition.

These functions are largely lost when development strips away native soil and vegetation and replaces it with minimal topsoil and sod. Not only are these important stormwater functions lost, but such landscapes themselves become pollution generating pervious surfaces due to increased use of pesticides, fertilizers and other landscaping and household/industrial chemicals, the concentration of pet wastes, and pollutants that accompany roadside litter.

Establishing soil quality and depth regains greater stormwater functions in the post development landscape, provides increased treatment of pollutants and sediments that result from development and habitation, and minimizes the need for some landscaping chemicals, thus reducing pollution through prevention.

Applicable Surfaces

Establishing a minimum soil quality and depth through soil amendment is not the same as preservation of naturally occurring soil and vegetation. However, establishing a minimum soil quality and depth will provide improved on-site management of stormwater flow and water quality.

Soil organic matter can be attained through numerous materials such as compost, composted woody material, biosolids, and forest product residuals. It is important that the materials used to meet the soil quality and depth BMP be appropriate and beneficial to the plant cover to be established. Likewise, it is important that imported topsoils improve soil conditions and do not have an excessive percent of clay fines.

Infeasibility Criteria

Soil amendment can be considered infeasible on till soil slopes greater than 33 percent.

C.2.13.1 MINIMUM DESIGN REQUIREMENTS

- Soil retention. Retain, in an undisturbed state, the duff layer and native topsoil to the maximum extent practicable. In any areas requiring grading remove and stockpile the duff layer and topsoil on site in a designated, controlled area, not adjacent to public resources and critical areas, to be reapplied to other portions of the site where feasible.
- Soil quality. All areas subject to clearing and grading that have not been covered by impervious surface, incorporated into a drainage facility or engineered as structural fill or slope shall, at project completion, demonstrate the following:
 1. A topsoil layer with a minimum organic matter content of 10% dry weight in beds, and 5% organic matter content in turf areas, and a pH from 6.0 to 8.0 or matching the pH of the undisturbed soil. The topsoil layer shall have a minimum depth of eight inches except where tree roots limit the depth of incorporation of amendments needed to meet the criteria. Subsoils below the topsoil layer should be scarified at least 4 inches with some incorporation of the upper material to avoid stratified layers, where feasible.
 2. Mulch planting beds with 2 inches of organic material
 3. Use compost and other materials that meet these organic content requirements:
 - a) The organic content for “pre-approved” amendment rates can be met only using compost meeting the compost specification for Bioretention (Refer to Section C.2.6) with the exception that the compost may have up to 35% biosolids or manure. The compost must also have an organic matter content of 40% to 65%, and a carbon to nitrogen ratio below 25:1. The

carbon to nitrogen ratio may be as high as 35:1 for plantings composed entirely of plants native to the Puget Sound Lowlands region.

- b) Calculated amendment rates may be met through use of composted material meeting “a)” above; or other organic materials amended to meet the carbon to nitrogen ratio requirements, and not exceeding the limits identified in Table 220-B, Testing Parameters, in WAC 173-350-220.
4. The resulting soil should be conducive to the type of vegetation to be established.
- Implementation Options: The soil quality design guidelines listed above can be met by using one of the methods listed below:
 1. Leave undisturbed native vegetation and soil, and protect from compaction during construction.
 2. Amend existing site topsoil or subsoil either at default “pre-approved” rates, or at custom calculated rates based on tests of the soil and amendment.
 3. Stockpile existing topsoil during grading, and replace it prior to planting.
 4. Stockpiled topsoil must also be amended if needed to meet the organic matter or depth requirements, either at a default “pre-approved” rate or at a custom calculated rate.
 5. Import topsoil mix of sufficient organic content and depth to meet the requirements.

More than one method may be used on different portions of the same site. Soil that already meets the depth and organic matter quality standards, and is not compacted does not need to be amended.

Runoff Model Representation

- Areas meeting the design guidelines shall be entered into approved runoff models as “Pasture” rather than “Lawn.”
- Flow reduction credits shall be taken in runoff modeling when Soil Amendment BMP is used as part of a dispersion design under the conditions described in:
 - Full Dispersion (for public road projects)
 - Limited Infiltration
 - Basic Dispersion

C.2.13.2 PLANNING AND PERMITTING

A site specific Soil Management Plan (SMP) must be approved as part of the clearing and grading or construction permit application.

The Soil Management Plan (SMP) includes:

- A scale-drawing (11" X 17" or larger) identifying area where native soil and vegetation will be retained undisturbed, and which soil treatments will applied in landscape areas.
- A completed SMP form identifying treatments and products to be used to meet the soil depth and organic content requirements for each area.
- Computations of compost or topsoil volumes to be imported (and/or site soil to be stockpiled) to meet “pre-approved” amendment rates; or calculations by a qualified professional to meet organic content requirements if using custom calculated rates. Qualified professionals include certified Agronomists, Soil Scientists or Crop Advisors; and licensed Landscape Architects, Civil Engineers or Geologists.
- Copies of laboratory analyses for compost and topsoil products to be used, documenting organic matter contents and carbon to nitrogen ratios.

C.2.13.3 INSPECTION/VERIFICATION PROCEDURES

Inspection and verification should be performed by appropriate jurisdiction inspectors. Some verification may be made by supervising Landscape Architects or Civil Engineers, who submit signed certification that the approved SMP had been implemented.

The following is an outline of a preferred inspection schedule and tasks:

Depending on local resources and procedures, the inspection tasks may be consolidated into fewer visits.

1. Pre-Grading Inspection

- Verify delineation and fencing off of native soils and vegetation to be left undisturbed, per the SMP.
- Review the SMP with the general contractor to ensure that topsoil stockpiling and other specified measures are incorporated into the work plan.

2. Grading Progress Inspection

- Verify that proper erosion control methods are being implemented.
- Verify that excavation and stockpiling of native soils follows the SMP.
- Verify that subgrades are consistent with the SMP.

3. Post-Construction Inspection

Preferably prior to planting, so that omissions can easily be corrected:

- Verify that compost, mulch, topsoil and amendment delivery tickets match volumes, types and sources approved in the SMP. If materials other than those approved in the SMP were delivered, submissions by the supplier should verify that they are equivalent to approved products.
- Check soil for compaction, scarification and amendment incorporation by digging at least one 12-inch deep test hole per acre for turf and at least one per acre for planting beds. Test holes must be excavated using only a garden spade driven solely by inspector's weight.
- Test 10 locations per landscaped acre (10 locations minimum) for compaction, using a simple "rod penetrometer" (a 4 foot long 3/8th inch diameter stainless steel rod, with and a 30 degree bevel cut into the side at that goes in 1/8 inch at the tip). Rod must penetrate to 12" depth driven solely by inspector's weight.
- Verify placement of two inches of organic mulch material on all planting beds.

Secondary Verification For Failing Sites:

If inspector believes the installation does not meet the approved permit conditions, additional testing may be ordered to determine whether remediation steps are required prior to final occupancy and payment. An independent consultant (Certified Soil Scientist, Crop Advisor or Agronomist; or Licensed Landscape Architect, Civil Engineer or Geologist) should conduct the following additional sampling and analysis:

- Organic matter content should be verified by an independent soil testing service, using the Loss On Ignition method.
- If necessary, the percentage of fine particles (less than #200 mesh) should be confirmed by a certified Soil Laboratory using a wet sieve test.
- At present, an analytical method for verifying scarification has not been identified. Verification may be a matter of professional opinion.

C.2.13.4 MAINTENANCE INSTRUCTIONS

If the soil amendment on-site BMP is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners,

the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.14 TREE RETENTION CREDIT

Trees provide flow control benefits via interception, transpiration, and increased infiltration. Additional environmental benefits include improved air quality, carbon sequestration, reduced heat island effect, pollutant removal, and habitat preservation or formation. When implemented in accordance with the criteria outlined below, retained trees can receive credits toward meeting on-site BMP requirements. The degree of flow control benefits provided by a tree depends on the tree type (i.e., evergreen or deciduous), canopy area, and whether or not the tree canopy overhangs impervious surfaces.

C.2.14.1 MINIMUM DESIGN REQUIREMENTS

1. Setbacks of proposed infrastructure from existing trees are critical considerations. Tree protection requirements limit grading and other disturbances in proximity to the tree. Existing tree species and location must be clearly shown on submittal drawings. Trees must be viable for long-term retention (i.e., in good health and compatible with proposed construction).
2. Tree size: To receive the tree retention credit, retained trees shall have a minimum 6 inches diameter at breast height (DBH). DBH is defined as the outside bark diameter at 4.5 feet above the ground on the uphill side of a tree.
3. The retained tree canopy area shall be measured as the area within the tree drip line. A drip line is the line encircling the base of a tree, which is delineated by a vertical line extending from the outer limit of a tree's branch tips down to the ground. If trees are clustered, overlapping canopies are not double counted.
4. Tree location: Tree retention credit depends upon proximity to ground level impervious or other hard surfaces. To receive a tree retention credit, the existing tree must be on the development site and within 20 feet of new and/or replaced ground level impervious surfaces (e.g., driveway or patio) on the development site. Distance from impervious surfaces is measured from the tree trunk center.
5. An arborist report may be required if impervious surface is proposed within the critical root zone of the existing tree. The critical root zone is defined as the line encircling the base of the tree with half the diameter of the dripline. If the arborist report concludes that impervious surface should not be placed within 20 feet of the tree and canopy overlap with impervious surface is still anticipated given a longer setback, the higher tree flow control credit may be approved.
6. Protection during construction: The existing tree roots, trunk, and canopy shall be fenced and protected during construction activities.
7. Retention and protection: Trees shall be retained, maintained and protected on the site after construction and for the life of the development or until any approved redevelopment occurs in the future. Trees that are removed or die shall be replaced with like species during the next planting season (typically in fall). Trees shall be pruned according to industry standards (ANSI A 300 standards).

C.2.14.2 EXAMPLE SIZING CALCULATION

Flow control credits for retained trees are provided in Table C.2.14.A by tree type. These credits can be applied to reduce impervious area requiring on-site BMPs. Credits are given as a percentage of the existing tree canopy area. The minimum credit for existing trees ranges from 50 to 100 square feet.

TABLE C.2.14.A TREE RETENTION CREDIT	
Tree Type	Credit
Evergreen	20% of canopy area (minimum of 100 sq.ft./tree)
Deciduous	10% of canopy area (minimum of 50 sq. ft./tree)

Impervious/Hard Surface Area Mitigated =

$$(\Sigma \text{ Evergreen Canopy Area} \times 0.2) + (\Sigma \text{ Deciduous Canopy Area} \times 0.1)$$

Tree credits are not applicable to trees in native vegetation areas used for flow dispersion or other impervious surface credits. Credits are also not applicable to trees in planters. The total tree retention credit shall not exceed 25 percent of impervious surface requiring mitigation.

C.2.14.3 MAINTENANCE INSTRUCTIONS

If tree retention is proposed for a project, maintenance and operation instructions must be recorded as an attachment to the required declaration of covenant and grant of easement per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions. Future updates to the instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

C.2.15 VEGETATED ROOFS

Vegetated roofs (also called green roofs) consist of pervious growing medium, plants and a moisture barrier. There are **currently several different proprietary systems available** that use different media types and thickness. Figure C.2.15.A and Figure C.2.15.B show a schematic representation of a typical vegetated roof and a vegetated roof tray system. Actual design specifications should be provided by the manufacturer and/or installer. The benefits of this BMP are reduced runoff peaks and volumes resulting from the increased water storage provided by the soil and the increased evapotranspiration provided by the vegetation.

Applicable Surfaces

Subject to the minimum design requirements and specifications in this section, vegetated roof systems may be applied to any roof area.

Design Considerations

The roof must be designed to carry the added load of a vegetated roof system; therefore design by a structural engineer may be needed.

Operation and Maintenance

See Section C.2.15.3.

C.2.15.1 MINIMUM DESIGN REQUIREMENTS

All of the following requirements must be met in order for a vegetated roof to be applicable to a **target impervious surface**.

1. A 60- to 80-mil reinforced PVC **membrane** must be placed on the roof surface to provide waterproofing and protect against root penetration, or if the roof is asphalt-based, the membrane must be high-density polyethylene (HDPE).
2. If the roof surface is flat or has a pitch flatter than 1 in 12, an **underdrain system** or layer must be provided to drain excess water away from the root zone of the soil layer.
3. The growing **medium** must have the capacity to store a minimum depth of 3 inches of water for full BMP credit, partial credit will be given for reduced storage.
4. The **soil layer** must be adequately contained on the roof with sidewalks or other appropriate means.
5. The **composition** of the soil layer must be confirmed by a **civil engineer** as meeting the desired soil storage and the maximum allowable loading specified by the structural engineer.
6. Grass or other **vegetative cover** suitable for shallow soils and harsh roof conditions (e.g., various species of *sedum*, *semperivum*, *creeping thyme*, *allium*, *phloxes*, *annternaria*, *armeria*, and *aubrieta*) shall be used.
7. Vegetated roofs must not be subject to any use that would significantly **compact** the soil.
8. Provision must be made for **supplemental irrigation** during the first dry season to ensure plant survival, replacing dead plants, and removal of weeds and leaves, clearing drain inlets.

C.2.15.2 EXAMPLE SIZING CALCULATION

Target impervious surface area: 1,000 square feet.

Proposed vegetated roof system provides 1.5 inches storage.

Required vegetated roof area = $(1000 \times 3)/1.5 = 2,000$ square feet.

FIGURE C.2.15. SCHEMATIC REPRESENTATION OF A TYPICAL VEGETATED ROOF





FIGURE C.2.15.B SCHEMATIC REPRESENTATION OF A VEGETATED ROOF TRAY SYSTEM



C.2.15.3 MAINTENANCE INSTRUCTIONS FOR VEGETATED ROOFS

If the vegetated roof on-site BMP is proposed for a project, maintenance and operation instructions, plus any provided by the manufacturer or installer, must be recorded as an attachment to the required declaration of covenant and grant of easement per Requirement 3 of Section C.1.3.4. The intent of these instructions is to explain to future property owners, the purpose of the BMP and how it must be maintained and operated. These instructions are intended to be a minimum; CED may require additional instructions based on site-specific conditions or manufacturer's recommendations. Future updates to the instructions will be posted on City of Renton's *Surface Water Design Manual* website.

A reproducible copy of the instructions, prepared for inclusion with the declaration of covenant, is located in Reference Section 8-M.

(This page intentionally left blank.)

C.3 CONSTRUCTION STORMWATER POLLUTION PREVENTION (CSWPP) MEASURES

This section presents the specifications for the kinds of the ESC and SWPPS measures applicable to **Simplified project sites** as allowed by the City's *Construction Stormwater Pollution Prevention (CSWPP) Standards* (Detached Appendix D of the *City of Renton Surface Water Design Manual*). For projects in Simplified Drainage Review, these ESC measures may be used if no more than 1 acre of soil will be disturbed by the project. Other ESC measures may be allowed or required by CED if these are inappropriate for the project or fail to contain sediment on the *project site*. A description of other measures and a more detailed description of those included here can be found in the *CSWPP Standards*. Projects that **disturb 1 acre or more** of soil will require an ESC plan developed by a *civil engineer* under a Targeted Drainage Review.

CSWPP: Intent of ESC and SWPPS Measures

The intent of ESC measures is to prevent, to the maximum extent practicable, the transport of sediment and other construction-related pollutants to streams, wetlands, lakes, drainage systems, and adjacent properties during and after construction. Erosion of disturbed areas on construction sites can result in excessive sediment transport to adjacent properties and to surface waters. This sediment can result in major adverse impacts, such as flooding due to obstructed drainage ways, smothering of salmonid spawning beds, creation of algal blooms in lakes, and violation of State water quality standards for turbidity. In addition to sediment, SWPPS measures address other construction-related pollutants that can be generated by uncovered waste materials, stockpiles, and demolition debris; de-watering; maintenance and operation of heavy equipment; chemical spills; oil spills; placement of concrete; and application of fertilizers and pesticides. Such pollutants can be toxic to both fish and humans and may violate State water quality standards and the prohibited discharges section of RMC 4-6-030. Stabilization of the *site* after construction and prior to the wet season is also important to preventing these impacts.

Organization of Section C.3

This section is organized as follows:

- “Stabilized Construction Entrance,” Section C.3.1
- “Mulching,” Section C.3.2
- “Nets and Blankets,” Section C.3.3
- “Plastic Covering,” Section C.3.4
- “Mark Clearing Limits/Minimize Clearing,” Section C.3.5
- “Silt Fence,” Section C.3.6
- “Vegetated Strip,” Section C.3.7
- “Triangular Silt Dike,” Section C.3.8
- “Storm Drain Inlet Protection,” Section C.3.9
- “Seeding,” Section C.3.10
- “Sodding,” Section C.3.11
- “Interceptor Dikes and Swales,” Section C.3.12
- “Ditches,” Section C.3.13
- “Pipe Slope Drain,” Section C.3.14
- “Dewatering Control,” Section C.3.15
- “Control of Other Pollutants (SWPPS),” Section C.3.16

The above measures must be implemented as needed to prevent the discharge of sediment-laden water and other pollutants from the construction site. Proposed measures must be shown on the **Small Site CSWPP**

plan required to be submitted with the Simplified Drainage Plans. Site-specific conditions during construction may require additional measures as deemed necessary by CED. As noted in Section C.3 above, other ESC and/or SWPPS measures found in Appendix D of the *SWDM* may be needed or may be more appropriate for the *project site* as determined by CED.

C.3.1 STABILIZED CONSTRUCTION ENTRANCE

Purpose

Construction entrances are stabilized to reduce the amount of sediment transported onto paved roads by motor vehicles or runoff by constructing a stabilized pad of quarry spalls at the entrances to construction sites.

Application

Construction entrances shall be stabilized wherever traffic will be leaving a construction site and traveling on paved roads or other paved areas within 1,000 feet of the *site*. Access and exits shall be limited to one route if possible, or two for linear projects such as roadway where more than one access/exit is necessary for maneuvering large equipment.

For residential construction provide stabilized construction entrances for each residence in addition to the main subdivision entrance. Stabilized surfaces shall be of sufficient length/width to provide vehicle access/parking, based on lot size/configuration.

Design and Installation Specifications

1. See schematic representation in Figure C.3.1.A.
2. A separation geotextile shall be placed under the spalls to prevent fine sediment from pumping up into the rock pad. The geotextile shall meet the following standards:


Grab Tensile Strength (ASTM D4632)	200 lbs min.
Grab Tensile Elongation (ASTM D4632)	30% max.(woven)
Puncture Strength (ASTM D6241)	495 lbs min.
AOS (ASTM D4751)	20–45 (U.S. standard sieve size)

3. Do not use crushed concrete, cement, or calcium chloride for construction entrance stabilization because these products raise pH levels in stormwater and concrete discharge to surface waters of the State is prohibited.
4. Hog fuel (wood based mulch) may be substituted for or combined with quarry spalls in areas that will not be used for permanent roads. The effectiveness of hog fuel is highly variable, but it has been used successfully on many construction sites. It generally requires more maintenance than quarry spalls. Hog fuel is not recommended for entrance stabilization in urban areas. The inspector may at any time require the use of quarry spalls if the hog fuel is not preventing sediment from being tracked onto pavement or if the hog fuel is being carried onto pavement. Hog fuel is prohibited in permanent roadbeds because organics in the subgrade soils cause difficulties with compaction.
5. Fencing shall be installed as necessary to restrict traffic to the construction entrance.
6. Whenever possible, the entrance shall be constructed on a firm, compacted subgrade. This can substantially increase the effectiveness of the pad and reduce the need for maintenance.

Maintenance

1. Quarry spalls (or hog fuel) shall be added if the pad is no longer in accordance with the specifications.

2. If the entrance is not preventing sediment from being tracked onto pavement, then alternative measures to keep the streets free of sediment shall be used. This may include street sweeping, an increase in the dimensions of the entrance, or the installation of a wheel wash. If washing is used, it shall be done on an area covered with crushed rock, and wash water shall drain to a sediment trap or pond.
3. Any sediment that is tracked onto pavement shall be removed immediately by sweeping. The sediment collected by sweeping shall be removed or stabilized onsite. The pavement shall not be cleaned by washing down the street, except when sweeping is ineffective and there is a threat to public safety. If it is necessary to wash the streets, a small sump must be constructed. The sediment would then be washed into the sump where it can be controlled. Wash water must be pumped back onto the *site* and cannot discharge to systems tributary to surface waters.
4. Any quarry spalls that are loosened from the pad and end up on the roadway shall be removed immediately.
5. If vehicles are entering or exiting the site at points other than the construction entrance(s), fencing shall be installed to control traffic.

FIGURE C.3.1.A SCHEMATIC REPRESENTATION OF A STABILIZED CONSTRUCTION ENTRANCE**NOTES:**

- PER KING COUNTY ROAD DESIGN AND CONSTRUCTION STANDARDS (KCRDCS), DRIVEWAYS SHALL BE PAVED TO EDGE OF R-O-W PRIOR TO INSTALLATION OF THE CONSTRUCTION ENTRANCE TO AVOID DAMAGING OF THE ROADWAY.
- IT IS RECOMMENDED THAT THE ENTRANCE BE CROWNED SO THAT RUNOFF DRAINS OFF THE PAD.

C.3.2 MULCHING

Purpose

The purpose of mulching soils is to provide immediate temporary protection from erosion. Mulch also enhances plant establishment by conserving moisture, holding fertilizer, seed, and topsoil in place, and moderating soil temperatures. There is an enormous variety of mulches that may be used. Only the most common types are discussed in this section.

Conditions of Use

As a temporary cover measure, mulch should be used:

1. On disturbed areas that require cover measures for less than 30 days
2. As a cover for seed during the wet season and during the hot summer months
3. During the wet season on slopes steeper than 3H:1V with more than 10 feet of vertical relief.

Design and Installation Specifications

For mulch materials, application rates, and specifications, see Table C.3.2.A.

Note: Thicknesses may be increased for disturbed areas in or near critical areas or other areas highly susceptible to erosion.

Maintenance Standards

1. The thickness of the mulch cover must be maintained.
2. Any areas that experience erosion shall be re-mulched and/or protected with a net or blanket. If the erosion problem is drainage related, then the drainage problem shall be assessed and alternate drainage such as interceptor swales may be needed to fix the problem and the eroded area re-mulched.

TABLE C.3.2.A MULCH STANDARDS AND GUIDELINES

Mulch Material	Quality Standards	Application Rates	Remarks
Straw	Air-dried; free from undesirable seed and coarse material	2"–3" thick; 2–3 bales per 1000 sf or 2–3 tons per acre	Cost-effective protection when applied with adequate thickness. Hand-application generally requires greater thickness than blown straw. Straw should be crimped to avoid wind blow. The thickness of straw may be reduced by half when used in conjunction with seeding.
Wood Fiber Cellulose	No growth inhibiting factors	Approx. 25–30 lbs per 1,000 sf or 1,000–1,500 lbs per acre	Shall be applied with hydromulcher. Shall not be used without seed and tackifier unless the application rate is at least doubled. Some wood fiber with very long fibers can be effective at lower application rates and without seed or tackifier.
Compost	No visible water or dust during handling. Must be purchased from supplier with Solid Waste Handling Permit.	2" thick min.; approx. 100 tons per acre (approx. 800 lbs per cubic yard)	More effective control can be obtained by increasing thickness to 3". Excellent mulch for protecting final grades until landscaping because it can be directly seeded or tilled into soil as an amendment. Sources for compost are available from the King County Commission for Marketing Recyclable Materials at 206-296-4439.
Hydraulic Matrices (Bonded Fiber Matrix [BFM])	This mulch category includes hydraulic slurries composed of wood fiber, paper fiber or a combination of the two held together by a binding system. The BFM shall be a mixture of long wood fibers and various bonding agents.	Apply at rates from 3,000 lbs per acre to 4,000 lbs per acre and based on manufacturers recommendations	The BFM shall not be applied immediately before, during or immediately after rainfall so that the matrix will have an opportunity to dry for 24 hours after installation. Application rates beyond 2,500 pounds may interfere with germination and are not usually recommended for turf establishment. BFM is generally a matrix where all fiber and binders are in one bag, rather than having to mix components from various manufacturers to create a matrix. BFMs can be installed via helicopter in remote areas. They are approximately \$1,000 per acre cheaper to install.
Chipped Site Vegetation	Average size shall be several inches.	2" minimum thickness	This is a cost-effective way to dispose of debris from clearing and grubbing, and it eliminates the problems associated with burning. Generally, it should not be used on slopes above approx. 10% because of its tendency to be transported by runoff. It is not recommended within 200 feet of surface waters. If seeding is expected shortly after mulch, the decomposition of the chipped vegetation may tie up nutrients important to grass establishment.

C.3.3 NETS AND BLANKETS

Purpose

Erosion control nets and blankets are intended to prevent erosion and hold seed and mulch in place on steep slopes and in channels so that vegetation can become well established. In addition, some nets and blankets can be used to permanently reinforce turf to protect drainage ways during high flows. Nets are strands of material woven into an open, but high-tensile strength net (for example, jute matting). Blankets are strands of material that are not tightly woven, but instead form a layer of interlocking fibers, typically held together by a biodegradable or photodegradable netting (for example, excelsior or straw blankets). They generally have lower tensile strength than nets, but cover the ground more completely. Coir (coconut fiber) fabric comes as both nets and blankets.

Conditions of Use

Erosion control nets and blankets should be used:

1. For permanent stabilization of slopes 2H:1V or greater and with more than 10 feet of vertical relief.
2. In conjunction with seed for final stabilization of a slope, not for temporary cover. However, they may be used for temporary applications as long as the product is not damaged by repeated handling. In fact, this method of slope protection is superior to plastic sheeting, which generates high-velocity runoff.
3. For drainage ditches and swales (highly recommended). The application of appropriate netting or blanket to drainage ditches and swales can protect bare soil from channelized runoff while vegetation is established. Nets and blankets also can capture a great deal of sediment due to their open, porous structure. Synthetic nets and blankets may be used to permanently stabilize channels and may provide a cost-effective, environmentally preferable alternative to riprap.

Design and Installation Specifications

1. See Figure C.3.3.A and Figure C.3.3.B for typical orientation and installation of nettings and blankets.

Note: Installation is critical to the effectiveness of these products. If good ground contact is not achieved, runoff can concentrate under the product, resulting in significant erosion.

2. With the variety of products available, it is impossible to cover all the details of appropriate use and installation. Therefore, it is critical that the design engineer thoroughly consults the **manufacturer's information** and that a site visit takes place in order to ensure that the product specified is appropriate.
3. Jute matting must be used in conjunction with mulch. Excelsior, woven straw blankets, and coir (coconut fiber) blankets may be installed without mulch. There are many other types of **erosion control nets and blankets** on the market that may be appropriate in certain circumstances. Other types of products will have to be evaluated individually. In general, most nets (e.g., jute matting) require mulch in order to prevent erosion because they have a fairly open structure. Blankets typically do not require mulch because they usually provide complete protection of the surface.
4. Purely synthetic blankets are allowed but shall only be used for long-term stabilization of waterways. The organic blankets authorized above are better for slope protection and short-term waterway protection because they retain moisture and provide organic matter to the soil, substantially improving the speed and success of re-vegetation.

Maintenance Standards

1. Good contact with the ground must be maintained, and there must not be erosion beneath the net or blanket.

2. Any areas of the net or blanket that are damaged or not in close contact with the ground shall be repaired and stapled.
3. If erosion occurs due to poorly controlled drainage, the problem shall be fixed and the eroded area protected.

FIGURE C.3.3.A WATERWAY INSTALLATION

- DO NOT STRETCH BLANKETS/MATTINGS TIGHT - ALLOW THE ROLLS TO MOLD TO ANY IRREGULARITIES.
- SLOPE SURFACE SHALL BE SMOOTH BEFORE PLACEMENT FOR PROPER SOIL CONTACT.
- ANCHOR, STAPLE, AND INSTALL CHECK SLOTS AS PER MANUFACTURER'S RECOMMENDATIONS.
- AVOID JOINING MATERIAL IN THE CENTER OF THE DITCH.
- LIME, FERTILIZE AND SEED BEFORE INSTALLATION.





FIGURE C.3.3.B SLOPE INSTALLATION



C.3.4 PLASTIC COVERING

Purpose

Plastic covering provides immediate, short-term erosion protection to slopes and disturbed areas.

Conditions of Use


1. Plastic covering may be used on disturbed areas that require cover measures for less than 30 days.
2. Plastic is particularly useful for protecting cut and fill slopes and stockpiles. *Note: The relatively rapid breakdown of most polyethylene sheeting makes it unsuitable for long-term applications.*
3. Clear plastic sheeting may be used over newly-seeded areas to create a greenhouse effect and encourage grass growth. Clear plastic should not be used for this purpose during the summer months because the resulting high temperatures can kill the grass.
4. Due to rapid runoff caused by plastic sheeting, this method shall not be used upslope of areas that might be adversely impacted by concentrated runoff. Such areas include steep and/or unstable slopes.

Note: There have been many problems with plastic, usually attributable to poor installation and maintenance. However, the material itself can cause problems, even when correctly installed and maintained, because it generates high-velocity runoff and breaks down quickly due to ultraviolet radiation. In addition, if the plastic is not completely removed, it can clog drainage system inlets and outlets. It is highly recommended that alternatives to plastic sheeting be used whenever possible and that its use be limited.

Design and Installation Specifications

1. See Figure C.3.4.A for details.
2. Plastic sheeting shall have a minimum thickness of 0.06 millimeters.
3. If erosion at the toe of a slope is likely, a gravel berm, riprap, or other suitable protection shall be installed at the toe of the slope in order to reduce the velocity of runoff.

FIGURE C.3.4.A PLASTIC COVERING



Maintenance Standards for Plastic Covering

1. Torn sheets must be replaced and open seams repaired.
2. If the plastic begins to deteriorate due to ultraviolet radiation, it must be completely removed and replaced.
3. When the plastic is no longer needed, it shall be completely removed.

C.3.5 MARK CLEARING LIMITS/MINIMIZE CLEARING

Purpose

Minimizing clearing is the most effective method of erosion control. Undisturbed vegetation intercepts and slows rainwater. Plant roots hold soil in place, and dead vegetation on the ground acts as a mulch. Marking clearing limits around existing or proposed on-site BMP areas helps protect their infiltrative soil characteristics from construction activity.

Applications

Clearing limits shall be marked and clearing minimized on any *site* where significant areas of undisturbed vegetation will be retained or where existing or proposed BMP/facility areas require protection from construction activities.

Design Specifications

1. Minimizing clearing should be incorporated into the *site* design. Clearing limits must be marked on the **Small Site CSWPP plan**.
2. On the ground, clearing limits must be clearly marked with brightly colored tape or plastic or metal safety fencing. If tape is used, it should be supported by vegetation or stakes, and should be about 3 to 6 feet high and highly visible. BMP/facility areas to be protected should be marked with brightly colored silt fence to add sedimentation protection. Equipment operators should be informed of areas of vegetation that are to be left undisturbed and BMP/facility areas that are to be protected.
3. The duff layer, native top soil, and natural vegetation shall be retained in an undisturbed state to the maximum extent practicable. If it is not practicable to retain the duff layer in place, it should be stockpiled on-site, covered to prevent erosion, and replaced immediately upon completion of the ground disturbing activities.

Maintenance

Fencing shall be inspected regularly and repaired or replaced as needed.

C.3.6 SILT FENCE

Purpose

Use of a silt fence reduces the transport of coarse sediment from a construction site by providing a temporary physical barrier to sediment and reducing the runoff velocities of overland flow.

Conditions of Use

1. Silt fence may be used downslope of all disturbed areas.
2. Silt fence is not intended to treat concentrated flows, nor is it intended to treat substantial amounts of overland flow. Any concentrated flows must be conveyed through the drainage system to a sediment trap or pond.

Design and Installation Specifications

1. See Figure C.3.6.A and Figure C.3.6.B for details.
2. The geotextile used must meet the standards listed below. A copy of the manufacturer's fabric specifications must be available onsite.

AOS (ASTM D4751)	30–100 sieve size (0.60–0.15 mm) for slit film 50–100 sieve size (0.30–0.15 mm) for other fabrics
Water Permittivity (ASTM D4491)	0.02 sec ⁻¹ minimum
Grab Tensile Strength (ASTM D4632) (see Specification Note 3)	180 lbs. min. for extra strength fabric 100 lbs. min. for standard strength fabric
Grab Tensile Elongation (ASTM D4632)	30% max. (woven)
Ultraviolet Resistance (ASTM D4355)	70% min.

3. Standard strength fabric requires wire backing to increase the strength of the fence. Wire backing or closer post spacing may be required for extra strength fabric if field performance warrants a stronger fence.
4. Where the fence is installed, the slope shall be no steeper than 2H:1V.
5. If a typical silt fence (per Figure C.3.6.A) is used, the standard 4 x 4 trench may not be reduced as long as the bottom 8 inches of the silt fence is well buried and secured in a trench that stabilizes the fence and does not allow water to bypass or undermine the silt fence.

Maintenance Standards

1. Any damage shall be repaired immediately.
2. If concentrated flows are evident uphill of the fence, they must be intercepted and conveyed to a sediment trap or pond.
3. It is important to check the uphill side of the fence for signs of the fence clogging and acting as a barrier to flow and then causing channelization of flows parallel to the fence. If this occurs, replace the fence or remove the trapped sediment.
4. Sediment must be removed when the sediment is 6 inches high.
5. If the filter fabric (geotextile) has deteriorated due to ultraviolet breakdown, it shall be replaced.

FIGURE C.3.6.A SILT FENCE





FIGURE C.3.6.B SILT FENCE INSTALLATION AND MAINTENANCE



C.3.7 VEGETATED STRIP

Purpose

Vegetated strips reduce the transport of coarse sediment from a construction site by providing a temporary physical barrier to sediment and reducing the runoff velocities of overland flow.

Conditions of Use

1. Vegetated strips may be used downslope of all disturbed areas.
2. Vegetated strips are not intended to treat concentrated flows, nor are they intended to treat substantial amounts of overland flow. Any concentrated flows must be conveyed through the drainage system to a sediment trap or pond.

Design and Installation Specifications

1. The vegetated strip shall consist of a 25-foot minimum width continuous strip of dense vegetation with a permeable topsoil. Grass-covered, landscaped areas are generally not adequate because the volume of sediment overwhelms the grass. Ideally, vegetated strips shall consist of undisturbed native growth with a well-developed soil that allows for infiltration of runoff.
2. The slope within the strip shall not exceed 4H:1V.
3. The uphill boundary of the vegetated strip shall be delineated with clearing limits as specified in Section C.3.5.

Maintenance Standards

1. Any areas damaged by erosion or construction activity shall be seeded immediately and protected by mulch.
2. If more than 5 feet of the original vegetated strip width has had vegetation removed or is being eroded, sod must be installed.

If there are indications that concentrated flows are traveling across the buffer, surface water controls must be installed to reduce the flows entering the buffer, or additional perimeter protection must be installed.

C.3.8 TRIANGULAR SILT DIKE

Purpose

Triangular silt dikes (TSDs) may be used as check dams, for perimeter protection, for temporary soil stockpile protection, for drop inlet protection, or as a temporary interceptor dike. Silt dikes, if attached to impervious surfaces with tack or other adhesive agent may also be used as temporary wheel wash areas, or concrete washout collection areas.

Conditions of Use

1. May be used for temporary check dams in ditches.
2. May be used on soil or pavement with adhesive or staples.
3. TSDs have been used to build temporary sediment ponds, diversion ditches, concrete washout facilities, curbing, water bars, level spreaders, and berms.

Design and Installation Specifications

1. TSDs must be made of urethane foam sewn into a woven geosynthetic fabric.
2. TSDs are triangular, 10 inches to 14 inches high in the center, with a 20-inch to 28-inch base. A 2-foot apron extends beyond both sides of the triangle along its standard section of 7 feet. A sleeve at one end allows attachment of additional sections as needed
3. Install TSDs with ends curved up to prevent water from flowing around the ends
4. Attach the TSDs and their fabric flaps to the ground with wire staples. Wire staples must be No. 11 gauge wire or stronger and shall be 200 mm to 300 mm in length.
5. When multiple units are installed, the sleeve of fabric at the end of the unit shall overlap the abutting unit and be stapled.
6. TSDs must be located and installed as soon as construction will allow.
7. TSDs must be placed perpendicular to the flow of water.
8. When used as check dams, the leading edge must be secured with rocks, sandbags, or a small key slot and staples.
9. When used in grass-lined ditches and swales, the TSD check dams and accumulated sediment shall be removed when the grass has matured sufficiently to protect the ditch or swale unless the slope of the swale is greater than 4 percent. The area beneath the TSD check dams shall be seeded and mulched immediately after dam removal.

Maintenance Standards

1. Triangular silt dikes shall be monitored for performance and sediment accumulation during and after each runoff producing rainfall event. Sediment shall be removed when it reaches one half the height of the silt dike.
2. Anticipate submergence and deposition above the triangular silt dike and erosion from high flows around the edges of the dike/dam. Immediately repair any damage or any undercutting of the dike/dam.

C.3.9 STORM DRAIN INLET PROTECTION

Purpose

Storm drain inlets are protected to prevent coarse sediment from entering storm drainage systems. Temporary devices around storm drains assist in improving the quality of water discharged to inlets or catch basins by ponding sediment-laden water. These devices are effective only for relatively small drainage areas.

Conditions of Use

1. Protection shall be provided for all storm drain inlets downslope and within 500 feet of a disturbed or construction area, unless the runoff that enters the catch basin will be conveyed to a sediment pond or trap.
2. Inlet protection may be used anywhere at the applicant's discretion to protect the drainage system. This will, however, require more maintenance, and it is highly likely that the drainage system will still require some cleaning.
3. The contributing drainage area must not be larger than one acre.

Design and Installation Specifications

1. There are many options **for protecting storm drain inlets**. Two commonly used options are filter fabric protection and catch basin inserts. *Filter fabric protection* (see Figure C.3.9.A) is filter fabric (geotextile) placed *over* the grate. This method is generally very ineffective and requires intense maintenance efforts. *Catch basin inserts* (see Figure C.3.9.B) are manufactured devices that nest inside a catch basin. This method also requires a high frequency of maintenance to be effective. Both options provide adequate protection, but filter fabric is likely to result in ponding of water above the catch basin, while the insert will not. Thus, filter fabric is only allowed where ponding will not be a traffic concern and where slope erosion will not result if the curb is overtopped by ponded water.

Trapping sediment in the catch basins is unlikely to improve the water quality of runoff if it is treated in a pond or trap because the coarse particles that are trapped at the catch basin settle out very quickly in the pond or trap. **Catch basin protection normally only improves water quality where there is no treatment facility downstream.** In these circumstances, catch basin protection is an important last line of defense. It is not, however, a substitute for preventing erosion.

The placement of filter fabric under grates is generally prohibited and the use of filter fabric over grates is strictly limited and discouraged.


2. It is sometimes possible to construct a small sump around the catch basin before final surfacing of the road. This is allowed because it can be a very effective method of sediment control.
3. Block and gravel filters, gravel and wire mesh filter barriers, and bag barriers filled with various filtering media placed around catch basins can be effective when the drainage area is 1 acre or less and flows do not exceed 0.5 cfs. It is necessary to allow for overtopping to prevent flooding. Many manufacturers have various inlet protection filters that are very effective in keeping sediment-laden water from entering the storm drainage system. The following are examples of a few common methods.
 - a) **Block and gravel filters** (Figure C.3.9.C) are a barrier formed around an inlet with standard concrete block and gravel, installed as follows:
 - Height is 1 to 2 feet above the inlet.
 - Recess the first row of blocks 2 inches into the ground for stability.
 - Support subsequent rows by placing a 2 x 4 through the concrete block opening.
 - Do not use mortar.
 - Lay some blocks in the bottom row on their side for dewatering the pooled water.
 - Place cloth or mesh with ½ inch openings over all block openings.
 - Place gravel below the top of blocks on slopes of 2:1 or flatter.
 - An alternate design is a gravel donut.
 - b) **Gravel and wire mesh filters** consist of a gravel barrier placed over the top of an inlet. This structure generally does not provide overflow. Install as follows:
 - Cloth or comparable wire mesh with ½ inch openings is placed over inlet.
 - Coarse aggregate covers the cloth or mesh.
 - Height/depth of gravel should be 1 foot or more, 18 inches wider than inlet on all sides.
 - c) **Curb inlet protection with a wooden weir** is a barrier formed around an inlet with a wooden frame and gravel, installed as follows:
 - Construct a frame and attach wire mesh (½ inch openings) and filter fabric to the frame.
 - Pile coarse washed aggregate against the wire/fabric.
 - Place weight on frame anchors.

- d) **Curb and gutter sediment barriers** (Figure C.3.9.D) consist of sandbags or rock berms (riprap and aggregate) 3 feet high and 3 feet wide in a horseshoe shape, installed as follows:
- Bags of either burlap or woven geotextile fabric, filled with a variety of media such as gravel, wood chips, compost or sand stacked tightly allows water to pond and allows sediment to separate from runoff.
 - Leave a “one bag gap” in the top row of the barrier to provide a spillway for overflow.
 - Construct a horseshoe shaped berm, faced with coarse aggregate if using riprap, 3 x 3 and at least 2 feet from the inlet.
 - Construct a horseshoe shaped sedimentation trap on the outside of the berm to sediment trap standards for protecting a culvert inlet.
4. **Excavated drop inlet sediment traps** are appropriate where relatively heavy flows are expected and overflow capability is needed. If emergency overflow is provided, additional end-of-pipe treatment may be required. Excavated drop inlets consist of an excavated impoundment area around a storm drain. Sediment settles out of the stormwater prior to enter the drain. Install according to the following specifications:
- a) The impoundment area should have a depth of 1 to 2 feet measured from the crest of the inlet structure.
 - b) Side slopes of the excavated area must be no steeper than 2:1.
 - c) Minimum volume of the excavated area should be 35 cubic yards.
 - d) Install provisions for draining the area to prevent standing water problems.
 - e) Keep the area clear of debris.
 - f) Weep holes may be drilled into the side of the inlet.
 - g) Protect weep holes with wire mesh and washed aggregate.
 - h) Weep holes must be sealed when removing and stabilizing excavated area.
 - i) A temporary dike may be necessary on the down slope side of the structure to prevent bypass flow.

Maintenance Standards


1. Any accumulated sediment on or around inlet protection shall be removed immediately. Sediment shall not be removed with water, and all sediment must be disposed of as fill on site or hauled off site.
2. Any sediment in the catch basin insert shall be removed when the sediment has filled one-third of the available storage. The filter media for the insert shall be cleaned or replaced at least monthly.
3. Regular maintenance is critical for all forms of catch basin/inlet protection. Unlike many forms of protection that fail gradually, catch basin protection will fail suddenly and completely if not maintained properly.

FIGURE C.3.9.A FILTER FABRIC PROTECTION



NOTE: ONLY TO BE USED WHERE PONDING OF WATER ABOVE THE CATCH BASIN WILL NOT CAUSE TRAFFIC PROBLEMS AND WHERE OVERFLOW WILL NOT RESULT IN EROSION OF SLOPES.


FIGURE C.3.9.B CATCH BASIN INSERT



NOTE: THIS DETAIL IS ONLY SCHEMATIC. ANY INSERT IS ALLOWED THAT HAS:

- A MIN. 0.5 C.F. OF STORAGE,
- THE MEANS TO DEWATER THE STORED SEDIMENT,
- AN OVERFLOW, AND
- CAN BE EASILY MAINTAINED.

FIGURE C.3.9.C BLOCK AND GRAVEL CURB INLET PROTECTION




NOTES:

1. USE BLOCK AND GRAVEL TYPE SEDIMENT BARRIER WHEN CURB INLET IS LOCATED IN GENTLY SLOPING SEGMENT, WHERE WATER CAN POND AND ALLOW SEDIMENT TO SEPARATE FROM RUNOFF.
2. BARRIER SHALL ALLOW FOR OVERFLOW FROM SEVERE STORM EVENT.
3. INSPECT BARRIERS AND REMOVE SEDIMENT AFTER EACH STORM EVENT. SEDIMENT AND GRAVEL MUST BE REMOVED FROM THE TRAVELED WAY IMMEDIATELY.

BLOCK AND GRAVEL CURB INLET PROTECTION
NTS

FIGURE C.3.9.D CURB AND GUTTER BARRIER PROTECTION



PLAN VIEW
NTS

NOTES:

1. PLACE CURB-TYPE SEDIMENT BARRIERS ON GENTLY SLOPING STREET SEGMENTS, WHERE WATER CAN POND AND ALLOW SEDIMENT TO SEPARATE FROM RUNOFF.
2. SANDBAGS OF EITHER BURLAP OR WOVEN GEOTEXTILE FABRIC ARE FILLED WITH GRAVEL, LAYERED AND PACKED TIGHTLY.
3. LEAVE A ONE-SANDBAG GAP IN THE TOP ROW TO PROVIDE A SPILLWAY FOR OVERFLOW.
4. INSPECT BARRIERS AND REMOVE SEDIMENT AFTER EACH STORM EVENT. SEDIMENT AND GRAVEL MUST BE REMOVED FROM THE TRAVELED WAY IMMEDIATELY.

CURB AND GUTTER BARRIER
NTS

C.3.10 SEEDING

Purpose

Seeding is intended to reduce erosion by stabilizing exposed soils. A well-established vegetative cover is one of the most effective methods of reducing erosion.

Conditions of Use

1. Seeding shall be used throughout the project on **disturbed areas** that have reached final grade or that will remain unworked for more than 30 days.
2. At the City's discretion, seeding without mulch during the **dry season** is allowed even though it will take more than seven days to develop an effective cover. Mulch is, however, recommended at all times because it protects seeds from heat, moisture loss, and transport due to runoff.
3. Prior to the beginning of the **wet season**, all disturbed areas shall be reviewed to identify which ones can be seeded in preparation for the winter rains. Disturbed areas shall be seeded within one week of the beginning of the wet season. A sketch map of those areas to be seeded and those areas to remain uncovered shall be submitted to the CED inspector. The CED inspector may require seeding of additional areas in order to protect surface waters, adjacent properties, or drainage facilities.
4. At final site stabilization, all disturbed areas not otherwise vegetated or stabilized shall be seeded and mulched.

Design and Installation Specifications

1. The best **time to seed** is fall (late September to October) or in spring (mid-March to June). **Irrigation** is required during the first summer following installation if seeding occurs in spring or summer or during prolonged dry times of year. Areas may also be seeded during the winter months, but it may take additional spring seeding applications to develop a dense groundcover due to cold temperatures. The application and maintenance of mulch is critical for winter seeding.
2. To prevent seed from being washed away, confirm that **all required surface water control measures** have been installed.
3. The **seedbed** should not be compacted because soils that are well compacted will not vegetate as quickly or thoroughly.
4. In general, 10-20-20 N-P-K (nitrogen-phosphorus-potassium) **fertilizer** may be used at a rate of 90 pounds per acre. Slow-release fertilizers are preferred because they are more efficient and have fewer environmental impacts. It is recommended that areas being seeded for final landscaping conduct soil tests to determine the exact type and quantity of fertilizer needed. This will prevent the over-application of fertilizer. Disturbed areas within 200 feet of water bodies and wetlands must use slow-release low-phosphorus fertilizer (typical proportions 3-1-2 N-P-K).
5. The following requirements apply to **mulching**:
 - a) Mulch is always required for seeding slopes greater than 3H:1V (see Section D.4.2.1).
 - b) If seeding during the wet season, mulch is required.
 - c) The use of mulch may be required during the dry season at the City's discretion if grass growth is expected to be slow, the soils are highly erodible due to soil type or gradient, there is a water body close to the disturbed area, or significant precipitation is anticipated before the grass will provide effective cover.
 - d) Mulch may be applied on top of the seed or simultaneously by hydroseeding.

6. **Hydroseeding** is allowed as long as tackifier is included. Hydroseeding with wood fiber mulch is adequate during the dry season. During the wet season, the application rate shall be doubled because the mulch and tackifier used in hydroseeding break down fairly rapidly.
7. Areas to be permanently landscaped shall use **soil amendments**. Good quality topsoil shall be tilled into the top six inches to reduce the need for fertilizer and improve the overall soil quality. Most native soils will require the addition of four inches of well-rotted compost to be tilled into the soil to provide a good quality topsoil. Compost used should meet specifications in Reference Section 11-C.
8. The **seed mixes** listed below in Table C.3.10.A and Table C.3.10.B include recommended mixes for both temporary and permanent seeding. These mixes, with the exception of the wetland mix, shall be applied at a rate of 80 to 100 seeds per square foot. Wet sites should apply 120 to 150 seeds per square foot. Local suppliers should be consulted for information on current Pure Live Seed (PLS) rates and species specific seeds per pound in order to determine seed mix PLS pounds of seed per acre. The appropriate mix depends on a variety of factors, including exposure, soil type, slope, and expected foot traffic. Alternative seed mixes approved by the City may be used.

TABLE C.3.10.A EROSION CONTROL SEED MIX

Common Name/Latin Name	% Species Composition	Desired Seeds per Square Foot	PLS pounds/Acre
Spike bentgrass <i>Agrostis exarata</i>	6	9	0.1
California brome/ <i>Bromus carinatus</i>	15	23	9.8
Tufted hairgrass/ <i>Deschampsia cespitosa</i>	15	23	0.4
Blue wildrye/ <i>Elymus glaucus</i>	18	27	10.7
California oatgrass/ <i>Danthonia californica</i>	18	27	5.6
Native red fescue/ <i>Festuca rubra</i> var. <i>rubra</i>	18	27	2.4
Meadow barley/ <i>Hordeum brachyantherum</i>	10	15	7.7

TABLE C.3.10.B LANDSCAPING SEED MIX

Common Name/Latin Name	% Species Composition	Desired Seeds per Square Foot	PLS pounds/Acre
Sideoats grama/ <i>Bouteloua curtipendula</i>	20	30	6.8
California oatgrass/ <i>Danthonia californica</i>	20	30	6.2
Native red fescue/ <i>Festuca rubra</i> var. <i>rubra</i>	30	45	3.9
Prairie junegrass/ <i>Koeleria macrantha</i>	30	45	0.8

Maintenance Standards for Seeding

1. Any seeded areas that fail to establish at least 80 percent cover within one month shall be reseeded. If reseeding is ineffective, an alternate method, such as sodding or nets/blankets, shall be used. If winter weather prevents adequate seed establishment and growth, this time limit may be relaxed at the discretion of the City when critical areas would otherwise be protected.
2. After adequate cover is achieved, any areas that experience erosion shall be re-seeded and protected by mulch. If the erosion problem is drainage related, the problem shall be fixed and the eroded area re-seeded and protected by mulch.
3. Seeded areas shall be supplied with adequate moisture, but not watered to the extent that it causes runoff.

C.3.11 SODDING

Purpose

The purpose of sodding is to establish permanent turf for immediate erosion protection and to stabilize drainage ways where concentrated overland flow will occur.

Conditions of Use

Sodding may be used in the following areas:

1. Disturbed areas that require short-term or long-term cover
2. Disturbed areas that require immediate vegetative cover

Design and Installation Specifications

Sod shall be free of weeds, of uniform thickness (approximately 1-inch thick), and shall have a dense root mat for mechanical strength.

The following steps are recommended for sod installation:

1. Shape and smooth the surface to final grade in accordance with the approved grading plan.
2. Amend two inches (minimum) of well-rotted compost into the top six inches of the soil if the organic content of the soil is less than ten percent. Compost used should meet specifications in Reference Section 11-C.
3. Fertilize according to the supplier's recommendations. Disturbed areas within 200 feet of water bodies and wetlands must use non-phosphorus fertilizer.
4. Work lime and fertilizer 1 to 2 inches into the soil, and smooth the surface.
5. Lay strips of sod beginning at the lowest area to be sodded and perpendicular to the direction of water flow. Wedge strips securely into place. Square the ends of each strip to provide for a close, tight fit. Stagger joints at least 12 inches. Staple on slopes steeper than 3H:1V.
6. Roll the sodded area and irrigate.
7. When sodding is carried out in alternating strips or other patterns, seed the areas between the sod immediately after sodding.

Maintenance Standards

If the grass is unhealthy, the cause shall be determined and appropriate action taken to reestablish a healthy groundcover. If it is impossible to establish a healthy groundcover due to frequent saturation, instability, or some other cause, the sod shall be removed, the area seeded with an appropriate mix, and protected with a net or blanket.

C.3.12 INTERCEPTOR DIKES AND SWALES

Purpose

Interceptor dikes and swales intercept storm runoff from drainage areas on or above disturbed slopes and convey it to a sediment pond or trap. They may also be used to intercept runoff from undisturbed areas and convey the runoff to a point below any exposed soils. Interception of surface water reduces the possibility of slope erosion. Interceptor dikes and swales differ from ditches in that they are intended to convey smaller flows along low-gradient drainage ways to larger conveyance systems such as ditches or pipe slope drains.

Conditions of Use

Interceptor dikes and swales are required in the following situations:

1. At the top of all slopes in excess of 3H:1V and with more than 20 feet of vertical relief.
2. At intervals on any slope that exceeds the dimensions specified in this section for the horizontal spacing of dikes and swales.

Design and Installation Specifications

1. See Figure C.3.12.A for details of an interceptor dike and Figure C.3.12.B for an interceptor swale.
2. Interceptor dikes and swales shall be **spaced horizontally** as follows:

Average Slope	Slope Percent	Flowpath Length
20H:1V or less	3–5%	300 feet
(10 to 20)H:1V	5–10%	200 feet
(4 to 10)H:1V	10–25%	100 feet
(2 to 4)H:1V	25–50%	50 feet

3. For slopes steeper than 2H:1V with more than 10 feet of vertical relief, **benches** may be constructed or closer spaced interceptor dikes or swales may be used. Whichever measure is chosen, the spacing and capacity of the measures must be designed by the engineer and the design must include provisions for effectively intercepting the high velocity runoff associated with steep slopes.
4. If the dike or swale intercepts runoff from **disturbed areas**, it shall discharge to a stable conveyance system that routes the runoff to a sediment pond or trap. If the dike or swale intercepts runoff that originates from **undisturbed areas**, it shall discharge to a stable conveyance system that routes the runoff downslope of any disturbed areas and releases the water at a stabilized outlet.
5. **Construction traffic** over temporary dikes and swales shall be minimized.

Maintenance Standards

1. Damage resulting from runoff or construction activity shall be repaired immediately.
2. If the facilities do not regularly retain storm runoff, the capacity and/or frequency of the dikes/swales shall be increased.

FIGURE C.3.12.A INTERCEPTOR DIKE





FIGURE C.3.12.B INTERCEPTOR SWALE



C.3.13 DITCHES

Purpose

Ditches intercept and convey runoff from disturbed areas to sediment control locations. They also convey runoff intercepted from undisturbed areas around the construction site to a non-erosive discharge point.

Conditions of Use

Ditches may be used anywhere that concentrated runoff is to be conveyed on or around the construction site. Temporary pipe systems may also be used to convey runoff.



Design and Installation Specifications

1. Up to 30,000 square feet may be drained by a 12-inch deep trapezoidal ditch with a 1-foot bottom width. Up to 2 acres may be drained by an 18-inch deep trapezoidal ditch with a 1-foot bottom width. Ditches draining larger areas will need to be sized by a *civil engineer*.
2. Ditch side slopes shall be no steeper than 2H:1V.
3. Ditches on 5% or steeper grades shall be armored with rip rap or contain crushed rock check dams spaced such that the crest of each dam is even with the toe of the next upstream dam. See Figure C.3.13.A for details on check dam installation.

Maintenance Standards

1. Any sediment deposition of more than 0.5 feet shall be removed so that the channel is restored to its design capacity.
2. If the channel capacity is insufficient for the design flow, it must be determined whether the problem is local (e.g., a constriction or bend) or the channel is under-designed. If the problem is local, the channel capacity must be increased through construction of a berm(s) or by excavation. If the problem is under-design, the design engineer shall be notified and the channel redesigned to a more conservative standard to be approved by the City.
3. The channel shall be examined for signs of scouring and erosion of the bed and banks. If scouring or erosion has occurred, affected areas shall be protected by riprap or an erosion control blanket or net.

FIGURE C.3.13.A CHECK DAMS



C.3.14 PIPE SLOPE DRAIN

Purpose

Pipe slope drains are designed to carry concentrated runoff down steep slopes without causing erosion, or saturation of slide-prone soils. Pipe slope drains may be used to divert water away from or over bare soil to prevent gullies, channel erosion, and saturation of slide prone soils

Conditions of Use

Pipe slope drains should be used when a temporary or permanent stormwater conveyance is needed to move water down a steep slope to avoid erosion. Pipe slope drains may be:

1. Used on any slope with a gradient of 2H:1V or greater and with at least 10 feet of vertical relief.
2. Used to drain water collected from aquifers exposed on cut slopes and convey it to the base of the slope.
3. Used to collect clean runoff from plastic sheet cover and direct away from any exposed soils.
4. Installed in conjunction with silt fence to drain collected water to a controlled area.


Design and Installation Specifications

1. See Figure C.3.14.A for details.
2. Up to 30,000 square feet may be drained by each 6-inch minimum diameter pipe. Up to 2 acres may be drained by each 12-inch minimum diameter pipe.
3. The **maximum drainage area** allowed for any 12-inch pipe is 2 acres. For larger areas, more than one pipe shall be used.
4. The **soil** around and under the pipe and entrance section shall be thoroughly compacted.
5. The **flared inlet section** shall be securely connected to the slope drain and be fused or welded, or have flange-bolted mechanical joints to ensure a watertight seal. Ensure that the entrance area is stable and large enough to direct flow into the pipe.
6. Slope drains shall be continuously fused, welded, or flange-bolted mechanical joint pipe systems with proper anchoring to the soil.
7. Re-establish cover immediately on areas disturbed by the installation.

Maintenance Standards

1. The inlet shall not be undercut or bypassed by water. If there are problems, the head wall shall be appropriately reinforced.
2. No erosion shall occur at the outlet point. If erosion occurs, additional protection shall be added.

FIGURE C.3.14.A PIPE SLOPE DRAIN



C.3.15 DEWATERING CONTROL

Purpose

To prevent the untreated discharge of sediment-laden water from dewatering of utility trenches, excavated areas, foundations, etc.

Conditions of Use

Dewatering control measures shall be used whenever there is a potential for runoff from dewatering of utility trenches, excavations, foundations, etc.

Design Specifications

1. Foundation, vault, excavation, and trench dewatering water that has similar characteristics to stormwater runoff at the site shall be discharged into a controlled conveyance system prior to discharge to a sediment trap or sediment pond. Foundation and trench dewatering water **that has similar characteristics to stormwater runoff** at the site, must be disposed of through one of the following options depending on site constraints:
 - a) Infiltration,
 - b) Transport offsite in a vehicle, such as a vacuum flush truck, for legal disposal in a manner that does not pollute surface waters,
 - c) Discharge to the sanitary sewer discharge with approval from King County and the City of Renton if there is no other option, or
 - d) Use of a sedimentation bag with outfall to a ditch or swale for small volumes of localized dewatering.
2. Clean, non-turbid dewatering water, such as well-point ground water, may be discharged via stable conveyance to systems tributary to surface waters, provided the dewatering flow does not cause erosion or flooding of receiving waters.
3. **Highly turbid or contaminated dewatering water shall be handled separately** from stormwater.

C.3.16 CONTROL OF OTHER POLLUTANTS (SWPPS)

Purpose

To prevent the discharge of pollutants resulting from construction activities.

SWPPS measures **are not modified** for Simplified sites; however, the scope and complexity may be lessened in accordance with the scope of the Simplified site project. Construction activity shall not allow pollutant discharge to surface waters or water resources. The measures listed below provide summary guidance on typical issues and associated BMPs. See Section D.2.2 in Appendix D for additional SWPPS information.

The **Small Site CSWPP plan** is not complete if this section is not included in the planning and implementation of CSWPP for the Simplified Site project.

Application

Pollution control measures shall be used whenever there is a potential for the discharge to ground or surface water of any pollutants used on the site.

Pollution Control Measures

The following pollution control measures shall be implemented as applicable using activity-specific BMPs detailed in SWDM Appendix D (*CWSPP Standards*) and the King County *Stormwater Pollution Prevention Manual (SPPM)*:

1. All pollutants, including waste materials, that occur onsite shall be handled and disposed of in a manner that does not cause contamination of stormwater. See Section D.2.2 in the *CWSPP Standards* and *SPPM* Activity Sheets A-8, A-11, A-12, A-16, A-17, A-22, A-29, A-38, and A-41.
2. Cover, containment, and protection from vandalism shall be provided for all chemicals, liquid products, petroleum products, and non-inert wastes present on the site (see Chapter 173-304 WAC for the definition of inert waste). Onsite fueling tanks shall include secondary containment. See Section D.2.2 in the *CWSPP Standards* and *SPPM* Activity Sheets A-2, A-3, A-4, A-6, A-8, and A-9.
3. Maintenance and repair of heavy equipment and vehicles involving oil changes, hydraulic system drain down, solvent and de-greasing cleaning operations, fuel tank drain down and removal, and other activities which may result in discharge or spillage of pollutants to the ground or into stormwater runoff must be conducted using spill prevention measures, such as drip pans. Contaminated surfaces shall be cleaned immediately following any discharge or spill incident. Emergency repairs may be performed onsite using temporary plastic placed beneath and, if raining, over the vehicle. See Section D.2.2 in the *CWSPP Standards* and *SPPM* Activity Sheets A-13, A-17, and A-18.
4. Application of agricultural chemicals, including fertilizers and pesticides, shall be conducted in a manner and at application rates that will not result in loss of chemical to stormwater runoff. Manufacturers' recommendations for application rates and procedures shall be followed. See Section D.2.2 in the *CWSPP Standards* and *SPPM* Activity Sheets A-5, A-25, and A-26.
5. Measures shall be used to prevent or treat contamination of stormwater runoff by pH modifying sources. These sources include, but are not limited to, bulk cement, cement kiln dust, fly ash, new concrete washing and curing waters, waste streams generated from concrete grinding and sawing, exposed aggregate processes, and concrete pumping and mixer washout waters. Stormwater discharges shall not cause or contribute to a violation of the water quality standard for pH in the receiving water. See Section D.2.2 in the *CWSPP Standards* and *SPPM* Activity Sheets A-19, A-20, A-29, A-43, and A-44.
6. For full compliance with RMC 4-6-030 Drainage (Surface Water) Standards, the project may need to include measures for the permanent structures and features constructed under associated permits (e.g., permanent canopy requirement for permanent outdoor vehicle maintenance areas constructed under a building permit). See the *SPPM* for Activity Sheets describing issues and measures to address them. Common issues include:
 - Containment area planning for storage of liquid materials in stationary or portable tanks, storage of solid waste and food wastes including cooking grease, and to avoid pollutant spills to surface waters. See *SPPM* Activity Sheets A-2, A-3, A-7, and A-8.
 - Permanent canopy and paving requirements for permanent outdoor vehicle parking, maintenance and storage areas, and manufacturing or processing associated with metal products. See *SPPM* BMP Information Sheets #3 and #4 and Activity Sheets A-21 and A-31.

(This page intentionally left blank.)

C.4 SIMPLIFIED DRAINAGE PLAN SPECIFICATIONS

This section presents the specifications of drainage plans and supporting documentation that must be submitted for projects in Simplified Drainage Review. See Section C.1.5 for a complete list of items that must be submitted. See Reference Section C.5.1 in this appendix for a description of the Simplified Drainage Review Process.

Organization of Section C.4

This section is organized as follows:

- Section C.4.1, “Components of Simplified Drainage Plans”
- Section C.4.2, “Specifications for Site Plans”
- Section C.4.3, “BMP Design and Maintenance Details”
- Section C.4.4, “Written Drainage Assessment”

C.4.1 COMPONENTS OF SIMPLIFIED DRAINAGE PLANS

Unless otherwise directed by CED, Simplified Drainage Plans **for projects on individual sites/lots** typically include a site plan, on-site BMP design and maintenance details, a **Small Site CSWPP plan**, and a written drainage assessment as described and illustrated in this section. If the project is a **subdivision**, a site improvement plan is typically required; but if on-site BMPs are proposed to be installed by the subdivision project on the individual lots, a site plan may substitute for the site improvement plan as allowed by CED. This should be determined in a preapplication meeting with CED.

*Note: if there are any **site** conditions or drainage issues that must be addressed by a **civil engineer** as determined by CED, an engineering plan as described in Chapter 2 of the SWDM will be required in addition to the Simplified Drainage Plan.*

C.4.1.1 COMPONENTS REQUIRED FOR INDIVIDUAL LOT PROJECTS

Most of the information required for the **Simplified Drainage Plan** is also required for a residential site plan, which must be submitted with the permit application (see CED Residential Building Permit Drainage Review Checklist). In fact, the residential site plan may be used as a base map for the site plan and **Small Site CSWPP plan** components of the **Simplified Drainage Plan**.

Required components for all individual lot projects are as follows:

1. **Site Plan.** This is a scale drawing of the individual **site/lot** used to show how required on-site BMPs will be applied to the **target impervious surface** and **new pervious surface** proposed on the **site/lot**. The site plan is intended to be a recordable document (or reducible to a recordable document) that can be attached to the declaration of covenant and grant of easement required for implementation of on-site BMPs on individual **sites/lots**. CED may allow a written version of this plan if they determine there is no need to illustrate the size and location of proposed on-site BMPs.
2. **On-site BMP Design and Maintenance Details** (required whenever on-site BMPs are proposed by a project). These are diagrams/figures, design specifications, and maintenance instructions for each on-site BMP proposed. On-site BMP design and maintenance details are intended to be recordable to facilitate attachment to the declaration of covenant and grant of easement required for implementation of on-site BMPs on individual **sites/lots**. CED may waive all or a portion of this component if they determine there is no need to specify design details or maintenance instructions for certain proposed BMPs (e.g., the reduced footprint BMP).
3. **Small Site CSWPP Plan.** This is a scale drawing of the **site** or **project site** used to show the limits of disturbance by the project and how required ESC measures will be applied to prevent sediment from

leaving the *project site*. Additionally, the plan identifies construction activities requiring SWPPS measures and how these measures will be applied. The plan must include or be accompanied by any necessary standard details for installation of proposed ESC and SWPPS measures. The figures in Section C.3 may be used as details. CED may allow a written version of this plan if they determine there is no need to illustrate the extent and location of proposed ESC and SWPPS measures.

Note: if the project proposes to disturb 1 or more acre, a CSWPP plan prepared by a civil engineer will be required in accordance with the City's CSWPP Standards (Appendix D of the SWDM).

4. **Written Drainage Assessment.**¹⁹ This is an overview of the proposed project and its compliance with the drainage requirements of this appendix. It includes a description of proposed *site* improvements, existing *site* conditions, critical areas, existing drainage features, proposed on-site BMPs, and ESC and SWPPS measures, including how they were selected and sized. The drainage assessment should also discuss the results and implications of any soils reports or special studies completed for the *site*.

C.4.1.2 COMPONENTS REQUIRED FOR SUBDIVISION PROJECTS

The components required for a subdivision project depend on whether on-site BMPs are proposed to be installed as part of the project as described below.

A. NO ON-SITE BMPS PROPOSED

1. **Site Improvement Plan.** This is a scale drawing of the *site* used to show the proposed lot layout, building restrictions, road and drainage improvements, and any measures necessary to mitigate the stormwater impacts of road improvements.
2. **Small Site CSWPP Plan.** Same as for individual lot projects in Section C.4.1.1.
3. **Written Drainage Assessment.** Same as for individual lot projects in Section C.4.1.1.

B. ON-SITE BMPS PROPOSED

1. **Site Plan** (required for each lot). This is a scale drawing of each lot used to show how required on-site BMPs will be applied to the **future anticipated target impervious surface** and **new pervious surface** on the *site/lot*. All other aspects of this plan are the same as for individual lot projects in Section C.4.1.1.
2. **On-site BMP Design and Maintenance Details** (required for each lot). Same as for individual lot projects in Section C.4.1.1.
3. **Site Improvement Plan.** May be waived by CED if they determine the site plan and design details are an adequate substitute or if no road or drainage improvements are proposed.
4. **Small Site CSWPP Plan.** Same as for individual lot projects in Section C.4.1.1.
5. **Written Drainage Assessment.** Same as for individual lot projects in Section C.4.1.1.

¹⁹ If engineering plans are required, the information requested in the written drainage assessment should be incorporated in the technical information report.

C.4.2 SPECIFICATIONS FOR SITE PLANS

Site plans, subdivision site improvement plans, and **Small Site CSWPP plans** are drawings of the entire *site* that contains the project. They should be drawn on 8½" x 11", 8½" x 14", or 11" x 17" paper, although the applicant is advised to draw **site plans** on 8½" x 11" or 8½" x 14" paper with 1-inch margins so they can be directly recorded as attachments to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4.

Site plans for projects in Simplified Drainage Review must include the information specified in the following subsections.

C.4.2.1 GENERAL INFORMATION

The following information must be included on **all** site plans, subdivision site improvement plans, and **Small Site CSWPP plans**, unless otherwise directed by CED:

Identification

- Name, address, and phone number of applicant
- Parcel number
- Dimension of all property lines, easements, and building setback lines
- Street names and existing or proposed property address
- Section, township, and range of proposal.
- North arrow
- Legend if needed
- **Scale**—use a scale that clearly illustrates drainage features and BMPs/measures (1" = 20' is standard scale; minimum acceptable scale is 1" = 50'). If necessary, split the *site* plan into two or more plan sheets and indicate a "match line" on each sheet to show how the sheets splice together. A variation of this approach is to use separate scales for the *project site* versus the entire *site* and draw them on separate plan sheets.

Building and Site Development Features

- Footprint of all structures (existing and proposed)
- Parking, roads, and driveways (existing and proposed)
- Sport courts and any other paved or impervious surfaces (existing and proposed)
- Pervious surface land cover (existing and proposed)
- Location of any retaining walls and rockeries (existing and proposed)
- Existing or proposed septic system, including all system components and both primary and reserve drainfields
- Utility structures (poles, fire hydrants, etc.)
- Existing wells or wells to be abandoned.

Topography

- Corner elevations of the *site/lot*
- Benchmark (a permanent mark indicating elevation and serving as a reference in the topographic survey)
- Datum [assumed datum is acceptable in many cases (i.e., fire hydrant base = 100'); datum for projects in or near FEMA floodplain should be per the relevant Flood Insurance Rate Map (FIRM) (typically NGVD 1929, or NAVD 1988 on many recently updated maps, see <https://msc.fema.gov/portal/search?AddressQuery=7732%2020th%20ave%20nw%2C%20seattle%20wa%2098117>>). Datum for projects in or near unmapped floodplain shall use NAVD 1988.]

- Show 5-foot contours for all slopes steeper than 15% and delineate the top and bottom of these slopes
- For *sites/lots* that are 22,000 square feet and larger, show 2-foot or 5-foot contours as needed to design and demonstrate compliance with the minimum design requirements and specifications for proposed on-site BMPs and ESC and SWPPS measures.

Drainage Features and Critical Areas

- Location of all existing and proposed ditches, swales, pipes, etc.
- Delineation of all streams, wetlands, lakes, closed depressions, or other water features (including any required buffer widths)
- Delineation of all flood hazard areas, *erosion hazard areas*, *steep slope hazard areas*, *landslide hazards*, and their buffers and building setback lines
- Delineation of all drainage easements, tracts, and right-of-way
- Delineation of all critical areas as shown on any recorded critical areas notice on title

C.4.2.2 INFORMATION SPECIFIC TO ON-SITE BMPS

In addition to the general information required in Section C.4.2.1, the following additional information is required on site plans and on subdivision site improvement plans that include installation of on-site BMPs within a dedicated tract or road right-of-way:

- Location and dimensions of on-site BMP devices such as dispersion trenches, infiltration trenches, drywells, ground surface depressions, bioretention, permeable pavements, rain water storage tanks, and perforated pipe connections
- Delineation and dimensions of target impervious surface and new pervious surface
- Delineation and dimensions of vegetated flowpath segments if applicable
- Delineation of native vegetated surface to be created and preserved
- Setback lengths between on-site BMPs and any property line, structure, steep slope, stream, wetland, or septic system

C.4.2.3 INFORMATION SPECIFIC TO SMALL SITE CSWPP PLANS

In addition to the general information required in Section C.4.2.1, the following additional information is required on **Small Site CSWPP plans**, unless otherwise directed by CED:

- Delineation of proposed **clearing limits** (i.e., area to be disturbed)
- Type and location of ESC and SWPPS measures
- Notes indicating the location of any **significant offsite drainage features** within 200 feet of the discharge point(s) for the *site/lot*, including streams, lakes, roadside ditches, etc.

C.4.2.4 EXAMPLE SITE PLANS

Presented in this section is an example of a **site plan** (Figure C.4.2.A) and a **Small Site CSWPP plan** (Figure C.4.2.B) for construction of a single family residence.

FIGURE C.4.2.A SINGLE FAMILY RESIDENCE – SITE PLAN

LEGEND:

PROPERTY LINE	---
ST. CENTERLINE	---
CONTOUR	---
WETLAND	
STEEP SLOPE (40%+)	
OFFSITE DRAINAGE	→

APPLICANT: Malene McResident
 600 NE Z Street
 Sometown, WA. 98111
 (206) 555-1212

PROJECT PARCEL NO.= 322708
 PROJECT ADDRESS= 7519 NE Q Street
 (proposed) Sometown, WA. 98111
 SECTION/TOWNSHIP/RANGE: 32-27-08

TOTAL SITE ACREAGE: 1.69
 TOTAL IMPERVIOUS AREA: 6950 SQ. FT.





FIGURE C.4.2.B SINGLE FAMILY RESIDENCE – SMALL SITE CSWPP PLAN

LEGEND:


- PROPERTY LINE ————
- ST. CENTERLINE ————
- CONTOUR ————
- WETLAND 
- STEEP SLOPE (40%+) 
- OFFSITE DRAINAGE 
- S.A.S.B. = SENSITIVE AREA SETBACK

APPLICANT: Malene McResident
 600 NE Z Street
 Sometown, WA. 98111
 (206) 555-1212

PROJECT PARCEL NO.= 322708
 PROJECT ADDRESS= 7519 NE Q Street
 (proposed) Sometown, WA. 98111
 SECTION/TOWNSHIP/RANGE: 32-27-08

TOTAL SITE ACREAGE: 1.69
 TOTAL IMPERVIOUS AREA: 6950 SQ. FT.

CSWPP/ESC CONTACT:
 Malene McResident (206) 555-1212
 DISTURBED ACREAGE: APPROX. 0.9




 SCALE: 1"=40'

C.4.3 BMP DESIGN AND MAINTENANCE DETAILS

For each on-site BMP shown on a site plan or in the right-of-way or tract of a subdivision site improvement plan, design details and maintenance instructions must be provided to clarify the design, installation, and long term maintenance and operation of the BMP. See the City of Renton Standard Details and the maintenance instructions in Reference Section 8-M.

C.4.3.1 DESIGN DETAILS

Design details are typically diagrams with notes that show a close-up view and/or cross-section of the BMP device and provide dimensions and specifications of size, placement, materials, components, downstream vegetation requirements, etc. Although diagrams are typical, there are many BMP devices (e.g., rock pads) for which only written details and specifications are more than sufficient. For some BMPs, design details may not be needed at all (e.g., the reduced footprint BMP).

Design details should be displayed on 8½" x 11" or 8½" x 14" paper with 1-inch margins so they can be directly recorded as attachments to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. No scale is required for the diagrams used. The design details for each on-site BMP may be combined with its maintenance instructions on the same sheet or multiple sheets. Design details may also be placed on the site plan if there is room. To be recordable, however, the font size must be no less than 8-pt.

The BMP-specific figures and minimum design specifications presented in Section C.2 can be used to prepare the design details for a specific application of an on-site BMP to a particular *site*/project. Also, the City of Renton Surface Water Utility's *Surface Water Design Manual* website contains downloadable, electronic versions of these and other figures/design specifications that can be adapted to a *site*/project as well. The 2005 *Puget Sound Low Impact Development Manual* is yet another source of figures and design specifications. If a **proprietary version** of an on-site BMP is used, the manufacturer or installer will usually provide a diagram and *site*-specific design specifications.

C.4.3.2 MAINTENANCE INSTRUCTIONS

Maintenance instructions are intended to explain to future property owners, the purpose of each on-site BMP and how it must be maintained and operated. A set of **minimum** maintenance instructions is provided for each on-site BMP is included in Reference Section 8-M. Updated maintenance instructions will be posted on the City of Renton's *Surface Water Design Manual* website. If a **proprietary facility** is used, system-specific maintenance instructions from the manufacturer or installer must be included.

Maintenance instructions should be displayed on 8½" x 11" or 8½" x 14" paper with 1-inch margins so they can be directly recorded as attachments to the required **declaration of covenant and grant of easement** per Requirement 3 of Section C.1.3.4. Instructions prepared in this format are located in Reference Section 8-M. The maintenance instructions for each on-site BMP may be combined with its design details on the same sheet or multiple sheets. Maintenance instructions may also be placed on the site plan if there is room. To be recordable, however, the font size must be no less than 8-pt.

C.4.4 WRITTEN DRAINAGE ASSESSMENT

The written drainage assessment is a supporting document of the Simplified Drainage Plan and typically includes the following information:

- A **narrative** description of proposed project
- Any proposed **changes** to the project after preliminary approval
- A description of **proposed on-site BMPs** shown on the site plan and how they were selected.
- Supporting documentation (e.g., soil tests, infiltration rates, geotechnical recommendations, etc.) where BMPs were not selected based upon determinations of infeasibility
- A description of **proposed ESC and SWPPS measures** shown or noted on the plans and how they were selected
- A description of any necessary **special studies** or **soils reports**
- A description of any **other information** required by CED

C.4.4.1 EXAMPLE ASSESSMENT FOR A SINGLE FAMILY RESIDENCE

The purpose of this section is to illustrate the application of simplified drainage requirements to a house being built on an existing lot. The site plan for this example is shown in Figure C.4.2.A, and the **Small Site CSWPP plan** is shown in Figure C.4.2.B. Although the example was written for an existing lot in King County, the level of detail included is an example of what could be used for a single lot in the City of Renton. The written drainage assessment is as follows:

Drainage Assessment

Malene McResident Residence

7519 NE Q Street

Permit # B05R7184

The project is located east of Duvall on a 1.69-acre lot that is zoned RA. The lot is mostly forested with a wetland on the northeast corner of the property. The lot slopes down from Q Street on the south to P Street on the north. The slope on the south portion of the property is 6-14%. The house and its septic drainfields are proposed on the southern portion of the lot. The driveway will be approximately 10 feet by 120 feet (1,200 square feet) of impervious surface, the parking area 1,200 square feet, and the house 3,750 square feet. The total proposed impervious surface is 6,150 square feet. The total proposed clearing for the house, yard, drainfield areas, and driveway is 0.84 acres.

The wetland is a Category III wetland with a minimum required buffer width of 60 feet as determined in the preapplication meeting with CED. By definition, the wetland is also a flood hazard area for which a floodplain and base flood elevation must be determined. Subject to CED review and approval, an approximate base flood elevation of 452 has been estimated based on a downstream overflow elevation of 450 (see attached notes from the project's land surveyor). This elevation is well below the proposed house and driveway location.

The portion of the lot that is on a 40-50% slope is a steep slope hazard area as determined in the preapplication meeting with CED. A 15-foot building setback as shown on the on-site BMP plan is required. Dispersion and infiltrative BMPs are not allowed within 200 feet of a steep slope hazard area without approval by a geotechnical engineer unless approved by the CED. The CED determined that dispersing of the roof runoff toward the steep slope was acceptable, as shown on the plan.

Because the lot is larger than 22,000 square feet, it is subject to the Large Lot BMP Requirements in Appendix C of the *Surface Water Design Manual*. As mandated by these requirements, all proposed impervious surface (6,150 square feet) is targeted for application of on-site BMPs. As for new pervious surface (totaling 30,440 square feet), it is less than 3/4 acre; therefore, no on-site BMPs are required for this surface beyond the requirement that the existing native topsoil be retained to the

maximum extent practicable. Soil amendments will be provided to mitigate for lost moisture holding capacity where compaction or removal of underlying topsoil occurs.

To address the requirements for mitigation of target impervious surface, the applicability and feasibility of full dispersion was considered first. After subtracting out the wetland and the portion of the lot that may be cleared, about 34,000 square feet of the lot will remain as unsubmerged native vegetated surface. This means that full dispersion could be applicable to up to 5,100 square feet of the target impervious surface (15% of 34,000). However, because of the lot's topography and the location of proposed clearing, there is no way to achieve the minimum required 100 feet of native vegetated flowpath segment that has a slope of 15% or flatter. Therefore, full dispersion is not feasible.

Full infiltration of roof runoff was considered next. According to the attached soils report for the septic system design, the soil on the project site is a sandy loam underlain by dense glacial till. Therefore, full infiltration is not applicable. Permeable pavement was considered for the driveway and parking area, but the geotechnical report recommended against this since the underlying soils do not have properties considered adequate to protect groundwater. This allowed for selection of basic dispersion as the on-site BMP of choice for application to the target impervious surfaces of this project.

To implement basic dispersion, the roof downspouts of the proposed house will discharge via splash blocks to minimum 50-foot vegetated flowpath segments located on slopes no steeper than 15% as shown on the site plan. No more than 700 square feet of roof area will discharge to any one splash block and vegetated flowpath segment. All of the flowpaths will be downslope of septic tank and drainfields.

The northern portion of the driveway will be discharged via sheet flow over a 10-foot vegetated flowpath segment to the north, as shown on the site plan. Runoff from approximately 700 square feet of the southern portion of the driveway will be collected by a rock-lined ditch and a concrete driveway berm and discharged to a 12-foot-long dispersion trench with notch board and then over a 25-foot vegetated flowpath segment toward the north. The 30-foot wide parking area will be discharged via sheet flow over a 2-foot-wide crushed rock strip and a vegetated flowpath segment of 15 feet as shown on the site plan.

In order to prevent erosion and trap sediments within the project site, the following BMPs will be used approximately as shown in the ESC details on the CSWPP plan:

- Clearing limits will be marked by fencing or other means on the ground.
- The driveway will be constructed and graveled immediately. A rock construction entrance will be placed at the end of the driveway. Dispersion trenches will be placed according to flow control requirements. Cleared areas accepting sheet flow from the driveway and parking area will be seeded and mulched.
- Runoff will not be allowed to concentrate and no water will be allowed to point discharge onto the slopes.
- Silt fencing will be placed along slope contours at the downslope limit of clearing.
- Mulch will be spread over all cleared areas of the site when they are not being worked. Mulch will consist of air-dried straw and chipped site vegetation.

(This page intentionally left blank.)

C.5 REFERENCE SECTION

This section contains background and supplemental information on the **Simplified Drainage Review process** and an example **declaration of covenant and grant of easement** required for individual lot developments. The materials in this section are for reference only and may be updated over time. For the latest versions of these materials, see the City of Renton's *Surface Water Design Manual* website.

C.5.1 SIMPLIFIED DRAINAGE REVIEW PROCESS

Drainage review, when required, is one of several reviews conducted by the CED as part of its review process for City development permits and approvals. The process used for drainage review depends largely on the permit review process already established for different types of developments (e.g., subdivision, single family residence, or commercial building). For projects in Simplified Drainage Review, the review process primarily depends on whether the project is a proposed short plat or just proposed *site* improvements to an existing parcel or combination of parcels (individual lot project). Below is a description of the Simplified Drainage Review process for each of these development types.

C.5.1.1 INDIVIDUAL LOT PROJECTS

This section describes the Simplified Drainage Review process for *single family residential projects* that apply for a permit or approval to make specific *site* improvements such as construction of buildings, additions, driveways, or other impervious surfaces, or clearing of native vegetation.

When a permit/approval for a *single family residential project* requires drainage review as specified in the *SWDM*, CED staff plot the project location on various maps (Assessor's, Kroll, topography, soils, etc.), research critical areas on or near the *site*, and check for adopted area-specific conditions that might affect the drainage requirements for the *site*. CED reviews this information with respect to the proposed application. In most cases, a visit to the *site* is made to check existing conditions and drainage concerns.

CED makes a determination of the type of drainage review required for the project and will either:

- Request additional information as needed,
- Request that a Simplified Drainage Plan (see Section C.4) be submitted,
- Determine the project is subject to Directed Drainage Review as described in Chapter 1 of the *SWDM*, request additional information as needed, specify which core and special requirements are applicable to the project, and specify the corresponding applicable drainage plan submittal requirements,
- Request that an engineered drainage plan be submitted in accordance with Chapter 2 of the *SWDM*,
OR
- Approve the permit subject to complying with an approved Simplified Drainage Plan or engineered drainage plan,
- Deny the permit application because it cannot meet required codes (e.g., a proposed new residence located in a FEMA floodway).

C.5.1.2 SUBDIVISION PROJECTS

For *single family residential projects* that are subdivisions, the Simplified Drainage Review process generally includes the following elements:

Pre-Application Submittal

A pre-application meeting is recommended for short plats prior to formal submittal. The purpose of the pre-application meeting is to identify potential *site* constraints and regulatory requirements for the

proposed project. If the short plat is subject to Simplified Drainage Review, the applicant may use this appendix or other information necessary to complete the Simplified Drainage Plan.

If the drainage requirements for a specific short plat are determined during a pre-application meeting, Simplified Drainage Plans (see Section C.4) may be submitted with the application. Section C.1.1 contains a series of questions that may help assess the requirements for a potential Simplified Drainage Plan submittal. Submitting plans with the short plat permit application may expedite the review of the proposed application. However, there is risk that the plans prepared may exceed, or not adequately address, the yet-to-be-determined conditions of preliminary approval.

Preliminary Approval

After formal permit application, a more detailed review of the *site* and a determination of the type of drainage review required for the proposed subdivision are made. If subject to Simplified Drainage Review, the application may be placed on hold pending the completion of a Simplified Drainage Plan.

The applicant is responsible for submitting a Simplified Drainage Plan as detailed in Section C.4. Upon completion and approval of the Simplified Drainage Plan (and other application requirements), preliminary approval may be granted, subject to the conditions of the Simplified Drainage Plan. For simple short plats that have no drainage issues triggering Targeted Drainage Review, engineered drainage plans are not usually required.

For proposed short plats requiring some engineering analysis, preliminary approval may be granted subject to the approval of engineering plans and a Simplified Drainage Plan. The applicant may choose to have the Simplified Drainage Plan incorporated into the engineered plans (prepared by a *civil engineer*) or may elect to have a separate Simplified Drainage Plan that is not prepared by an engineer.

Proposed short plats that are subject to Simplified Drainage Review but cannot comply with the Simplified drainage requirements will be subject to Full Drainage Review. Any proposed short plats unable to comply with all applicable regulations (drainage or non-drainage) may be denied.

Engineering Review

Short plats receiving preliminary approval subject to the completion of a Simplified Drainage Plan and/or engineering plans are subject to engineering review. When separate plans are being prepared, submittals for engineering review should include both sets of plans to minimize review time and re-submittal fees.

Final Recording

All short plat applications must complete the requirements of final recording. Simplified projects may require additional note(s) be placed on the recorded documents that reference the approved Simplified Drainage Plan for future lot construction.

Note: Future building permit applications that do not comply with the conditions of the approved Simplified Drainage Plan (e.g., impervious coverage limits, location of BMPs, etc.) may be subject to Full Drainage Review.

C.5.1.3 CHANGES FROM THE ORIGINAL APPROVED PLAN

Approval of Simplified Drainage Plans is based on a specific proposed project. Changes from the original approved Simplified Drainage Plan (e.g., additional impervious surface or clearing, right-of-way improvements) may require additional review by CED staff, or they may initiate Full Drainage Review, where a *civil engineer* must analyze the project and submit engineering plans. This will add additional review time and expense to the review process.

Changes proposed prior to permit issuance must be submitted through the standard revision process for the type of application.

Changes proposed after permit issuance (during construction) must be submitted through CED. Proposed changes shall not be implemented prior to CED approval. Changes performed without engineering approval may be subject to Stop Work notices and accompanying fees and reviews.

C.5.2 DECLARATION OF COVENANT

A declaration of covenant may be used to achieve the objectives specified in Requirement 3 of Section C.1.3.4. The completed covenant must be reviewed and approved by CED prior to recording. When preparing any form that grants an interest in real property, applicants are encouraged to seek legal advice from a professional qualified in real estate matters. The declaration of covenant can be found on the City of Renton's Surface Water Design Standards web site:
<<http://rentonwa.gov/government/default.aspx?id=7122>>

(This page intentionally left blank.)